
Hands-on Python Tutorial

Release 2.0

Dr. Andrew N. Harrington

May 25, 2020

1	Beginning With Python	3
1.1	Context	3
1.2	The Python Interpreter and Idle, Part I	7
1.3	Whirlwind Introduction To Types and Functions	13
1.4	Integer Arithmetic	14
1.5	Strings, Part I	17
1.6	Variables and Assignment	18
1.7	Print Function, Part I	21
1.8	Strings Part II	21
1.9	The Idle Editor and Execution	22
1.10	Input and Output	25
1.11	Defining Functions of your Own	30
1.12	Dictionaries	42
1.13	Loops and Sequences	47
1.14	Decimals, Floats, and Floating Point Arithmetic	61
1.15	Summary	64
2	Objects and Methods	73
2.1	Strings, Part III	73
2.2	More Classes and Methods	80
2.3	Mad Libs Revisited	82
2.4	Graphics	88
2.5	Files	114
2.6	Summary	117
3	More On Flow of Control	121
3.1	If Statements	121
3.2	Loops and Tuples	138
3.3	While Statements	143
3.4	Arbitrary Types Treated As Boolean	158
3.5	Further Topics to Consider	160
3.6	Summary	161
4	Dynamic Web Pages	165
4.1	Overview	165
4.2	Web page Basics	166
4.3	Composing Web Pages in Python	168
4.4	CGI - Dynamic Web Pages	172
4.5	Summary	183
5	Appendices	187

5.1	Using Error Messages	187
5.2	Some Special Windows Instructions	193
5.3	Some Special Mac Instructions	194
5.4	HTML Source Markup	197

Dr. Andrew N. Harrington

Computer Science Department, Loyola University Chicago

© Released under the Creative Commons Attribution-Noncommercial-Share Alike 4.0 United States License
<https://creativecommons.org/licenses/by-nc-sa/4.0/> _____

BEGINNING WITH PYTHON

© Released under the Creative commons Attribution-Noncommercial-Share Alike 3.0 United States License
<http://creativecommons.org/licenses/by-nc-sa/3.0/us/>

1.1 Context

You have probably used computers to do all sorts of useful and interesting things. In each application, the computer responds in different ways to your input, from the keyboard, mouse or a file. Still the underlying operations are determined by the design of the program you are given. In this set of tutorials you will learn to write your own computer programs, so you can give the computer instructions to react in the way *you* want.

1.1.1 Low-Level and High-Level Computer Operations

First let us place Python programming in the context of the computer hardware. At the most fundamental level in the computer there are instructions built into the hardware. These are very simple instructions, peculiar to the hardware of your particular type of computer. The instructions are designed to be simple for the hardware to execute, not for humans to follow. The earliest programming was done with such instructions. It was difficult and error-prone. A major advance was the development of higher-level languages and translators for them. Higher-level languages allow computer programmers to write instructions in a format that is easier for humans to understand. For example

$z = x + y$

is an instruction in many high-level languages that means something like:

1. Access the value stored at a location labeled x
2. Calculate the sum of this value and the value stored at a location labeled y
3. Store the result in a location labeled z.

No computer understands the high-level instruction directly; it is not in *machine language*. A special program must first translate instructions like this one into machine language. This one high-level instruction might be translated into a sequence of three machine language instructions corresponding to the three step description above:

```
0000010010000001
0000000010000010
0000010110000011
```

Obviously high-level languages were a great advance in clarity!

If you follow a broad introduction to computing, you will learn more about the layers that connect low-level digital computer circuits to high-level languages.

1.1.2 Why Python

There are many high-level languages. The language you will be learning is Python. Python is one of the easiest languages to learn and use, while at the same time being very powerful: It is one of the most used languages by highly productive professional programmers. Also Python is a free language! If you have your own computer, you can download it from the Internet....

1.1.3 Obtaining Python for Your Computer

Even if you have Python on your own computer, you may well not have the latest version.

If you think you already have a current Python set to go, then try starting Idle: [Starting Idle](#) (page 11). If Idle starts, see if the version stated near the top of its window matches the latest version of Python, then fine!

Otherwise, if you are using Windows or a Mac, see the [Appendices](#) (page 187) for instructions for individual operating systems.

Linux An older version of Python is generally installed, and even if a current version, 3.1+, is installed, Idle is not always installed. Look for a package to install, something like ‘idle-python’ (the name in the Ubuntu distribution).

1.1.4 Philosophy and Implementation of the Hands-On Python Tutorials

Although Python is a high-level language, it is *not* English or some other natural human language. The Python translator does not understand “add the numbers two and three”. Python is a formal language with its own specific rules and formats, which these tutorials will introduce gradually, at a pace intended for a beginner. These tutorials are also appropriate for beginners because they gradually introduce fundamental logical programming skills. Learning these skills will allow you to much more easily program in other languages besides Python. Some of the skills you will learn are

- breaking down problems into manageable parts
- building up creative solutions
- making sure the solutions are clear for humans
- making sure the solutions also work correctly on the computer.

Guiding Principals for the Hands-on Python Tutorials:

- The best way to learn is by active participation. Information is principally introduced in small quantities, where your active participation, experiencing Python, is assumed. In many place you will only be able to see what Python does by doing it yourself (in a hands-on fashion). The tutorial will often not show. Among the most common and important words in the tutorial are “Try this:”
- Other requests are for more creative responses. Sometimes there are Hints, which end up as hyperlinks in the web page version, and footnote references in the pdf version. Both formats should encourage you to think actively about your response first before looking up the hint. The tutorials also provide labeled exercises, for further practice, without immediate answers provided. The exercises are labeled at three levels

No label Immediate reinforcement of basic ideas - *preferably do on your first pass.*

* Important and more substantial - be sure you can end up doing these. Allow time to do them!

** Most creative

- Information is introduced in an order that gives you what you need as soon as possible. The information is presented in context. Complexity and intricacy that is not immediately needed is delayed until later, when you are more experienced.

- In many places there are complications that *are* important in the beginning, because there is a *common* error caused by a slight misuse of the current topic. If such a common error is likely to make no sense and slow you down, more information is given to allow you to head off or easily react to such an error.

Although this approach is an effective way to introduce material, it is not so good for reference. Referencing is addressed in several ways:

- Detailed Table of Contents
- Extensive Index in the web page version
- Flexible Search Engine built into the html version (does *not* work on an html version that you download to your computer)
- Cross references to sections that elaborate on an introductory section. Hyperlinks allow you to jump between the referenced parts in the html version or the pdf version viewed on a computer. The pdf version also gives page references.
- Concise chapter summaries, grouping logically related items, even if that does not match the order of introduction.

1.1.5 Using the Tutorial - Text and Video

The Hands-on Python Tutorial was originally a document to read, with both the html version and a pdf version. Even if you do not print it, some people use the pdf version online, preferring its formatting to the formatting in the html version.

Some people learn better visually and verbally from the very beginning. The Tutorial has videos for many sections.

Also mentioned for the convenience of my Comp 150 class are videos beyondPython, for the part of the class after Python.

The videos are copied into two places:

- [OneDrive](https://loyolauniversitychicago-my.sharepoint.com/:f/g/personal/aharrin_luc_edu/EsF_0EGwnmFAPwhmnHjNVakB-AK2yqMbQ?e=K2l8S9) (https://loyolauniversitychicago-my.sharepoint.com/:f/g/personal/aharrin_luc_edu/EsF_0EGwnmFAPwhmnHjNVakB-AK2yqMbQ?e=K2l8S9). There are five zip files of videos that you can download and unzip, plus individual mp4's for the Python Tutorial appendix sections. There is one zip file for each chapter 1-4 of the Python Tutorial and one zip file (BeyondPython.zip) for the remainder of my Comp class after the Python.

Downloads of the parts do not need any ID. Unzip (expand) any zip file before using.

- [Google Drive](https://drive.google.com/drive/folders/0B5WvvnDHeaIYMGE2MzU4OWEtYzQ4Zi00YzhiLTliMTItNjRjYzMyY): <https://drive.google.com/drive/folders/0B5WvvnDHeaIYMGE2MzU4OWEtYzQ4Zi00YzhiLTliMTItNjRjYzMyY>

You need a Google Drive/Docs login ID. If you are not already logged into Google Drive/Docs, you will need to do it when you click on the link. If you have that ID, then the advantage of Google Drive is that you can select exactly what parts to view or download. This may not work with Internet Explorer, but it does work with Firefox, Safari or Chrome browser.

To get the most out of the tutorial, I strongly suggest the following approach for each part:

- Watch a video if you like. They are clearly labeled by numerical section. Stop the video where I ask you to *think*. The videos hit the high points and take advantage of being able to point at specific places on the screen. They are not as recent as the current text, so they may look a bit different than the tutorial in a web page.

Some details may only appear in the written text.

Stop the video frequently to test things for yourself! If a new function is introduced, do not only watch the video, but try it out for yourself, including with data not in the video. In some places the written version mentions more examples to try.

- Whether you look at the video of a section or not, do look through a written version, either as a first pass or to review and fill in holes from the videos. Be sure to stop and try things yourself, and see how they actually work on your computer.
- Look at the labeled exercises. You are strongly recommended to give the unstarred ones an immediate try to reinforce basic concepts. The starred ones (*) are important for a strong understanding. Do not get too far ahead in reading/watching before trying the starred exercises. Understanding earlier parts well enough to be able to solve problems is going to either be completely necessary for understanding some later sections or at least make later sections easier to follow and fully comprehend.
- Python provides too rich an environment to be able to show you all interrelationships immediately. That can mean errors send you in a strange (to you) direction. See the appendix section [Using Error Messages](#) (page 187).

Have fun and be creative, and discover your power with Python!

1.1.6 Learning to Problem-Solve

While the tutorial introduces all the topics, there is more to say about using it effectively. There is way too much detail to just absorb all at once. So what are the first things to learn?

More important than memorizing details is having an idea of the building blocks available and how they are useful. For the most direct exercises, you might just look back over the most recent section looking for related things, but that will not work when you have scores of sections that might have useful parts! The basic idea of the building blocks should be in your head. For instance, looking ahead to when you have finished the Tutorial through 1.10.4, you will want to have these ideas very present in your head to be ready to start on the exercises:

- You can use numbers and do arithmetic.
- You can store and retrieve data using variable names and assignment statements.
- Python has many useful built-in functions that can affect the system or return results for you to use.
- You can get keyboard input from the user and print things back for the user.
- Data comes in different types, and you can convert where it makes sense.
- You can use strings and generate them in many ways: literal strings, concatenation operator (+), string format method.

Once you have an idea of the appropriate building blocks needed to solve a specific problem, then you can worry about more details. Particularly at the beginning, you are not likely to have all the exact Python syntax for the parts of your solution nailed down! It is not important to remember it precisely, but it is important to know how to find a clear explanation efficiently: Know the location in examples or in the tutorial, or use the index, the search capacity, summaries, and/or write things in notes for yourself - as for an exam. Writing short bits down is also useful because the *act of writing* helps many people absorb what they are writing.

As your experience increases you will get used to and remember more and more stuff, but there is always the latest idea/syntax to get used to! Your notes of what is important, but still not in immediate recall, will evolve continuously.

This multi-tiered approach means that what you absorb should not just be an enormous collection of unstructured facts that you plumb through in its entirety to find a useful idea. You first need to be particularly aware of the major headings of useful features, and then do what you need to drill down to details as necessary.

This approach is important in the real-world, away from Python. The world is awash with way too much information to memorize, but you must access the information that you need to synthesize and formulate solutions/arguments ... effectively!

Knowing all the building blocks of a solution is obviously important. Many successful holistic thinkers can do this effectively. In some domains a knowledge of the pieces and their relationships is enough. Programming requires more than this, however: It is critical to sort out the exact *sequence* in which the pieces must logically appear. Some

excellent holistic thinkers have a hard time with this sequencing, and must pay extra attention when planning code. If you are like this, be patient and be prepared to ask for help where needed.

What to do *after* you finish an exercise is important, too. The natural thing psychologically, particularly if you had a struggle, is to think, “Whew, outta here!!!!”

On something that came automatically or flowed smoothly, that is not a big deal - you will probably get it just as fast the next time. If you had a hard time and only eventually got to success, you may be doing yourself a disservice with “Whew, outta here!!!”

We have already mentioned how not everything is equally important, and some things are more important to keep in your head than others. The same idea applies to all the steps in solving a possibly long problem. Some parts were easy; some were hard; there may have been several steps. If all of that goes into your brain in one continuous stream of stuff that you remember at the same level, then you are going to leave important nuggets mixed in with an awful lot of unimportant and basically useless information. Then the information is likely to all fade into oblivion, or be next to impossible to cycle through looking for the useful nuggets. Why do the problem anyway if you are just going to bury important information further down in your brain?

What is important? The most obvious thing you will need at a higher level of recall is what *just messed you up*, what you missed until doing this problem: After finishing the actual problem, *actively* follow up and ask yourself:

- What did I get in the end that I was missing initially? What was the connection I made?
- Does this example fit in to some larger idea/abstraction/generalization in a way that I did not see before?
- How am I going to look at this so I can make a similar connection in a similar (or maybe only partly similar) problem?
- Is there a kernel here that I can think of as a new tool in my bag of tricks?

Your answers to these questions are the most important things to take away from your recent hard work. The extra consideration puts them more in the “priority” part of your brain, so you can really learn from your effort. When you need the important ideas next, you do not need to play through all the details of the stuff you did to solve the earlier problem.

Keep coming back to this section and check up on your process: It is really important.

1.2 The Python Interpreter and Idle, Part I

1.2.1 Your Python Folder and Python Examples

First you need to set up a location to store your work and the example programs from this tutorial. You can put the folder for your Python programs most anywhere you like. However, for Chapter 4, it will be important that *none of the directories leading down to your Python folder contain any blanks in them*, in particular your home folder.

The normal place for you to have my examples folder is under your home folder, which has the same name as your Login ID. If you are just creating a login ID, it will save some hassle in Chapter 4, if your login ID does *not have a space in it*. “Andy” or “anh” or AndyHarrington” would be fine for me, but

“Andy Harrington”

would bomb the server in Chapter 4. It is possible to do Chapter 4 with a folder outside your home folder, as discussed at the beginning of Chapter 4.

1.2.2 Folder For My Examples

Download and save <http://anh.cs.luc.edu/python/hands-on/3.1/examples.zip>.

Note that the examples, like this version of the tutorial, are for Python 3. There were major changes to Python in version 3.0, making it incompatible with earlier versions.

If you are using Python version 2.7 for some good reason, you should continue with the older version of the tutorial. Go to <http://anh.cs.luc.edu/python/hands-on> and find the links to the proper version of the tutorial and examples.

Once you have the examples.zip archive, you need to extract the files. Make a file browser window set to the directory where you put the zip file. Then:

Windows Right click on examples.zip, select Extract All. This will create the folder `examples`. End up with a file browser window showing the contents of the examples folder. This will be your *Python folder* in later discussion.

Mac Double click on the zip file and the expanded examples folder appears.

Warning: On Windows, files in a zip archive can be viewed while they are still in the zip archive. Modifying and adding files is not so transparent. Be sure that you *unzip the archive* and *work from the regular directory* that holds the resulting unzipped files.

You also have the option of downloading

- An archive containing the web version of the tutorial <http://anh.cs.luc.edu/python/hands-on/3.1/handsonHtml.zip> for local viewing, without the Internet. Download it and unzip as with the examples. The local file to open in your browser in the `handsonHtml` folder you unzipped and the main web page file to open is called `index.html`.
- The PDF version of the tutorial for printing <http://anh.cs.luc.edu/python/hands-on/3.1/Hands-onPythonTutorial.pdf>. Some people also like the typography of this version on the web, too. It is hyperlinked like html version.

1.2.3 Running A Sample Program

This section assumes Python 3 is already on your computer. Windows does not come with Python. (To load Python see *Obtaining Python for Your Computer* (page 4).)

Before getting to the individual details of Python, you will run a simple text-based sample program. Find `madlib.py` in your Python folder, set up in *Your Python Folder and Python Examples* (page 7).

Note: Different keyboards label the key for ending a line differently: Windows keyboards may use `Enter` while Mac keyboards use `Return`. The tutorial may intermix instructions to press `Enter` or press `Return`. They both are intended to mean the key for ending a line.

Options for running the program:

- If you have trouble with the following options, opening the program in Idle is discussed in *Starting Idle* (page 11).
- In Windows, you can display your folder contents, and double click on `madlib.py` to start the program.
- On a Mac, you can Control-click on `madlib.py` in the Finder, select Open With, and choose the Python Launcher for your Python 3 version. When you are done with the program, close the terminal window.
- In Linux you may be able to open a terminal window, change into your Python examples directory, and enter the command

```
python madlib.py
```

or possibly to distinguish Python 2 and 3:

```
python3 madlib.py
```

If neither of these work, get help.

Try the program a second time and make different responses.

1.2.4 A Sample Program, Explained

If you want to get right to the detailed explanations of writing your own Python, you can *skip to the next section Starting Idle* (page 11). If you would like an overview of a working program, even if all the explanations do not make total sense yet, read on.

Here is the text of the madlib.py program, followed by line-by-line brief explanations. Do not worry if you not totally understand the explanations! Try to get the gist now and the details later. The numbers on the right are not part of the program file. They are added for reference in the comments below:

```
#!/usr/bin/env python3 0
''' 1
String Substitution for a Mad Lib 2
Adapted from code by Kirby Urner 3
''' 4
5
storyFormat = ''' 6
Once upon a time, deep in an ancient jungle, 7
there lived a {animal}. This {animal} 8
liked to eat {food}, but the jungle had 9
very little {food} to offer. One day, an 10
explorer found the {animal} and discovered 11
it liked {food}. The explorer took the 12
{animal} back to {city}, where it could 13
eat as much {food} as it wanted. However, 14
the {animal} became homesick, so the 15
explorer brought it back to the jungle, 16
leaving a large supply of {food}. 17
18
The End 19
''' 20
21
def tellStory(): 22
    userPicks = dict() 23
    addPick('animal', userPicks) 24
    addPick('food', userPicks) 25
    addPick('city', userPicks) 26
    story = storyFormat.format(**userPicks) 27
    print(story) 28
29
def addPick(cue, dictionary): 30
    '''Prompt for a user response using the cue string, 31
    and place the cue-response pair in the dictionary. 32
    ''' 33
    prompt = 'Enter an example for ' + cue + ': ' 34
    response = input(prompt) 35
    dictionary[cue] = response 36
37
tellStory() 38
input('Press Enter to end the program.') 39
```

Line By Line Explanation

```
#!/usr/bin/env python3
```

```
0
```

This is not technically a part of the program. It is there to tell the operating system what version of Python to choose, since the older Python 2 is incompatible with the newer Python 3. We will mostly run programs from inside the Idle programming environment, where this line is not needed. To run just by clicking on the program in an operating system window, however, the line is important if your computer also has Python 2.

```
'''
String Substitution for a Mad Lib
Adapted from code by Kirby Urner
'''
```

```
1
2
3
4
```

1-4: There is multi-line text enclosed in triple quotes. Quoted text is called a *string*. A string at the very beginning of a program like this is *documentation* for the file.

5,21,29,37: Blank lines are included for human readability to separate logical parts. The computer ignores the blank lines.

```
storyFormat = '''
Once upon a time, deep in an ancient jungle,
there lived a {animal}. This {animal}
liked to eat {food}, but the jungle had
very little {food} to offer. One day, an
explorer found the {animal} and discovered
it liked {food}. The explorer took the
{animal} back to {city}, where it could
eat as much {food} as it wanted. However,
the {animal} became homesick, so the
explorer brought it back to the jungle,
leaving a large supply of {food}.

The End
'''
```

```
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
```

6: The equal sign tells the computer that this is an *assignment statement*. The computer will now associate the value of the expression between the triple quotes, a multi-line *string*, with the name on the left, `storyFormat`.

7-20: These lines contain the body of the string and the ending triple quotes. This `storyFormat` string contains some special symbols making it a *format string*, unlike the string in lines 1-4. The `storyFormat` string will be used later to provide a format into which substitutions are made. The parts of the string enclosed in braces are places a substitute string will be inserted later. The substituted string will come from a custom *dictionary* that will contain the user's definitions of these words. The words in the braces: `{animal}`, `{food}`, `{city}`, indicate that `animal`, `food`, and `city` are words in a dictionary. This custom dictionary will be created in the program and contain the user's definitions of these words. These user's definitions will be substituted later in the *format string* where each `{...}` is currently.

```
def tellStory():
    userPicks = dict()
    addPick('animal', userPicks)
    addPick('food', userPicks)
    addPick('city', userPicks)
    story = storyFormat.format(**userPicks)
    print(story)
```

```
22
23
24
25
26
27
28
```

22: `def` is short for **definition** of a function. This line is the heading of a **definition**, which makes the name `tellStory` becomes **defined** as a short way to refer to the sequence of statements that start indented on line 23, and continue through line 28.

23: The equal sign tells the computer that this is another assignment statement. The computer will now associate the

name `userPicks` with a new empty dictionary created by the Python code `dict()`.

24-26: `addPick` is the name for a function defined by the sequence of instructions on lines 29-31, used to add another definition to a dictionary, based on the user's input. The result of these three lines is to add definitions for each of the three words `animal`, `food`, and `city` to the dictionary called `userPicks`.

27: Assign the name `story` to a string formed by substituting into `storyFormat` using definitions from the dictionary `userPicks`, to give the user's customized story.

28: This is where all the work becomes visible: Print the `story` string to the screen.

```
def addPick(cue, dictionary):           30
    '''Prompt for a user response using the cue string, 31
    and place the cue-response pair in the dictionary. 32
    '''                                   33
    prompt = 'Enter an example for ' + cue + ': '      34
    response = input(prompt)                        35
    dictionary[cue] = response                      36
```

30: This line is the heading of a definition, which gives the name `addPick` as a short way to refer to the sequence of statements indented on line 34-36. The name `addPick` is followed by two words in parenthesis, `cue` and `dictionary`. These two words are associated with an actual cue word and dictionary given when this definition is invoked in lines 24-26.

31-33: A documentation comment for the `addPick` definition.

34: The plus sign here is used to concatenate parts of the string assigned to the name `prompt`. The current value of `cue` is placed into the string.

35: The right-hand-side of this equal sign causes an interaction with the user, to input text from the keyboard: The `prompt` string is printed to the computer screen, and the computer waits for the user to enter a line of text. That line of text then becomes a string inside the program. This string is assigned to the name `response`.

36: The left-hand-side of the equal sign is a reference to the definition of the cue word in the dictionary. The whole line ends up making the definition of the current cue word become the response typed by the user.

```
tellStory()                             38
input('Press Enter to end the program.') 39
```

38: The definition of `tellStory` above does not make the computer do anything besides *remember* what the instruction `tellStory` means. It is only in this line, with the name, `tellStory`, followed by parentheses, that the whole sequence of remembered instructions are actually carried out.

39: This line is only here to accommodate running the program in Windows by double clicking on its file icon. Without this line, the story would be displayed and then the program would end, and Windows would make it immediately disappear from the screen! This line forces the program to continue being displayed until there is another response from the user, and meanwhile the user may look at the output from `tellStory`.

1.2.5 Starting Idle

The program that translates Python instructions and then executes them is the *Python interpreter*.

This interpreter is embedded in a number of larger programs that make it particularly easy to develop Python programs. Such a programming environment is *Idle*, and it is a part of the standard distribution of Python.

It is possible to open the Idle app directly:

- Start a search:

Windows: Press the Windows key or go to the start menu.

Mac: open Spotlight (Command-spacebar).

- Enter Idle in the search field. Select the Idle app.


If you have Linux:

The approach depends on the installation. In Ubuntu, you should find Idle in the Programming section of the Applications menu. You are better starting idle from a terminal, with the current directory being your Python folder. You may need a special name set up to distinguish idle for versions 2 and 3, for instance `idle3` for version 3.X.

We will discuss later that if you want to edit files, this is *not* the best way to start Idle, since the associated folder is not the one you want, but it works for now.

1.2.6 Windows in Idle


Idle has several parts you may choose to display, each with its own window. Depending on the configuration, Idle can start up showing either of two windows, an Edit Window or a Python Shell Window. You are likely to first see an Edit window, whose top left corner looks something like in Windows:



For more on the Edit Window, see *The Idle Editor and Execution* (page 22).

If you see this Edit Window with its Run menu on top, go to the Run menu and choose PYTHON SHELL to open a Python Shell Window for now. Then you may close the Edit Window. For now we will just be using the Python Shell.

Either initially, or after explicitly opening it, you should now see the Python Shell window, with a menu like the following, though the text may be slightly different:



In the Shell the last line should look like


```
>>>
```

The `>>>` is the *prompt*, telling you Idle is waiting for *you* to type something. Continuing on the same line enter

```
6+3
```

Be sure to end with the Enter key. After the Shell responds, you should see something like

```
>>> 6+3
9
>>>
```

The shell evaluates the line you entered, and prints the result. You see Python does arithmetic. At the end you see a further prompt `>>>` where you can enter your next line.... The result line, showing 9, that is produced by the computer, does not start with `>>>`.

When we get to whole programs, we will use [The Idle Editor and Execution](#) (page 22).

1.3 Whirlwind Introduction To Types and Functions

Python directly recognizes a variety of types of data. Here are a few:

Numbers: 3, 6, -7, 1.25

Character strings: 'hello', 'The answer is: '

Lists of objects of any type: [1, 2, 3, 4], ['yes', 'no', 'maybe']

A special datum meaning nothing: None

Python has large collection of built-in functions that operate on different kinds of data to produce all kinds of results. To make a function do its action, parentheses are required. These parentheses surround the parameter or parameters, as in a function in algebra class.

The general syntax to execute a function is

functionName (*parameters*)

One function is called `type`, and it returns the type of any object. The Python Shell will evaluate functions. In the Shell the last line should look like

```
>>>
```

Continuing on the same line enter

```
type(7)
```

Always remember to end with the Return (or Enter) key. After the Shell responds, you should see something like

```
>>> type(7)
<class 'int'>
>>>
```

In the result, `int` is the way Python abbreviates integer. The word *class* is basically a synonym for type in Python.

Note that the line with the value *produced* by the shell does not start with `>>>` and appears at the left margin. Hence you can distinguish what the computer responds from what you type (after the `>>>` prompt).

At the end you see a further prompt where you can enter your next line....

For the rest of this section, at the `>>>` prompt in the Python *Shell*, individually enter each line below that is set off in typewriter font. So next enter

```
type(1.25)
```

Note the name in the last result is `float`, not real or decimal, coming from the term “floating point”, for reasons that will be explained later, in *Floats, Division, Mixed Types* (page 62).

Enter

```
type('hello')
```

In your last result you see another abbreviation: `str` rather than string. Enter

```
type([1, 2, 3])
```

Strings and lists are both sequences of parts (characters or elements). We can find the **length** of that sequence with another function with the abbreviated name `len`. Try both of the following, separately, in the *Shell*:

```
len([2, 4, 6])
len('abcd')
```

Some functions have no parameters, so nothing goes between the parentheses. For example, some types serve as no-parameter functions to create a simple value of their type. Try

```
list()
```

You see the way an empty list is displayed.

Functions may also take more than one parameter. Try

```
max(5, 11, 2)
```

Above, `max` is short for maximum.

Some of the names of types serve as conversion functions (where there is an obvious meaning for the conversion). Try each of the following, one at a time, in the *Shell*:

```
str(23)
int('125')
```

Note the presence and absence of quotes.

An often handy Shell feature: an earlier Shell line may be copied and edited by clicking anywhere in the previously displayed line and then pressing the Return (or Enter) key. For instance you should have entered several lines starting with `len`. click on any one, press Return, and edit the line for a different test.

1.4 Integer Arithmetic

1.4.1 Addition and Subtraction

We start with the integers and integer arithmetic, not because arithmetic is exciting, but because the symbolism should be mostly familiar. Of course arithmetic is important in many cases, but Python is probably more often used to manipulate text and other sorts of data, as in the sample program in *Running A Sample Program* (page 8).

Python understands numbers and standard arithmetic. *For the whole section on integer arithmetic*, where you see a set-off line in typewriter font, type individual lines at the `>>>` prompt in the Python *Shell*. Press Enter after each line to get Python to respond:

```
77
2 + 3
5 - 7
```

Python should evaluate and print back the value of each expression. Of course the first one does not require any calculation. It appears that the shell just echoes back what you printed.

The Python Shell is an interactive interpreter. As you can see, after you press `Return` (or `Enter`), it is evaluating the expression you typed in, and then printing the result automatically. This is a very handy environment to check out simple Python syntax and get instant feedback. For more elaborate programs that you want to save, we will switch to an Editor Window later.

1.4.2 Multiplication, Parentheses, and Precedence

Try in the *Shell*:

```
2 x 3
```

You should get your first *syntax error*. The `x` should have become highlighted, indicating the location where the Python interpreter discovered that it cannot understand you: Python does not use `x` for multiplication as you may have done in grade school. The `x` can be confused with the use of `x` as a variable (more on that later).

Instead the symbol for multiplication is an asterisk `*`. Enter each of the following. You may include spaces or not. The Python interpreter can figure out what you mean either way. (The space can make understanding quicker for a human reader.) Try in the *Shell*:

```
2*5
2 + 3 * 4
```

If you expected the last answer to be 20, think again: Python uses the normal *precedence* of arithmetic operations: Multiplications and divisions are done before addition and subtraction, unless there are parentheses. Try

```
(2+3)*4
2 * (4 - 1)
```

Now try the following in the *Shell*, exactly as written, followed by `Enter`, with *no* closing parenthesis:

```
5 * (2 + 3
```

Look carefully. There is no answer given at the left margin of the next line and no prompt `>>>` to start a *new* expression. If you are using Idle, the cursor has gone to the next line and has only *indented* slightly. Python is waiting for you to finish your expression. It is smart enough to know that opening parentheses are always followed by the same number of closing parentheses. The cursor is on a *continuation* line. Type just the matching close-parenthesis and `Enter`,

```
)
```

and you should finally see the expression evaluated. (In some versions of the Python interpreter, the interpreter puts `'...'` at the beginning of a continuation line, rather than just indenting.)

Negation also works. Try in the *Shell*:

```
-(2 + 3)
```

1.4.3 Division and Remainders

If you think about it, you learned several ways to do division. Eventually you learned how to do division resulting in a decimal. Try in the *Shell*:

```
5/2
14/4
```

As you saw in the previous section, numbers with decimal points in them are of type float in Python. They are discussed more in *Floats, Division, Mixed Types* (page 62).

In early grade school you would likely say “14 divided by 4 is 3 with a remainder of 2”. The problem here is that the answer is in two parts, the integer quotient 3 and the remainder 2, and neither of these results is the same as the decimal result. Python has *separate* operations to generate each part. Python uses the doubled division symbol `//` for the operation that produces just the integer quotient, and introduces the symbol `%` for the operation of finding the remainder. Try each in the *Shell*:

```
14/4
14//4
14%4
```

Now predict and then try each of

```
23//5
23%5
20%5
6//8
6%8
6/8
```

Finding remainders will prove more useful than you might think in the future!

OPTIONAL from here to the end of the section, considering negative numbers in integer quotients and remainders:

In grade school you were probably always doing such remainder calculations with positive integers, as we have above. This is all we are likely to need for this course. However, the remainder operation is defined for all integers, even a negative divisor. We will *probably not need it in this course*, but try

```
17 % -5
-17 % 5
-17 % -5
```

You can stop here and just beware mixing in negative numbers in your integer arithmetic, or go on to a fuller explanation:

Go back to positive numbers first.

17 divided by 5: $17//5$ is 3; $17 \% 5$ is 2. The basic relationship is $17 = 5*3 + 2$:

dividend = quotient * divisor + remainder

We want that to always be true.

The issue is really with integer division when the dividend and divisor are not both positive: the value of this determines the remainder, solving above:

$$\text{remainder} = \text{dividend} - \text{quotient} * \text{divisor}$$

With positive numbers the integer quotient is always no bigger than the real quotient. In its definition, Python requires that this is true, no matter what the signs of the operands :

$17/(-5)$ is -3.2, so $17//(-5)$ must be -4 (not greater than -3.25),

By the general relationship between quotients and remainders, that forces

$$17 \% (-5) = 17 - (-4)*(-5) = -3$$

Swapping the negative signs,

$-17 / 5$ is still -3.2 so

$-17 // 5$ is still -4,

but now look at the remainder formula:

$$-17\%5 = -17 - (-4)*5 = 3$$

Last sign switch: both negative

$$-17 / (-5) \text{ is } 3.2 \text{ so}$$

$$-17 // (-5) \text{ is } 3$$

Remainder formula:

$$-17\% (-5) = -17 - (3)*(-5) = -2$$

Note the sign of nonzero remainders always matches the sign of the divisor IN PYTHON.

Side note: Many other languages (Java, C++, ...) use a different definition for integer division, saying its MAGNITUDE is never larger than the real division. This forces the remainders for mixed sign divisions to be different than in Python. Example where this is significant: In Python you can identify an arbitrary odd number because it has remainder 1 when dividing by 2. This is true in Python whether the odd number is positive or negative, but it is NOT true in the other languages!

1.5 Strings, Part I

Enough with numbers for a while. Strings of characters are another important type in Python.

1.5.1 String Delimiters, Part I

A string in Python is a sequence of characters. For Python to recognize a sequence of characters, like `hello`, as a string, it must be enclosed in quotes to delimit the string.

For this whole section on strings, continue trying each set-off line of code in the Shell. Try

```
"hello"
```

Note that the interpreter gives back the string with *single* quotes. Python does not care what system you use. Try

```
'Hi!'
```

Having the choice of delimiters can be handy.

Figure out how to give Python the string containing the text: `I'm happy`. Try it. If you got an error, try it with another type of quotes, and figure out why that one works and not the first.

There are many variations on delimiting strings and embedding special symbols. We will consider more ways later in *Strings Part II* (page 21).

Note: A string can have any number of characters in it, including 0. The empty string is `''` (two quote characters with nothing between them). Many beginners forget that having no characters in the middle is legal. It can be useful.

Strings are a new Python type. Try

```
type('dog')
type('7')
type(7)
```

The last two lines show how easily you can get confused! Strings can include any characters, *including* digits. Quotes turn even digits into strings. This will have consequences in the next section....

1.5.2 String Concatenation

Strings also have operation symbols. Try in the *Shell* (noting the *space* after `very`):

```
'very ' + 'hot '
```

The plus operation with strings means *concatenate* the strings. Python looks at the type of operands before deciding what operation is associated with the `+`.

Think of the relation of addition and multiplication of integers, and then guess the meaning of

```
3*'very ' + 'hot '
```

Were you right? The ability to repeat yourself easily can be handy.

Predict the following and then test. Remember the last section on types:

```
7+2  
'7'+'2'
```

Python checks the types and interprets the plus symbol based on the type. Try

```
'7'+2
```

With mixed string and int types, Python sees an ambiguous expression, and does not guess which you want - it just gives an error! ¹

This is a traceback error. These occur when the code is being executed. In the last two lines of the traceback it shows the Python line where the error was found, and then a reason for the error. Not all reasons are immediately intelligible to a starting programmer, but they are certainly worth checking out. In this case it is pretty direct. You need to make an explicit conversion, so both are strings if you mean concatenation, `'7' + str(2)`, or so both are int if you mean addition, `int('7') + 2`.

With literal strings these examples are only useful for illustration: There is no reason to write such verbose expressions when you already know the intended result. With *variables*, starting in the next section, expressions involving these conversions become more important....

String Exercise

Figure out a *compact* way to get Python to make the string, `'YesYesYesYesYes'`, and try it. How about `'MaybeMaybeMaybeYesYesYesYesYes'`? Hint: ²

1.6 Variables and Assignment

Each set-off line in this section should be tried in the Shell.

Try

```
width = 10
```

Nothing is displayed by the interpreter after this entry, so it is not clear anything happened. Something has happened. This is an *assignment statement*, with a *variable*, `width`, on the left. A variable is a name for a value. An assignment statement associates a variable name on the left of the equal sign with the value of an expression calculated from the right of the equal sign. Enter

¹ Be careful if you are a Java or C# programmer! This is unlike those languages, where the `2` would be automatically converted to `'2'` so the concatenation would make sense.

² Hint for the second one: use two `*`'s and a `+`.

```
width
```

Once a variable is assigned a value, the variable can be used in place of that value. The response to the expression `width` is the same as if its value had been entered.

The interpreter does not print a value after an assignment statement because the value of the expression on the right is not lost. It can be recovered if you like, by entering the variable name and we did above.

Try each of the following lines:

```
height = 12
area = width * height
area
```

The equal sign is an unfortunate choice of symbol for assignment, since Python's usage is not the mathematical usage of the equal sign. If the symbol \leftarrow had appeared on keyboards in the early 1990's, it would probably have been used for assignment instead of `=`, emphasizing the asymmetry of assignment. In mathematics an equation is an *assertion* that *both* sides of the equal sign *are already, in fact, equal*. A Python assignment statement *forces* the variable on the left hand side *to become* associated with the value of the expression on the right side. The difference from the mathematical usage can be illustrated. Try:

```
10 = width
```

so this is not equivalent in Python to `width = 10`. The *left hand* side must be a variable, to which the assignment is made. Reversed, we get a *syntax error*. Try

```
width = width + 5
```

This is, of course, nonsensical as mathematics, but it makes perfectly good sense as an assignment, with the right-hand side calculated first. Can you figure out the value that is now associated with `width`? Check by entering

```
width
```

In the assignment statement, the expression on the right is evaluated *first*. At that point `width` was associated with its original value 10, so `width + 5` had the value of `10 + 5` which is 15. That value was then assigned to the variable on the left (`width` again) to give it a *new* value. We will modify the value of variables in a similar way routinely.

Assignment and variables work equally well with strings. Try:

```
first = 'Sue'
last = 'Wong'
name = first + ' ' + last
name
```

Try entering:

```
first = fred
```

Note the different form of the error message. The earlier errors in these tutorials were *syntax* errors: errors in translation of the instruction. In this last case the syntax was legal, so the interpreter went on to execute the instruction. Only *then* did it find the error described. There are no quotes around `fred`, so the interpreter assumed `fred` was an identifier, but the name `fred` was not defined at the time the line was executed.

It is both easy to forget quotes where you need them for a literal string and to mistakenly put them around a variable name that should not have them!

Try in the *Shell*:

```
fred = 'Frederick'
first = fred
first
```

There `fred`, without the quotes, makes sense.

There are more subtleties to assignment and the idea of a variable being a “name for” a value, but we will worry about them later, in *Issues with Mutable Objects* (page 97). They do not come up if our variables are just numbers and strings.

Autocompletion: A handy short cut. Idle remembers all the variables you have defined at any moment. This is handy when editing. Without pressing Enter, type into the Shell just

```
f
```

Windows users: Then *hold down* the Alt key and press the / key. This key combination is abbreviated Alt-/.

Mac users: The Windows key combination above may give you a funny character. (If so backspace over it.) In that case you need to hold down both the control key and the alt/option key when pressing the '/'. This may hold in other places in this tutorial, where the Alt key is called for in Windows.)

Assuming you are following on the earlier variable entries to the Shell, you should see `f` *autocompleted* to be

```
first
```

This is particularly useful if you have long identifiers! You can press Alt-/ several times if more than one identifier starts with the initial sequence of characters you typed. If you press Alt-/ again you should see `fred`. Backspace and edit so you have `fi`, and then and press Alt-/ again. You should not see `fred` this time, since it does not start with `fi`.

1.6.1 Literals and Identifiers

Expressions like `27` or `'hello'` are called *literals*, coming from the fact that they *literally* mean exactly what they say. They are distinguished from variables, whose value is *not* directly determined by their name.

The sequence of characters used to form a variable name (and names for other Python entities later) is called an *identifier*. It identifies a Python variable or other entity.

There are some restrictions on the character sequence that make up an identifier:

- The characters must all be letters, digits, or underscores `_`, and must start with a letter. In particular, punctuation and blanks are not allowed.
- There are some words that are *reserved* for special use in Python. You may not use these words as your own identifiers. They are easy to recognize in Idle, because they are automatically colored orange. For the curious, you may *read* the full list:

<code>False</code>	<code>await</code>	<code>else</code>	<code>import</code>	<code>pass</code>
<code>None</code>	<code>break</code>	<code>except</code>	<code>in</code>	<code>raise</code>
<code>True</code>	<code>class</code>	<code>finally</code>	<code>is</code>	<code>return</code>
<code>and</code>	<code>continue</code>	<code>for</code>	<code>lambda</code>	<code>try</code>
<code>as</code>	<code>def</code>	<code>from</code>	<code>nonlocal</code>	<code>while</code>
<code>assert</code>	<code>del</code>	<code>global</code>	<code>not</code>	<code>with</code>
<code>async</code>	<code>elif</code>	<code>if</code>	<code>or</code>	<code>yield</code>

There are also identifiers that are automatically defined in Python, and that you could redefine, but you probably should not unless you really know what you are doing! When you start the editor, we will see how Idle uses color to help you know what identifiers are predefined.

Python is case sensitive: The identifiers `last`, `LAST`, and `LaSt` are all different. Be sure to be consistent. Using the Alt-/ auto-completion shortcut in Idle helps ensure you are consistent.

What is legal is distinct from what is conventional or good practice or recommended. Meaningful names for variables are important for the humans who are looking at programs, understanding them, and revising them. That sometimes means you would like to use a name that is more than one word long, like `price at opening`, but blanks are

illegal! One poor option is just leaving out the blanks, like `priceatopening`. Then it may be hard to figure out where words split. Two practical options are

- underscore separated: putting underscores (which are legal) in place of the blanks, like `price_at_opening`.
- using *camel-case*: omitting spaces and using all lowercase, except capitalizing all words after the first, like `priceAtOpening`

Use the choice that fits your taste (or the taste or convention of the people you are working with).

1.7 Print Function, Part I

In interactive use of the Python interpreter, you can type an expression and immediately see the result of its evaluation. This is fine to test out syntax and maybe do simple calculator calculations. In a program run from a file like the first sample program, Python does not display expressions this way. If you want your program to display something, you can give explicit instructions with the `print` function. Try in the *Shell*:

```
x = 3
y = 5
print('The sum of', x, 'plus', y, 'is', x+y)
```

The `print` function will print as strings everything in a comma-separated sequence of expressions, and it will separate the results with single blanks, and advance to the next line at the end, by default. Note that you can mix types: anything that is not already a string is automatically converted to its string representation.

You can also use it with no parameters:

```
print()
```

to only advance to the next line.

1.8 Strings Part II

1.8.1 Triple Quoted String Literals

Strings delimited by one quote character, like `'`, are required to lie within a single Python line. It is sometimes convenient to have a multi-line string, which can be delimited with triple quotes, `'''`. Try typing the following. You will get continuation lines until the closing triple quotes. Try in the *Shell*:

```
sillyTest = '''Say,
"I'm in!"
This is line 3'''
print(sillyTest)
```

The line structure is preserved in a multi-line string. As you can see, this also allows you to embed both single and double quote characters!

1.8.2 Escape Codes

Continuing in the *Shell* with `sillyTest`, enter just

```
sillyTest
```

The answer looks strange! It indicates an alternate way to encode the string internally in Python using *escape codes*. Escape codes are embedded inside string literals and start with a backslash character `\`. They are used to embed characters that are either unprintable or have a special syntactic meaning to Python that you want to suppress. In this example you see some of the ones in this short list of most common escape codes:

Escape code	Meaning
<code>\\</code>	<code>\</code> (backslash)
<code>\n</code>	newline
<code>\'</code>	' (single quote character)
<code>\"</code>	" (double quote character)

The newline character indicates further text will appear on a new line when *printed*. When you use the `print` function, you get the actual printed meaning of the escape coded character.

Predict the result, and try in the *Shell*:

```
print('a\nb\n\nc')
```

Did you guess the right number of lines splitting in the right places?

1.9 The Idle Editor and Execution

1.9.1 Loading a Program in the Idle Editor, and Running It

It is time to put longer collections of instructions together. That is most easily done by creating a text file and running the Python interpreter on the file. Idle simplifies that process.

First you can put an existing file into an Idle Edit Window. Start with the sample program `madlib.py`. If you have not downloaded it yet, see *Your Python Folder and Python Examples* (page 7).

Assuming you are already in Idle from the previous sections, you can open a file from there:

- Click on the Idle *File* menu and select *Open*. (Or as you see, you can use the shortcut `Ctrl-O`. That means holding down the `Ctrl` key, and pressing the letter `O` for *Open*.) You should get a file selection dialog.
- You need to navigate to the folder with the file you want. If you already had a file open, and its window has the foreground focus when you make access the File menu, then the folder that opens is the same as the folder from which the current file came.

If the Shell Window has the foreground focus, then the folder opened depends on the operating system:

- Windows: At least through Python 3.7, Windows is likely to open a buried system folder that you *do not want to mess with!* Switch to your Desktop or Documents, and find the right folder from there. Hopefully the behaviour will be more like on a Mac in future version.
- Mac and Linux: A reasonable folder opens: Documents. Navigate from there.

Hence it is important to set the focus on an Edit window to have the same folder appear when opening a new file.

- Select the file you want. (The initial suggestion was `madlib.py`.)

You will see the source code again. Now run this program from inside of Idle: Go to the *Run* menu of that Edit window, and select *Run Module*. Notice the shortcut (`F5`) also available.

If the Shell window does not automatically come to the foreground, select it. You should see a line saying `RESTART` and then the start of the execution of the Mad Lib program with the cursor waiting for your entry after the first prompt. Finish executing the program. Be sure to type the final requested Enter, so you get back to the interpreter prompt: `>>>`

Look at the editor window again. You should see that different parts of the code have different colors. String literals are likely green. The reserved word `def` is likely orange. Look at the last two lines, where the identifier `tellStory` is black, and the identifier `input` is likely purple. Only identifiers that are *not* predefined by Python are black. If you create an identifier name, make sure Idle shows it in *black*.

1.9.2 Starting Idle for Editing

You are strongly suggested to keep the programs you write in the given examples folder along with all the examples provided to you. You can always easily see the files you created, all together, by sorting by creation date. You are likely to create new programs derived from some of the given examples, and some earlier programs of your own. Everything is easy to access if you keep them together.

The way I recommended to start Idle to work on this tutorial is to start by opening it on a file in the folder where you want to work, either a file you want to further edit, a related file you want to modify, or just any Python file in the same folder if you want to start from scratch.

To open Idle with an initial file to edit, select the Python file in an operating system window, right click (Windows) or control-click (Mac), to get a pop-up window to select how to open the file. On Windows, the line for Idle requires you to open a sub-menu. Select Idle for the latest version.

Opening Idle without a file reference, directly from the operating system, makes the associated folder for opening and saving files be the same *wrong* one as described in the previous section from inside Idle, when the Shell Window has foreground focus.

Alternate approaches to starting Idle are discussed in the operating specific appendix sections.

1.9.3 The Classic First Program

Have Idle started as in the previous section, so some Python file has the foreground focus.

Open a new window by going to the *File* menu and selecting *New File*. This gives you a rather conventional text editing window with the mouse available, ability to cut and paste, plus a few special options for Python.

Type (or paste) the following into the *editor* window (not the Shell Window):

```
print('Hello world!')
```

Save the file with the menu sequence *File* → *Save*, and then enter the file name `hello.py`. Python program files should always be given a name ending in `.py`. If you give no extension, `.py` is assumed. You can also enter it explicitly.

There are also the options *File* → *Save As* and *File* → *Save Copy As*. Both save a copy to a different name, but only *File* → *Save As* changes the name of the file you are editing in Idle.

Warning: It is the contents of the foreground Idle window that get saved. You are unlikely to mean to save the contents of the Shell window, but it is easy for that window to have the focus when you mean to save a program in an edit window.

Syntax coloring: If you look in the editor, you should see that your text is color coded. The editor will color different parts of Python syntax in special colors.

Now that you have a complete, saved program, choose *Run* → *Run Module*. You should see the program run in the Python Shell window.

You just wrote and executed a program. Unlike when you use the shell, this code is saved to a file in your Python folder. You can open and execute the file any time you want. (In Idle, use *File* → *Open*.)

To the interpreter, a program source file is a Python *module*. We will tend to use the more general term: a program file is a module. Note the term from the menu when running the program.

Distinguish program code from Shell text: It is easy to confuse the Shell and the Edit windows. Make sure you keep them straight. The `hello.py` program is just the line

```
print('Hello world!')
```

that you typed into the edit window and saved. When you ran the program in Idle, you saw results in the Shell. First came the Restart notice, the one-line output from the program saying hello, and a further Shell prompt:

```
>>> ===== RESTART =====
>>>
Hello world!
>>>
```

You could also have typed this single printing line directly in the Shell in response to a Shell prompt. When you see `>>>`, you could enter the `print` function and get the exchange between you and the Shell:

```
>>> print('Hello world')
Hello world!
>>>
```

Warning: The three lines above are *not* a program you could save in a file and run. This is just an exchange in the *Shell*, with its `>>>` prompts, individual line to execute, and the response. Again, just the single line, with no `>>>`,

```
print('Hello world!')
```

entered into the *Edit* window forms a program you can save and run. The `>>>` prompts have no place in a Python program file.

We will shortly get to more interesting many-statement programs, where it is much more convenient to use the Edit window than the Shell!

The general assumption in this Tutorial will be that programs are run in Idle and the Idle Shell is the Shell referred to. It will be explicitly stated when you should run a program directly from the operating system.

In general it is also fine to run our programs from a cmd console (Windows) or terminal (Mac) or from a different development environment.

Warning: Running the text based example programs in Windows, like `birthday2.py`, by selecting them to run from a file folder, will *not* work well: The program ends and the window automatically closes before you can see the final output.

On a Mac you get to explicitly close the verbose terminal window created when you run a Python program from the Finder.

1.9.4 Program Documentation String

The hello program above is self evident, and shows how short and direct a program can be (unlike other languages such as Java). Still, right away, get used to documenting a program. Python has a special feature: If the beginning of a program is just a quoted string, that string is taken to be the program's *documentation string*. Open the example file `hello2.py` in the Edit window:

```
'''A very simple program,
showing how short a Python program can be!
```

```
Authors: ___, __
'''
print('Hello world!')  #This is a stupid comment after the # mark
```

Most commonly, the initial documentation goes on for several lines, so a multi-line string delimiter is used (the triple quotes). Just for completeness of illustration in this program, another form of comment is also shown, a comment that starts with the symbol # and extends to the end of the line. The Python interpreter completely ignores this form of comment. Such a comment should only be included for better human understanding. Avoid making comments that do not really aid human understanding. (Do what I say, not what I did above.) Good introductory comment strings and appropriate names for the parts of your programs make fewer # symbol comments needed!

Run the program and see the documentation and comment make no difference in the result.

1.9.5 Screen Layout

Of course you can arrange the windows on your computer screen any way that you like. A suggestion is to display the combination of the editor to write, the shell to run, and the tutorial to follow along.

There is an alternative to maximization for the Idle editor window: If you want it to go top to bottom of the screen but not widen, you can toggle that state with *Options -> Zoom Height* or the keyboard shortcut shown beside it.

1.10 Input and Output

1.10.1 The input Function

The hello program of *The Classic First Program* (page 23) always does the same thing. This is not very interesting. Programs are only going to be reused if they can act on a variety of data. One way to get data is directly from the user. Modify the hello.py program as follows in the editor, and save it with *File -> Save As...*, using the name hello_you.py.

```
person = input('Enter your name: ')
print('Hello', person)
```

Run the program. In the Shell you should see

```
Enter your name:
```

Make sure the typing cursor is in the Shell window, at the end of this line. Then follow the instruction (and press Enter). After you type your response, you can see that the program has taken in the line you typed. That is what the built-in function `input` does: First it prints the string you give as a parameter (in this case 'Enter your name: '), and then it waits for a line to be typed in, and returns the string of characters you typed. In the `hello_you.py` program this value is assigned to the variable `person`, for use later.

The parameter inside the parentheses after `input` is important. It is a *prompt*, prompting you that keyboard input is expected at that point, and hopefully indicating what is being requested. Without the prompt, the user would not know what was happening, and the computer would just sit there waiting!

Open the example program, `interview.py`. Before running it (with any made-up data), see if you can figure out what it will do:

```
'''Illustrate input and print.'''

applicant = input("Enter the applicant's name: ")
interviewer = input("Enter the interviewer's name: ")
```

```
time = input("Enter the appointment time: ")
print(interviewer, "will interview", applicant, "at", time)
```

The statements are executed in the order they appear in the text of the program: *sequentially*. This is the simplest way for the execution of the program to flow. You will see instructions later that alter that natural flow.

If we want to reload and modify the `hello_you.py` program to put an exclamation point at the end, you could try:

```
person = input('Enter your name: ')
print('Hello', person, '!')
```

Run it and you see that it is not spaced right. There should be no space after the person's name, but the default behavior of the print function is to have each field printed separated by a space. There are several ways to fix this. You should know one. Think about it before going on to the next section. Hint: ³

1.10.2 Print with Keyword Parameter `sep`

One way to put punctuation but no space after the person in `hello_you.py` is to use the plus operator, `+`. Another approach is to change the default *separator* between fields in the print function. This will introduce a new syntax feature, *keyword parameters*. The print function has a keyword parameter named `sep`. If you leave it out of a call to print, as we have so far, it is set equal to a space by default. If you add a final field, `sep=''`, in the print function in `hello_you.py`, you get the following example file, `hello_you2.py`:

```
'''Hello to you!  Illustrates sep with empty string in print.
'''

person = input('Enter your name: ')
print('Hello ', person, '!', sep='')
```

Try the program.

Keyword parameters must be listed at the end of the parameter list. They have the keyword name, followed by an equal sign, before the value being given. We will see another example shortly.

It is a standard Python convention that when giving a keyword and value, the equal sign has *no* space on either side. (This is the only place you are not encouraged to set off an equal sign with spaces.)

1.10.3 Numbers and Strings of Digits

Consider the following problem: Prompt the user for two numbers, and then print out a sentence stating the sum. For instance if the user entered 2 and 3, you would print 'The sum of 2 and 3 is 5.'

You might imagine a solution like the example file `addition1.py`, shown below. There is a problem. Can you figure it out before you try running it? Hint: ⁴

```
'''Error in addition from input.'''

x = input("Enter a number: ")
y = input("Enter a second number: ")
print('The sum of ', x, ' and ', y, ' is ', x+y, '.', sep='') #error
```

End up running it in any case.

We do not want string concatenation, but integer addition. We need integer operands. Briefly mentioned in *Whirlwind Introduction To Types and Functions* (page 13) was the fact that we can use type names as functions to convert types.

³ The `+` operation on strings adds no extra space.

⁴ The input function produces values of string type.

One approach would be to do that. Further variable names are also introduced in the example `addition2.py` file below to emphasize the distinctions in types. Read and run:

```
'''Conversion of strings to int before addition'''

xString = input("Enter a number: ")
x = int(xString)
yString = input("Enter a second number: ")
y = int(yString)
print('The sum of ', x, ' and ', y, ' is ', x+y, '.', sep='')
```

Needing to convert string input to numbers is a common situation, both with keyboard input and later in web pages. While the extra variables above emphasized the steps, it is more concise to write as in the variation in example file, `addition3.py`, doing the conversions to type `int` immediately:

```
'''Two numeric inputs, with immediate conversion'''

x = int(input("Enter a number: "))
y = int(input("Enter a second number: "))
print('The sum of ', x, ' and ', y, ' is ', x+y, '.', sep='')
```

The simple programs so far have followed a basic *programming pattern*: input-calculate-output. Get all the data first, calculate with it second, and output the results last. The pattern sequence would be even clearer if we explicitly create a named result variable in the middle, as in `addition4.py`

```
'''Two numeric inputs, explicit sum'''

x = int(input("Enter an integer: "))
y = int(input("Enter another integer: "))
sum = x+y
print('The sum of ', x, ' and ', y, ' is ', sum, '.', sep='')
```

We will see more complicated patterns, which involve repetition, in the future.

Exercise for Addition

Write a version, `add3.py`, that asks for three numbers, and lists all three, and their sum, in similar format to `addition4.py` displayed above.

Exercise for Quotients

Write a program, `quotient.py`, that prompts the user for two integers, and then prints them out in a sentence with an integer division problem in a form just like

```
The quotient of 14 and 3 is 4 with a remainder of 2
```

Review *Division and Remainders* (page 15) if you forget the integer division or remainder operator.

1.10.4 String Format Operation

In grade school quizzes a common convention is to use fill-in-the blanks. For instance,

Hello ____!

and you can fill in the name of the person greeted, and combine given text with a chosen insertion. *We use this as an analogy*: Python has a similar construction, better called fill-in-the-braces. There is a particular operation on strings

called `format`, that makes substitutions into places enclosed in braces. For instance the example file, `hello_you3.py`, creates and prints the same string as in `hello_you2.py` from the previous section:

```
'''Hello to you!  Illustrates format with {} in print.
'''

person = input('Enter your name: ')
greeting = 'Hello, {}'.format(person)
print(greeting)
```

There are several new ideas here!

First *method* calling syntax for *objects* is used. You will see this very important modern syntax in more detail at the beginning of the next chapter in *Object Orientation* (page 73). All data in Python are objects, including strings. Objects have a special syntax for functions, called *methods*, associated with the *particular type of object*. In particular `str` objects have a method called `format`. The syntax for methods has the object followed by a period followed by the method name, and any further parameters in parentheses.

object.methodname (parameters)

In the example above, the object is the string `'Hello {}'`. The method is named `format`. There is one further parameter, `person`.

The string for the `format` method has a special form, with braces embedded. Places where braces are embedded are replaced by the value of an expression taken from the parameter list for the `format` method. There are many variations on the syntax between the braces. In this case we use the syntax where the first (and only) location in the string with braces has a substitution made from the first (and only) parameter.

In the code above, this new string is assigned to the identifier `greeting`, and then the string is printed.

The identifier `greeting` was introduced to break the operations into a clearer sequence of steps. However, since the value of `greeting` is only referenced once, it can be eliminated with the more concise version:

```
person = input('Enter your name: ')
print('Hello {}'.format(person))
```

Consider the interview program. Suppose we want to add a period at the end of the sentence (with no space before it). One approach would be to combine everything with plus signs. Another way is printing with keyword `sep=''`. Another approach is with string formatting. Using our grade school analogy, the idea is to fill in the blanks in

_____ will interview _____ at _____.

There are multiple places to substitute, and the format approach can be extended to multiple substitutions: Each place in the format string where there is `' {} '`, the `format` operation will substitute the value of the *next* parameter in the format parameter list.

Run the example file `interview2.py`, and check that the results from all three methods match.

```
'''Compare print with concatenation and with format string.'''

applicant = input("Enter the applicant's name: ")
interviewer = input("Enter the interviewer's name: ")
time = input("Enter the appointment time: ")
print(interviewer + ' will interview ' + applicant + ' at ' + time + '.')
print(interviewer, ' will interview ', applicant, ' at ', time, '.', sep='')
print('{} will interview {} at {}'.format(interviewer, applicant, time))
```

Sometimes you want a single string, but not just for printing. You can combine pieces with the `+` operator, but then all pieces must be strings or *explicitly converted to strings*. An advantage of the `format` method is that it will convert types to string automatically, like the `print` function. Here is another variant of our addition sentence example, `addition4a.py`, using the `format` method.


```
'''Two numeric inputs, explicit sum'''

x = int(input("Enter an integer: "))
y = int(input("Enter another integer: "))
sum = x+y
sentence = 'The sum of {} and {} is {}'.format(x, y, sum)
print(sentence)
```

Conversion to strings was not needed in `interview2.py`. (Everything started out as a string.) In `addition4a.py`, however, the automatic conversion of the integers to strings is useful.

So far there is no situation that requires a format string instead of using other approaches. Sometimes a format string provides a shorter and simpler expression. Except where specifically instructed in an exercise for practice, use whatever approach to combining strings and data that you like. There are many elaborations to the fields in braces to control formatting. We will look at one later, *String Formats for Float Precision* (page 63), where format strings are particularly useful.

A technical point: Since braces have special meaning in a format string, there must be a special rule if you want braces to actually be included in the final *formatted* string. The rule is to double the braces: `'{{' and '}}'`. The example code `formatBraces.py`, shown below, makes `setStr` refer to the string `'The set is {5, 9}'`. The initial and final doubled braces in the format string generate literal braces in the formatted string:

```
'''Illustrate braces in a formatted string.'''

a = 5
b = 9
setStr = 'The set is {{{}, {}}}.'.format(a, b)
print(setStr)
```

This kind of format string depends directly on the order of the parameters to the format method. There is another approach with a dictionary, that was used in the first sample program, `madlib.py`, and will be discussed more in *Dictionaries and String Formatting* (page 44). The dictionary approach is probably the best in many cases, but the count-based approach is an easier start, particularly if the parameters are just used once, in order.

Optional elaboration with explicitly numbered entries Imagine the format parameters numbered in order, starting from 0. In this case 0, 1, and 2. The number of the parameter position may be included inside the braces, so an alternative to the last line of `interview2.py` is (added in example file `interview3.py`):

```
print('{0} will interview {1} at {2}'.format(interviewer, applicant, time))
```

This is more verbose than the previous version, with no obvious advantage. However, if you desire to use some of the parameters more than once, then the approach with the numerical identification with the parameters is useful. Every place the string includes `'{0}'`, the format operation will substitute the value of the initial parameter in the list. Wherever `'{1}'` appears, the next format parameter will be substituted...

Predict the results of the example file `arith.py` shown below, if you enter 5 and 6. Then check yourself by running it. In this case the numbers referring to the parameter positions are necessary. They are both repeated and used out of order:

```
'''Fancier format string example with
parameter identification numbers
-- useful when some parameters are used several times.'''

x = int(input('Enter an integer: '))
y = int(input('Enter another integer: '))
formatStr = '{0} + {1} = {2}; {0} * {1} = {3}.'
equations = formatStr.format(x, y, x+y, x*y)
print(equations)
```

Try the program with other data.

Now that you have a few building blocks, you will see more exercises where you need to start to do creative things. You are encouraged to go back and reread *Learning to Problem-Solve* (page 6).

Addition Format Exercise

Write a version of *Exercise for Addition* (page 27), `add3f.py`, that uses the string format method to construct the same final string as before.

Quotient Format Exercise

Write a version of the quotient problem in *Exercise for Quotients* (page 27), `quotientformat.py`, that uses the string format method to construct the same final string as before. Again be sure to give a full sentence including the initial numbers and both the integer quotient and the remainder.

1.11 Defining Functions of your Own

1.11.1 Syntax Template Typography

When new Python syntax is introduced, the usual approach will be to give both specific examples and general templates. In general templates for Python syntax the typeface indicates the the category of each part:

Typeface	Meaning	Example
Typewriter font	Text to be written <i>verbatim</i>	<code>sep=' '</code>
<i>Emphasized</i>	A place where you can use an arbitrary expression.	<i>integerValue</i>
Bold	A place where you can use an arbitrary identifier.	variable-Name
Normal text	A description of what goes in that position, without giving explicit syntax	A digit, 0-9

A more complete example of using this typography with several parts would be a description of an assignment statement:

variableName = *someExpression*

with an arbitrary identifier, the specific symbol =, and an expression.

I try to make the parts that are not verbatim to be descriptive of the expected use.

I will use these conventions shortly in the discussion of function syntax, and will continue to use the conventions throughout the tutorial.

1.11.2 A First Function Definition

If you know it is the birthday of a friend, Emily, you might tell those gathered with you to sing “Happy Birthday to Emily”.

We can make Python display the song. *Read*, and run if you like, the example program `birthday1.py`:

```
print("Happy Birthday to you!")
print("Happy Birthday to you!")
print("Happy Birthday, dear Emily.")
print("Happy Birthday to you!")
```

You would probably not repeat the whole song to let others know what to sing. You would give a request to sing via a descriptive name like “Happy Birthday to Emily”.

In Python we can also give a name like `happyBirthdayEmily`, and associate the name with whole song by using a *function definition*. We use the Python `def` keyword, short for *define*.

Read for now:

```
1 def happyBirthdayEmily(): #program does nothing as written
2     print("Happy Birthday to you!")
3     print("Happy Birthday to you!")
4     print("Happy Birthday, dear Emily.")
5     print("Happy Birthday to you!")
```

There are several parts of the syntax for a function definition to notice:

Line 1: The *heading* contains `def`, the name of the function, parentheses, and finally a colon. A more general syntax is

```
def function_name() :
```

Lines 2-5: The remaining lines form the function *body* and are indented by a consistent amount. (The exact amount is not important to the interpreter, though 2 or 4 spaces are common conventions.)

The whole definition does just that: *defines* the meaning of the name `happyBirthdayEmily`, but it does not do anything else yet - for example, the definition itself does not make anything be printed yet. This is our first example of altering the order of execution of statements from the normal sequential order.

Note: The statements in the function *definition* are *not* executed as Python first passes over the lines.

The code above is in example file `birthday2.py`. Load it in Idle and execute it from there. *Nothing* should happen visibly. This is just like defining a variable: Python just remembers the function definition for future reference.

After Idle finished executing a program, however, its version of the Shell remembers function definitions from the program.

In the Idle *Shell* (not the editor), enter

```
happyBirthdayEmily
```

The result probably surprises you! When you give the Shell an identifier, it tells you its *value*. Above, without parentheses, it identifies the function code as the value (and gives a location in memory of the code). Now try the name in the Idle Shell with *parentheses* added:

```
happyBirthdayEmily()
```

The parentheses tell Python to *execute* the named function rather than just *refer* to the function. Python goes back and looks up the definition, and only then, executes the code inside the function definition. The term for this action is a *function call* or function *invocation*.

Note: In the function *call* there is no `def`, but there is the function name followed by parentheses.

```
function_name()
```

In many cases we will use a feature of program execution in Idle: that after program execution is completed, the Idle Shell still remembers functions defined in the program. This is not true if you run a program by selecting it directly in the operating system.

Look at the example program `birthday3.py`. See it just adds two more lines, *not* indented. Can you guess what it does? Try it:

```
1  '''Function definition and invocation.'''
2
3  def happyBirthdayEmily():
4      print("Happy Birthday to you!")
5      print("Happy Birthday to you!")
6      print("Happy Birthday, dear Emily.")
7      print("Happy Birthday to you!")
8
9  happyBirthdayEmily()
10 happyBirthdayEmily()
```

The *execution* sequence is different from the *textual* sequence:

1. Lines 3-7: Python starts from the top, reading and remembering the definition. The definition ends where the indentation ends. (The code also shows a blank line there, but that is only for humans, to emphasize the end of the definition.)
2. Line 9: this is not indented inside any definition, so the interpreter executes it directly, calling `happyBirthdayEmily()` while remembering where to return.
3. Lines 3-7: The code of the function is executed for the first time, printing out the song.
4. End of line 9: Back from the function call. continue on.
5. Line 10: the function is called again while this location is remembered.
6. Lines 3-7: The function is executed again, printing out the song again.
7. End of line 10: Back from the function call, but at this point there is nothing more in the program, and execution stops.

Functions alter execution order in several ways: by statements not being executed as the definition is first read, and then when the function is called during execution, jumping to the function code, and back at the the end of the function execution.

If it also happens to be Andre's birthday, we might define a function `happyBirthdayAndre`, too. Think how to do that before going on

1.11.3 Multiple Function Definitions

Here is example program `birthday4.py` where we add a function `happyBirthdayAndre`, and call them both. Guess what happens, and then try it:

```
'''Function definitions and invocation.'''

def happyBirthdayEmily():
    print("Happy Birthday to you!")
    print("Happy Birthday to you!")
    print("Happy Birthday, dear Emily.")
    print("Happy Birthday to you!")

def happyBirthdayAndre():
    print("Happy Birthday to you!")
```

```

print("Happy Birthday to you!")
print("Happy Birthday, dear Andre.")
print("Happy Birthday to you!")

happyBirthdayEmily()
happyBirthdayAndre()

```

Again, everything is definitions except the last two lines. They are the only lines executed directly. The calls to the functions *happen* to be in the same order as their definitions, but that is arbitrary. If the last two lines were swapped, the order of operations would change. Do swap the last two lines so they appear as below, and see what happens when you execute the program:

```

happyBirthdayAndre()
happyBirthdayEmily()

```

Functions that you write can also call other functions you write. It is a good convention to have the main action of a program be in a function for easy reference. The example program `birthday5.py` has the two Happy Birthday calls inside a final function, `main`. Do you see that this version accomplishes the same thing as the last version? Run it. :

```

1  '''Function definitions and invocation.'''
2
3  def happyBirthdayEmily():
4      print("Happy Birthday to you!")
5      print("Happy Birthday to you!")
6      print("Happy Birthday, dear Emily.")
7      print("Happy Birthday to you!")
8
9  def happyBirthdayAndre():
10     print("Happy Birthday to you!")
11     print("Happy Birthday to you!")
12     print("Happy Birthday, dear Andre.")
13     print("Happy Birthday to you!")
14
15  def main():
16      happyBirthdayEmily()
17      happyBirthdayAndre()
18
19  main()

```

If we want the program to do anything automatically when it is runs, we need one line outside of definitions! The final line is the only one directly executed, and it calls the code in `main`, which in turn calls the code in the other two functions.

Detailed order of execution:

1. Lines 3-17: Definitions are read and remembered
2. Line 19: The only statement outside definitions, is executed directly. This location is remembered as `main` is executed.
3. Line 15: Start on `main`
4. Line 16. This location is remembered as execution jumps to `happyBirthdayEmily`
5. Lines 3-7 are executed and Emily is sung to.
6. Return to the end of Line 16: Back from `happyBirthdayEmily` function call
7. Line 17: Now `happyBirthdayAndre` is called as this location is remembered.
8. Lines 9-13: Sing to Andre

9. Return to the end of line 17: Back from `happyBirthdayAndre` function call, done with `main`

10. Return to the end of line 19: Back from `main`; at the end of the program

There is one practical difference from the previous version. After execution, if we want to give another round of Happy Birthday to *both* persons, we only need to enter one further call in the *Shell* to:

```
main()
```

As a simple example emphasizing the significance of a line being indented, guess what the example file `order.py` does, and run it to check:

```
def f():
    print('In function f')
    print('When does this print?')
f()
```

Modify the file so the second print function is **out**dentented like below. What should happen now? Try it:

```
def f():
    print('In function f')
print('When does this print?')
f()
```

The lines indented inside the function definition are *remembered* first, and only executed when the function `f` is invoked at the end. The lines outside any function definition (not indented) are executed in order of appearance.

Poem Function Exercise

Write a program, `poem.py`, that defines a function that prints a *short* poem or song verse. Give a meaningful name to the function. Have the program end by calling the function three times, so the poem or verse is repeated three times.

1.11.4 Function Parameters

As a young child, you probably heard Happy Birthday sung to a couple of people, and then you could sing to a new person, say Maria, without needing to hear the whole special version with Maria's name in it word for word. You had the power of *abstraction*. With examples like the versions for Emily and Andre, you could figure out what change to make it so the song could be sung to Maria!

Unfortunately, Python is not that smart. It needs explicit rules. If you needed to explain *explicitly* to someone how Happy Birthday worked in general, rather than just by example, you might say something like this:

First you have to be *given* a person's name. Then you sing the song with the person's name inserted at the end of the third line.

Python works something like that, but with its own syntax. The term “person's name” serves as a stand-in for the actual data that will be used, “Emily”, “Andre”, or “Maria”. This is just like the association with a variable name in Python. “person's name” is not a legal Python identifier, so we will use just `person` as this stand-in.

The function definition indicates that the variable name `person` will be used inside the function by inserting it between the parentheses of the definition. Then in the body of the definition of the function, `person` is used in place of the real data for any specific person's name. Read and then run example program `birthday6.py`:

```
1 '''Function with parameter.'''
2
3 def happyBirthday(person):
4     print("Happy Birthday to you!")
5     print("Happy Birthday to you!")
```

```

6     print("Happy Birthday, dear " + person + ".")
7     print("Happy Birthday to you!")
8
9     happyBirthday('Emily')
10    happyBirthday('Andre')

```

In the definition heading for `happyBirthday`, `person` is referred to as a *formal parameter*. This variable name is a placeholder for the real name of the person being sung to.

The last two lines of the program, again, are the only ones outside of definitions, so they are the only ones executed directly. There is now an actual name between the parentheses in the function calls. The value between the parentheses here in the function call is referred to as an *argument* or *actual parameter* of the function call. The argument supplies the actual data to be used in the function execution. When the call is made, Python does this by associating the formal parameter name `person` with the actual parameter data, as in an assignment statement. In the first call, this actual data is `'Emily'`. We say the actual parameter value is *passed* to the function.⁵

The execution in greater detail:

1. Lines 3-7: Definition remembered
2. Line 9: Call to `happyBirthday`, with actual parameter `'Emily'`.
3. Line 3: `'Emily'` is passed to the function, so `person = 'Emily'`.
4. Lines 4-7: The song is printed, with `'Emily'` used as the value of `person` in line 4: printing

```
Happy Birthday, dear Emily.
```

5. End of line 9 after returning from the function call
6. Line 10: Call to `happyBirthday`, this time with actual parameter `'Andre'`
7. Line 3: `'Andre'` is passed to the function, so `person = 'Andre'`.
8. Lines 4-7: The song is printed, with `'Andre'` used as the value of `person` in line 4: printing

```
Happy Birthday, dear Andre.
```

9. End of line 10 after returning from the function call, and the program is over.

Note: Be sure you completely understand `birthday6.py` and the sequence of execution! It illustrates extremely important ideas that many people miss the first time!

It is essential to understand the difference between

1. *Defining* a function (lines 3-7) with the `def` heading including *formal* parameter names, where the code is merely instructions to be remembered, not acted on immediately.
2. *Calling* a function with *actual* parameter values to be substituted for the formal parameters and have the function code actually *run* when the instruction containing the call is run. Also note that the function can be called multiple times with different expressions as the actual parameters (line 9 and again in line 10).

The beauty of this system is that the same function definition can be used for a call with a different actual parameter, and then have a different effect. The value of the formal parameter `person` is used in the third line of `happyBirthday`, to put in whatever actual parameter value was given.

Note: This is the power of *abstraction*. It is one application of the most important principal in programming. Rather than have a number of separately coded parts with only slight variations, see where it is appropriate to combine them

⁵ I have given the explicit terminology “formal parameter” and “actual parameter”. In various places you may see either of these terms replaced by just “parameter” or maybe “argument”. In that case you must determine from context which is being discussed: a definition and formal parameter or a function call and an actual parameter.

using a function whose parameters refer to the parts that are different in different situations. Then the code is written to be simultaneously appropriate for the separate specific situations, with the substitutions of the right parameter values.

You can go back to having a main function again, and everything works. Run `birthday7.py`:

```
'''Function with parameter called in main'''

def happyBirthday(person):
    print("Happy Birthday to you!")
    print("Happy Birthday to you!")
    print("Happy Birthday, dear " + person + ".")
    print("Happy Birthday to you!")

def main():
    happyBirthday('Emily')
    happyBirthday('Andre')

main()
```

In `birthday6.py`, the function calls in lines 9 and 10 were outside any function definition, so they did actually lead to immediate execution of the function. In `birthday7.py` the calls to `happyBirthday` are inside another function definition (`main`), so they are not actually run until the function `main` is run (from the last line, outside any function).

See *Birthday Function Exercise* (page 37).

We can combine function parameters with user input, and have the program be able to print Happy Birthday for anyone. Check out the main method and run `birthday_who.py`:

```
1  '''User input supplies function parameter'''
2
3  def happyBirthday(person):
4      print("Happy Birthday to you!")
5      print("Happy Birthday to you!")
6      print("Happy Birthday, dear " + person + ".")
7      print("Happy Birthday to you!")
8
9  def main():
10     userName = input("Enter the Birthday person's name: ")
11     happyBirthday(userName)
12
13  main()
```

This last version illustrates several important ideas:

1. There are more than one way to get information into a function:
 - (a) Have a value passed in through a parameter (from line 10 to line 3).
 - (b) Prompt the user, and obtain data from the keyboard (line 11).
2. It is a good idea to separate the *internal* processing of data from the *external* input from the user by the use of distinct functions. Here the user interaction is in `main`, and the data is manipulated in `happyBirthday`.
3. In the first examples of actual parameters, we used literal values. In general an actual parameter can be an expression. The expression is evaluated before it is passed in the function call. One of the simplest expressions is a plain variable name, which is evaluated by replacing it with its associated value. Since it is only the value of the actual parameter that is passed, not any variable name, there is *no need* to have a variable name used in an actual parameter match a formal parameter name. (Here we have the value of `userName` in `main` becoming the value of `person` in `happyBirthday`.)

Now that we have nested function calls, it is worth looking further at tracebacks from execution errors. If I add a line to `main` in `birthday7.py`:

```
happyBirthday(2)
```

as in example file `birthdayBad.py`, and then run it, you get something close to:

Traceback (most recent call last):

File “/hands-on/./examples/birthdayBad.py”, line 15, in <module>

main()

File “/hands-on/./examples/birthdayBad.py”, line 13, in main

happyBirthday(2)

File “/hands-on/./examples/birthdayBad.py”, line 6, in happyBirthday

print(“Happy Birthday, dear ” + person + ”.”)

TypeError: Can’t convert ‘int’ object to str implicitly

Your file folder is probably different than `/hands-on/examples`. The last three lines are most important, giving the line number where the error was detected, the text of the line in question, and a description of what problem was found. Often that is all you need to look at, but this example illustrates that the *genesis* of the problem may be far away from the line where the error was *detected*. Going further up the traceback, you find the sequence of function calls that led to the line where the error was detected. You can see that in `main` I call `happyBirthday` with the bad parameter, 2.

Birthday Function Exercise

Make your own further change to `birthday7.py` and save it as `birthdayMany.py`: Add a function call (but *not* another function *definition*), so Maria gets a verse, in addition to Emily and Andre. Also print a blank line between verses. (You may *either* do this by adding a print line to the function definition, *or* by adding a print line between all calls to the function.)

1.11.5 Multiple Function Parameters

A function can have more than one parameter in a parameter list separated by commas. Here the example program `addition5.py` changes example program `addition4a.py`, using a function to make it easy to display many sum problems. Read and follow the code, and then run:

```
'''Display any number of sum problems with a function.
Handle keyboard input separately.
'''

def sumProblem(x, y):
    sum = x + y
    sentence = 'The sum of {} and {} is {}'.format(x, y, sum)
    print(sentence)

def main():
    sumProblem(2, 3)
    sumProblem(1234567890123, 535790269358)
    a = int(input("Enter an integer: "))
    b = int(input("Enter another integer: "))
    sumProblem(a, b)

main()
```

The actual parameters in the function call are evaluated left to right, and then these values are associated with the formal parameter names in the function definition, also left to right. For example a function call with actual parameters, `f(actual1, actual2, actual3)`, calling a function `f` with definition heading:

```
def f(formal1, formal2, formal3):
```

acts approximately as if the first lines executed inside the called function `f` were

```
formal1 = actual1
formal2 = actual2
formal3 = actual3
```

Functions provide extremely important functionality to programs, allowing tasks to be defined once and performed repeatedly with different data. It is essential to see the difference between the **formal** parameters used to describe what is done inside the function definition (like `x` and `y` in the definition of `sumProblem`) and the **actual** parameters (like `2` and `3` or `1234567890123` and `535790269358`) which *substitute* for the formal parameters when the function is actually executed. The main method above uses three different sets of actual parameters in the three calls to `sumProblem`.

Quotient Function Exercise

The example `addition5.py` is a modification of `addition4a.py`, putting the arithmetic problem into a function and then calling the function several times with different parameters. Similarly modify `quotientformat.py` from *Quotient Format Exercise* (page 30) and save it as `quotientProb.py`. You should create a function `quotientProblem` with numerical parameters. Like in all the earlier versions, it should print a full sentence containing the inputs, quotient, and remainder. The `main` method in the new program should test the `quotientProblem` function on several sets of literal values, and also test the function with input from the user.

1.11.6 Returned Function Values

You probably have used mathematical functions in algebra class: They all had calculated values associated with them. For instance if you defined

$$f(x)=x^2$$

then it follows that `f(3)` is 3^2 , and `f(3)+f(4)` is $3^2 + 4^2$

Function calls in expressions get replaced during evaluation by the value of the function.

The corresponding definition and examples in Python would be the following, taken from example program `return1.py`. Read and run:

```
'''A simple function returning a value, used in an expression'''

def f(x):
    return x*x

print(f(3))
print(f(3) + f(4))
```

The new Python syntax is the *return statement*, with the word `return` followed by an expression. Functions that return values can be used in expressions, just like in math class. When an expression with a function call is evaluated, the function call is effectively replaced temporarily by its returned value. Inside the Python function definition, the value to be returned is given by the expression in the `return` statement.

After the function `f` finishes executing from inside

```
print(f(3))
```

it is as if the statement temporarily became

```
print(9)
```

and similarly when executing

```
print(f(3) + f(4))
```

the interpreter first evaluates `f(3)` and effectively replaces the call by the returned result, 9, as if the statement temporarily became

```
print(9 + f(4))
```

and then the interpreter evaluates `f(4)` and effectively replaces the call by the returned result, 16, as if the statement temporarily became

```
print(9 + 16)
```

resulting finally in 25 being calculated and printed.

Python functions can return any type of data, not just numbers, and there can be any number of statements executed before the return statement. Read, follow, and run the example program `return2.py`:

```
1  '''A function returning a string and using a local variable'''
2
3  def lastFirst(firstName, lastName):
4      separator = ', '
5      result = lastName + separator + firstName
6      return result
7
8  print(lastFirst('Benjamin', 'Franklin'))
9  print(lastFirst('Andrew', 'Harrington'))
```

The code above has a new feature, variables `separator` and `result` are given a value inside the function, but `separator` and `result` are *not* among the formal parameters. The assignments work as you would expect here. More on this shortly, in *Local Scope* (page 41).

Details of the execution:

1. Lines 3-6: Remember the definition
2. Line 8: call the function, remembering where to return
3. Line 3: pass the parameters: `firstName = 'Benjamin'; lastName = 'Franklin'`
4. Line 4: Assign the variable `separator` the value `', '`
5. Line 5: Assign the variable `result` the value of `lastName + separator + firstName` which is `'Franklin' + ', ' + 'Benjamin'`, which evaluates to `'Franklin, Benjamin'`
6. Line 6: Return `'Franklin, Benjamin'`
7. Line 8: Use the value returned from the function call so the line effectively becomes `print('Franklin, Benjamin')`, so print it.
8. Line 9: call the function with the new actual parameters, remembering where to return
9. Line 3: pass the parameters: `firstName = 'Andrew'; lastName = 'Harrington'`
10. Lines 4-6: ... calculate and return `'Harrington, Andrew'`
11. Line 9: Use the value returned by the function and print `'Harrington, Andrew'`

Compare `return2.py` and `addition5.py`, from the previous section. Both use functions. Both print, but where the printing *is done* differs. The function `sumProblem` prints directly inside the function and returns nothing explicitly. On the other hand `lastFirst` does not print anything but returns a string. The caller gets to decide what to do with the string, and above it is printed in the main program.

Open `addition5.py` again, and introduce a *common mistake*. Change the last line of the function `main` inserting `print`, so it says

```
print(sumProblem(a, b))
```

Then try running the program. The desired printing is actually done inside the function `sumProblem`. You introduced a statement to print what `sumProblem` *returns*. Although `sumProblem` returns nothing *explicitly*, Python does make every function return something. If there is nothing explicitly returned, the special value `None` is returned. You should see that in the program's Shell output. This is a fairly common error.

Warning: If you see a 'None' in your printed output where you do not expect it, it is likely that you have printed the return value of a function that did not return anything explicitly!

In general, functions should do a single thing. You can easily combine a sequence of functions, and you have more flexibility in the combinations if each does just one unified thing. The function `sumProblem` in `addition5.py` does two things: It creates a sentence, and prints it. If that is all you have, you are out of luck if you want to do something different with the sentence string. A better way is to have a function that just creates the sentence, and returns it for whatever further use you want. Printing is one possibility, done in `addition6.py`:

```
'''Display a sum problems with a function returning a string,
not printing directly.
'''

def sumProblemString(x, y):
    sum = x + y
    return 'The sum of {} and {} is {}'.format(x, y, sum)

def main():
    print(sumProblemString(2, 3))
    print(sumProblemString(1234567890123, 535790269358))
    a = int(input("Enter an integer: "))
    b = int(input("Enter another integer: "))
    print(sumProblemString(a, b))

main()
```

Quotient String Return Exercise

Create `quotientReturn.py` by modifying `quotientProb.py` in *Quotient Function Exercise* (page 38) so that the program accomplishes the same thing, but everywhere change the `quotientProblem` function into one called `quotientString` that merely *returns* the string rather than printing the string directly. Have the `main` function print the result of each call to the `quotientString` function.

1.11.7 Two Roles: Writer and Consumer of Functions

The remainder of this section covers finer points about functions that you might skip on a first reading.

We are only doing tiny examples so far to get the basic idea of functions. In much larger programs, functions are useful to manage complexity, splitting things up into logically related, modest sized pieces. Programmers are both

writers of functions and consumers of the other functions called inside their functions. It is useful to keep those two roles separate:

The user of an already written function needs to know:

1. the name of the function
2. the order and meaning of parameters
3. what is returned or produced by the function

How this is accomplished is not relevant at this point. For instance, you use the work of the Python development team, calling functions that are built into the language. You need know the three facts about the functions you call. You do not need to know exactly *how* the function accomplishes its purpose.

On the other hand when you *write* a function you need to figure out exactly how to accomplish your goal, name relevant variables, and write your code, which brings us to the next section.

1.11.8 Local Scope

For the logic of writing functions, it is important that the writer of a function knows the names of variables inside the function. On the other hand, if you are only using a function, maybe written by someone unknown to you, you should not care what names are given to values used internally in the implementation of the function you are calling. Python enforces this idea with *local scope* rules: Variable names initialized and used inside one function are *invisible* to other functions. Such variables are called *local* variables. For example, an elaboration of the earlier program `return2.py` might have its `lastFirst` function with its local variable `separator`, but it might also have another function that defines a `separator` variable, maybe with a different value like `'\n'`. They would not conflict. They would be independent. This avoids lots of errors!

For example, the following code in the example program `badScope.py` causes an execution error. Read it and run it, and see:

```
'''program causing an error with an undefined variable'''

def main():
    x = 3
    f()

def f():
    print(x) # error: f does not know about the x defined in main

main()
```

We will fix this error below. The execution error message mentions “global name”. Names defined outside any function definition, at the “top-level” of your program are called *global*. They are a special case. They are discussed more in the next section.

If you do want local data from one function to go to another, define the called function so it includes parameters! Read and compare and try the program `goodScope.py`:

```
'''A change to badScope.py avoiding any error by passing a parameter'''

def main():
    x = 3
    f(x)

def f(x):
    print(x)

main()
```

With parameter passing, the parameter name `x` in the function `f` does not need to match the name of the actual parameter in `main`. The definition of `f` could just as well have been:

```
def f(whatever):  
    print(whatever)
```

1.11.9 Global Constants

If you define *global variables* (variables defined outside of any function definition), they are visible inside all of your functions. They have *global scope*. It is good programming practice to avoid defining global variables and instead to put your variables inside functions and explicitly pass them as parameters where needed. One common exception is constants: A *constant* is a name that you give a fixed data value to, by assigning a value to the name only in a single assignment statement. You can then use the name of the fixed data value in expressions later. A simple example program is `constant.py`:

```
'''Illustrate a global constant being used inside functions.'''  
  
PI = 3.14159265358979    # global constant -- only place the value of PI is set  
  
def circleArea(radius):  
    return PI*radius*radius    # use value of global constant PI  
  
def circleCircumference(radius):  
    return 2*PI*radius        # use value of global constant PI  
  
def main():  
    print('circle area with radius 5:', circleArea(5))  
    print('circumference with radius 5:', circleCircumference(5))  
  
main()
```

This example uses numbers with decimal points, discussed more in *Decimals, Floats, and Floating Point Arithmetic* (page 61). By convention, names for constants are all capital letters.

Issues with global variables do not come up if they are only used as constants.

Function names defined at the top-level also have global scope. This is what allows you to use one function you defined inside another function you define, like calling `circleArea` from inside `main`.

1.12 Dictionaries

1.12.1 Definition and Use of Dictionaries

In common usage, a *dictionary* is a collection of words matched with their definitions. Given a word, you can look up its definition. Python has a built in dictionary type called `dict` which you can use to create dictionaries with arbitrary definitions for character strings. It can be used for the common usage, as in a simple English-Spanish dictionary.

Look at the example program `spanish1.py` and run it.

```
"""A tiny English to Spanish dictionary is created,  
using the Python dictionary type dict.  
Then the dictionary is used, briefly.  
"""
```

```
spanish = dict()
spanish['hello'] = 'hola'
spanish['yes'] = 'si'
spanish['one'] = 'uno'
spanish['two'] = 'dos'
spanish['three'] = 'tres'
spanish['red'] = 'rojo'
spanish['black'] = 'negro'
spanish['green'] = 'verde'
spanish['blue'] = 'azul'

print(spanish['two'])
print(spanish['red'])
```

First an empty dictionary is created using `dict()`, and it is assigned the descriptive name `spanish`.

To refer to the definition for a word, you use the dictionary name, follow it by the word inside *square brackets*. This notation can either be used on the left-hand side of an assignment to make (or remake) a definition, or it can be used in an expression (as in the `print` functions), where its earlier definition is retrieved. For example,

```
spanish['hello'] = 'hola'
```

makes an entry in our `spanish` dictionary for `'hello'`, with definition `'hola'`.

```
print(spanish['red'])
```

retrieves the definition for `'red'`, which is `'rojo'`.

Since the Spanish dictionary is defined at the top-level, the variable name `spanish` is still defined after the program runs: After running the program, use `spanish` in the Shell to check out the translations of some more words, other than `'two'` and `'red'`.

Creating the dictionary is a well defined and quite different activity from the *use* of the dictionary at the end of the code, so we can use a functions to encapsulate the task of creating the dictionary, as in the example program `spanish2.py`, which gives the same result:

```
"""A tiny English to Spanish dictionary is created,
using the Python dictionary type dict.
Then the dictionary is used, briefly.
"""
```

```
def createDictionary():
    '''Returns a tiny Spanish dictionary'''
    spanish = dict()
    spanish['hello'] = 'hola'
    spanish['yes'] = 'si'
    spanish['one'] = 'uno'
    spanish['two'] = 'dos'
    spanish['three'] = 'tres'
    spanish['red'] = 'rojo'
    spanish['black'] = 'negro'
    spanish['green'] = 'verde'
    spanish['blue'] = 'azul'
    return spanish

def main():
    dictionary = createDictionary()
    print(dictionary['two'])
    print(dictionary['red'])
```

```
main()
```

This code illustrates several things about functions.

- First, like whole files, functions can have a documentation string immediately after the definition heading. It is a good idea to document the return value!
- The dictionary that is created is returned, but the local variable name in the function, `spanish`, is lost when the function terminates.
- To remember the dictionary returned to `main`, it needs a name. The name does not have to match the name used in `createDictionary`. The name `dictionary` is descriptive.

We could also use the dictionary more extensively. The example program `spanish2a.py` is the same as above except it has the following main method:

```
def main():
    dictionary = createDictionary()
    print('Count in Spanish: ' + dictionary['one'] + ', ' +
          dictionary['two'] + ', ' + dictionary['three'] + ', ...')
    print('Spanish colors: ' + dictionary['red'] + ', ' +
          dictionary['blue'] + ', ' + dictionary['green'] + ', ...')
```

Try it, and check that it makes sense.

Python dictionaries are actually more general than the common use of dictionaries. They do not have to associate words and their string definitions. They can associate many types of objects with some arbitrary object. The more general Python terminology for word and definition are *key* and *value*. Given a key, you can look up the corresponding value. The only restriction on the key is that it be an *immutable* type. This means that a value of the key's type cannot be changed internally after it is initially created. Strings and numbers are immutable. A dictionary is *mutable*: its value can be changed internally. (You can add new definitions to it!) We will see more mutable and immutable types later and explore more of the internal workings of data types.

Number Dictionary Exercise

Write a tiny Python program `numDict.py` that makes a dictionary whose keys are the words 'one', 'two', 'three', and 'four', and whose corresponding values are the numerical equivalents, 1, 2, 3, and 4 (of type `int`, not strings). Include code to test the resulting dictionary by referencing several of the definitions and printing the results.

(This dictionary illustrates simply that the values in a Python dictionary are not required to be strings.)

1.12.2 Dictionaries and String Formatting

At the end of the main function in `spanish2a.py` from the last section, two strings are constructed and printed. The expressions for the two strings include a sequence of literal strings concatenated with interspersed values from a dictionary. There is a much neater, more readable way to generate these strings. We will develop this in several steps. The first string could be constructed and printed as follows:

```
numberFormat = 'Count in Spanish: {one}, {two}, {three}, ...'
withSubstitutions = numberFormat.format(one='uno', two='dos', three='tres')
print(withSubstitutions)
```

There are several new ideas here!. We are using an alternate form of format string and format method parameters from those described in *String Format Operation* (page 27).

Note the form of the string assigned the name `numberFormat`: It has the English words for numbers in *braces* where we want the Spanish definitions substituted. (This is unlike in *String Format Operation* (page 27), where we had empty braces or a numerical index inside.)

As in *String Format Operation* (page 27), the second line uses *method* calling syntax. A reminder of the syntax for methods:

object.methodname (parameters)

has the object followed by a period followed by the method name, and further parameters in parentheses.

In the example above, the object is the string called `numberFormat`. The method is named `format`. The parameters in this case are all *keyword* parameters. You have already seen keyword parameter `sep` used in `print` function calls. In this particular application, the keywords are chosen to include all the words that appear enclosed in braces in the `numberFormat` string.

When the string `numberFormat` has the `format` method applied to it with the given keyword parameters, a new string is created with substitutions into the places enclosed in braces. The substitutions are just the values given by the keyword parameters. Hence the printed result is

Count in Spanish: uno, dos, tres, ...

Now we go one step further: The keyword parameters associate the keyword names with the values after the equal signs. The dictionary from `spanish2a.py` includes exactly the same associations. There is a special notation allowing such a dictionary to supply keyword parameters. Assuming `dictionary` is the Spanish dictionary from `spanish2a.py`, the method call

```
numberFormat.format(one='uno', two='dos', three='tres')
```

returns the same string as

```
numberFormat.format(**dictionary)
```

The special syntax `**` before the dictionary indicates that the dictionary is not to be treated as a *single* actual parameter. Instead keyword arguments for *all* the entries in the dictionary effectively appear in its place.

Below is a substitute for the main method in `spanish2a.py`. The whole revised program is in example program `spanish3.py`:

```
def main():
    dictionary = createDictionary()
    numberFormat = "Count in Spanish: {one}, {two}, {three}, ..."
    withSubstitutions = numberFormat.format(**dictionary)
    print(withSubstitutions)
    print("Spanish colors: {red}, {blue}, {green}, ...".format(**dictionary))
```

In this `main` function the string with the numbers is constructed in steps as discussed above. The printing of the string with the Spanish colors is coded more concisely. There are not named variables for the format string or the resulting formatted string. You are free to use either coding approach.

In general, use this syntax for the string format method with a dictionary, returning a new formatted string:

*formatString.format(**aDictionary)*

where the format string contains dictionary keys in braces where you want the dictionary values substituted. The dictionary key names must follow the rules for legal identifiers.

At this point we have discussed in some detail everything that went into the first sample program, `madlib.py`, in *A Sample Program, Explained* (page 9)! This is certainly the most substantial program so far.

Look at `madlib.py` again, see how we have used most of the ideas so far. If you want more description, you might look at section *A Sample Program, Explained* (page 9) again (or for the first time): it should make much more sense now.

We will use `madlib.py` as a basis for more substantial modifications in structure in *The Revised Mad Lib Program* (page 86).

Mad Lib Exercise

To confirm your better understanding of `madlib.py`, load it in the editor, *rename* it as `myMadlib.py`, and *modify it to have a less lame story*, with more and different entries in the dictionary. Make sure `addPick` is called for each key in your format string. Test your version.

1.12.3 Dictionaries and Python Variables

Dictionaries are central to the implementation of Python. Each variable identifier is associated with a particular value. These relationships are stored in dictionaries in Python, and these dictionaries are accessible to the user: You can use the function call `locals()` to return a dictionary containing all the current local variables names as keys and all their values as the corresponding dictionary values. This dictionary can be used with the string format method, so you can embed local variable names in a format string and use them very easily!

For example, run the example program `arithDict.py`

```
'''Fancier format string example, with locals().'''

x = 20
y = 30
sum = x + y
prod = x * y
formatStr = '{x} + {y} = {sum}; {x} * {y} = {prod}.'
equations = formatStr.format(**locals())
print(equations)
```

Note the variable names inside braces in `formatStr`, and the dictionary reference used as the format parameter is `**locals()`.

A string like `formatStr` is probably the most readable way to code the creation of a string from a collection of literal strings and program values. The ending part of the syntax, `.format(**locals())`, may appear a bit strange, but it is very useful! It clearly indicate how values are embedded into the format string, and avoids having a long list of parameters to format.

The example program `hello_you4.py` does the same thing as the earlier `hello_you` versions, but with a dictionary reference:

```
'''Hello to you! Illustrates locals() for formatting in print.
'''

person = input('Enter your name: ')
greeting = 'Hello, {person}!'.format(**locals())
print(greeting)
```

F-Strings: (Optional, but handy!) A simplification for formatting added in Python 3.6 is *f-strings*. They have many features, but the simplest thing is to shorten formatting of a literal string with local variable references like above: Merely add an `f` immediately *before* the literal format string, and eliminate the `.format(**locals())`. See example `arithfstring.py`:

```
'''Fancier f-string example for formatting'''
x = 20
y = 30
sum = x + y
prod = x * y
print(f'{x} + {y} = {sum}; {x} * {y} = {prod}.')
# see the f directly before the literal format string
# automatically substituting local variable values
```

Quotient String Dictionary Exercise

Create `quotientDict.py` by modifying `quotientReturn.py` in [Quotient String Return Exercise](#) (page 40) so that the `quotientString` function accomplishes the same thing: Put local variable names inside the braces of a format string, and either process the format string by appending `.format(**locals())` or else make the format string into an f-string. If you use meaningful names for the variables, the format string should be particularly easy to understand.

1.13 Loops and Sequences

Modern computers can do millions or even billions of instructions a second. With the techniques discussed so far, it would be hard to get a program that would run by itself for more than a fraction of a second.

Practically, we cannot write millions of instructions to keep the computer busy. To keep a computer doing useful work we need *repetition*, looping back over the same block of code again and again. There are two Python statement types to do that: the simpler `for` loops, which we take up shortly, and `while` loops, which we take up later, in [While Statements](#) (page 143).

Two preliminaries:

1. The value of already defined variables can be updated. This will be particularly important in loops. To prepare for that we first follow how variables can be updated in an even simpler situation, where statements are just executed in textual order.
2. Sequence types are used in `for` loops. We will look at a basic sequence type: `list`.

Then we put this all together. This is a long section. Go slowly and carefully.

1.13.1 Updating Variables

The programs so far have defined and used variables, but other than in early shell examples we have not changed the value of existing variables. For now consider a particularly simple example, just chosen as an illustration, in the example file `updateVar.py`:

```
1 x = 3          # simple sequential code
2 y = x + 2      # updating two variables
3 y = 2*y
4 x = y - x
5 print(x, y)
```

Can you *predict* the result? Run the program and check. Particularly if you did not guess right, it is important to understand what happens, one step at a time. That means keeping track of what changes to variables are made by each statement.

In the table below, statements are referred to by the numbers labeling the lines in the code above. We can track the state of each variable after each line is executed. A dash is shown where a variable is not defined. For instance after

line 1 is executed, a value is given to `x`, but `y` is still undefined. Then `y` gets a value in line 2. The comment on the right summarizes what is happening. Since `x` has the value 3 when line 2 starts, `x+2` is the same as `3+2`. In line three we use the fact that the right side of an assignment statement uses the values of variables when the line starts executing (what is left after the previous line of the table executed), but the assignment to the variable `y` on the left causes a change to `y`, and hence the updated value of `y`, 10, is shown in the table. Line 4 then changes `x`, using the *latest* value of `y` (10, not the initial value 5!). The result from line 5 confirms the values of `x` and `y`.

Line	x	y	Comment
1	3	-	
2	3	5	5=3+2, using the value of x from the previous line
3	3	10	10=2*5 on the right, use the value of y from the previous line
4	7	10	7=10-3 on the right, use the value of x and y from the previous line
5	7	10	print: 7 10

When we create such a table, the order of execution will always be the order of the lines in the table. In this simple *sequential* code, that *also* follows the *textual* order of the program. Following each line of execution of a program in the proper order of execution, carefully, keeping track of the current values of variables, will be called *playing computer*. A table like the one above is an organized way to keep track.

1.13.2 The list Type

Lists are ordered sequences of arbitrary data. Lists are the first kind of data discussed so far that are *mutable*: the length of the sequence can be changed and elements substituted. We will delay the discussion of changes to lists until a further introduction to objects. Lists can be written explicitly. *Read* the following examples

```
['red', 'green', 'blue']
[1, 3, 5, 7, 9, 11]
['silly', 57, 'mixed', -23, 'example']
[] # the empty list
[ [7, 11], [1], [] ] # list containing three elements; each a list
```

The basic format is a square-bracket-enclosed, comma-separated list of arbitrary data.

1.13.3 The range Function, Part 1

There is a built-in function `range`, that can be used to automatically generate regular arithmetic sequences. Try the following in the *Shell*:

```
list(range(4))
list(range(10))
```

The general pattern for use is

```
range(sizeOfSequence)
```

This syntax will generate the integers, one at a time, *as needed* ⁶. If you want to see all the results at once as a list, you can convert to a `list` as in the examples above. The resulting sequence starts at 0 and ends *before* the parameter. We will see there are good reasons to start from 0 in Python. One important property of sequences generated by `range(n)` is that the total number of elements is `n`: The sequence omits the number `n` itself, but includes 0 instead.

With more parameters, the `range` function can be used to generate a much wider variety of sequences. The elaborations are discussed in [Random Colors](#) (page 112) and [The Most General range Function](#) (page 145).

⁶ In computer jargon, producing values of a sequence only as needed is called *lazy* evaluation.

1.13.4 Basic for Loops

Try the following in the *Shell*. You get a sequence of continuation lines before the Shell responds. After seeing the colon at the end of the first line, the Shell knows later lines are to be indented.

Be sure to enter another empty line. (Just press Enter.) at the end to get the Shell to respond. :

```
1 for count in [1, 2, 3]:
2     print(count)
3     print('Yes' * count)
```

This is a `for` loop. It has the heading starting with `for`, followed by a variable name (`count` in this case), the word `in`, some sequence, and a final colon. As with function definitions and other heading lines, the colon at the end of the line indicates that a consistently indented block of statements follows to complete the `for` loop.

`for item in sequence:`

indented statements to repeat; may use **item**

The block of lines is repeated once for each element of the sequence, so in this example the two lines in the indented block are repeated three times. Furthermore the variable in the heading (`count` here) may be used in the block, and each time through it takes on the *next* value in the sequence, so the first time through the loop `count` is 1, then 2, and finally 3. Look again at the output and see that it matches this sequence. A more detailed sequence is given, playing computer, in the table:

Line	count	comment
1	1	start with the first element of the list
2	1	print 1
3	1	'yes' * 1 is 'yes'; print yes
1	2	change count to the next element in the list
2	2	print 2
3	2	'yes' * 2 is 'yesyes'; print yesyes;
1	3	change count to the next element in the list
2	3	print 3
3	3	'yes' * 3 is 'yesyesyes'; print yesyesyes; done with list

When executing step by step, note that the `for` loop heading serves *two* purposes:

- Each time the heading line executes, it implicitly assigns a new value to the variable name you use in place of **item**.
- After each execution of the heading line, the statements in the indented block are executed, generally making use of the the new value for the variable assigned in the heading.

Note: When playing computer with a loop, the same line numbers can reappear over and over, because the `for` loop heading line and the indented body under it are each executed repeatedly. Each time one of these lines is executed, it must be listed separately, in time sequence!

A `for` loop is technically a single *compound statement*. Its level of indentation is considered to be the level of indentation of its heading.

When you used the *Shell* to enter a loop, there was a reason that the interpreter waited to respond until after you entered an empty line: The interpreter did not know how long the loop block was going to be! The empty line is a signal to the interpreter that you are done with the loop block, and hence ready to execute the complete compound loop statement.

Look at the following example program `for123.py`, and run it.

```
for count in [1, 2, 3]:
    print(count)
    print('Yes' * count)
print('Done counting.')
for color in ['red', 'blue', 'green']:
    print(color)
```

In a file, where the interpreter does not need to respond immediately, the blank line is not necessary. Instead, as with a function definition or any other format with an indented block, you indicate being past the indented block by **dedenting**. Here the following `print` statement has the same level of indentation as the `for` loop heading. Because they have the same level of indentation, they are executed in sequence. Hence in the code above, “Done Counting.” is printed once after the first loop completes *all* of its repetitions. Execution of the program ends with another simple loop.

As with the indented block in a function, it is important to get the indentation right. Alter the code above, so the fourth line is indented:

```
for count in [1, 2, 3]:
    print(count)
    print('Yes' * count)
    print('Done counting.') # changed so indented
for color in ['red', 'blue', 'green']:
    print(color)
```

Predict the change, and run the code again to test.

Loops are one of the most important features in programming. While the `for` loop syntax is pretty simple, using them creatively to solve problems (rather than just look at a demonstration) is among the biggest challenges for many learners at an introductory level. One way to simplify the learning curve is to classify common situations and patterns, and give them names. One of the simplest patterns is illustrated in all of the `for` loop examples so far, a simple *for-each* loop: **For each** element of the sequence, do the same sort of thing with it. Stated as more Pythonic pseudo-code:

```
for item in sequence:
    do something with the current item
```

(It would be even more like English if `for` were replaced by `for each`, but the shorter version is the one used by Python.)

In the `for` loop examples above, something is printed that is related to each item in the list. Printing is certainly one form of “do something”, but the possibilities for “do something” are completely general!

We can use a *for-each* loop to revise our first example in the Tutorial. *Recall* the code from `madlib.py`:

```
addPick('animal', userPicks)
addPick('food', userPicks)
addPick('city', userPicks)
```

Each line is doing exactly the same thing, except varying the string used as the cue, while repeating the rest of the line. This is the *for-each* pattern, but we need to list the sequence that the cues come from. *Read* the alternative:

```
for cue in ['animal', 'food', 'city']: # heading
    addPick(cue, userPicks)           # body
```

Seeing this feature requires the ability to *abstract* the general pattern from the group of examples. This is essential for using loops effectively.

If you wish to see or run the whole program with this small modification, see the example `madlibloop.py`. A common naming convention is used in the program: Each element in the list is a `cue`, while the list with all the elements is named with the plural `cues`. In later situations I make a list name be the plural of the variable name used for an individual item of the list.

Note the logic of the transformation between the two program versions: The alternative pieces of data are collected in the list in the `for` loop heading. A single variable name (here I chose `cue`) is used in the heading as a placeholder to refer to the *current* choice being handled, and the body refers to this variable `cue` in place of the explicit data values included each time in the original no-loop version.

It is important to understand the sequence of operations, how execution goes back and forth between the heading and the body. Here are the details:

1. heading first time: variable `cue` is set to the first element of the sequence, `'animal'`
2. body first time: since `cue` is now `'animal'`, effectively execute `addPick('animal', userPicks)` (Skip the details of the function call in this outline.)
3. heading second time: variable `cue` is set to the next element of the sequence, `'food'`
4. body second time: since `cue` is now `'food'`, effectively execute `addPick('food', userPicks)`
5. heading third time: variable `cue` is set to the next (last) element of the sequence, `'city'`
6. body third time: since `cue` is now `'city'`, effectively execute `addPick('city', userPicks)`
7. heading done: Since there are no more elements in the sequence, the entire `for` loop is done and execution would continue with the statement after it (not indented).

In this example the data values are just a few given literals, and there is only one line in the repeated pattern. Hence the use of a `for` loop is not a big deal, but it makes a simple example! This looping construction would be much handier if you were to modify the original mad lib example, and had a story with many more cues. Also this revision will allow for further improvements in *The Revised Mad Lib Program* (page 86), after we introduce more about string manipulation.

Pattern Loop Exercise

Write a two-line for-each loop in a file `types2.py` containing a call to the `type` function, so that this code with the for-each loop produces exactly the same printed output as the code in example file `types1.py`. The `types1.py` code is shown below:

```
print(2, type(2))
print(3.5, type(3.5))
print([], type([]))
print(True, type(True))
print(None, type(None))
```

Execute both versions to check yourself. Hint 1: ⁷ Hint 2: ⁸

Triple Exercise

Complete the following function. This starting code is in `tripleStub.py`. Save it to the *new* name `triple.py`. Note the way an example is given in the documentation string. It simulates the use of the function in the Shell. This is a common convention:

⁷ The elements of the list in the `for` loop heading are not all of the same type.

⁸ You need to use the loop variable twice in the loop body.

```
def tripleAll(nums):  
    ''' print triple each of the numbers in the list nums.  
    >>> tripleAll([2, 4, 1, 5])  
    6  
    12  
    3  
    15  
    >>> tripleAll([-6])  
    -18  
    '''
```

1.13.5 Simple Repeat Loop

The examples above all used the value of the variable in the `for` loop heading. An even simpler `for` loop usage is when you just want to repeat the *exact* same thing a specific number of times. In that case only the *length* of the sequence, not the individual elements are important. We have already seen that the `range` function provides an easy way to produce a sequence with a specified number of elements. Read and run the example program `repeat1.py`:

```
''' A simple repeat loop'''  
  
for i in range(10):  
    print('Hello')
```

In this situation, the variable `i` is not used inside the body of the `for`-loop.

The user could choose the number of times to repeat. Read and run the example program `repeat2.py`:

```
'''The number of repetitions is specified by the user.'''  
  
n = int(input('Enter the number of times to repeat: '))  
for i in range(n):  
    print('This is repetitious!')
```

When you are reading code, you look at variable names as they are introduced, and see where they are used later. In the simple repeat loops above, the loop variable `i` is introduced, because there must be a variable name there, but it is never used.

One convention to indicate the simple repeat loop variable is never used again, is to use the special variable name `_` (just an underscore), as in:

```
for _ in range(10):  
    print('Hello')
```

1.13.6 Successive Modification Loops

Suppose I have a list of items called `items`, and I want to print out each item and number them successively. For instance if `items` is `['red', 'orange', 'yellow', 'green']`, I would *like* to see the *output*:

```
1 red  
2 orange  
3 yellow  
4 green
```

Read about the following thought process for developing this:

If I allow myself to omit the numbers, it is easy: For any `item` in the list, I can process it with


```
print(item)
```

and I just go through the list and do it *for each* one. (Copy and run if you like.)

```
items = ['red', 'orange', 'yellow', 'green']
for item in items:
    print(item)
```

Clearly the more elaborate version with numbers has a pattern with *some* consistency, each line is at least in the form:

```
number item
```

but the number changes each time, and the numbers do *not* come straight from the list of items.

A variable can change, so it makes sense to have a variable `number`, so we have the potential to make it change correctly. We could easily get it right the first time, and then repeat the *same* number. Read and run the example program `numberEntries1.py`:

```
'''In this version number does not change.'''

items = ['red', 'orange', 'yellow', 'green']
number = 1
for item in items:
    print(number, item)
```

Of course this is still not completely correct, since the idea was to *count*. After the first time number is printed, it needs to be changed to 2, to be right the next time through the loop, as in the following code: Read and run the example program `numberEntries2.py`:

```
'''prints poorly numbered entries from the list'''

items = ['red', 'orange', 'yellow', 'green']
number = 1
for item in items:
    print(number, item)
    number = 2 # will change to 2 after printing 1
```

This is closer, but still not completely correct, since we never get to 3! We need a way to change the value of `number` *that will work each time through the loop*. The pattern of counting is simple, so simple in fact that you probably do not think consciously about how you go from one number to the next: You can describe the pattern by saying each successive number is *one more than the previous number*. We need to be able to change `number` so it is one more than it was before. That is the additional idea we need! Change the last line of the loop body to get the example program `numberEntries3.py`. See the addition and run it:

```
1 items = ['red', 'orange', 'yellow', 'green']
2 number = 1
3 for item in items:    # print numbered entries
4     print(number, item)
5     number = number + 1 # crucial added line
```

It is important to understand the step-by-step changes during execution. Below is another table showing the results of playing computer. The line numbers are much more important here to keep track of the flow of control, because of the jumping around at the end of the loop.

Again note that the program line numbers in the Line column of the playing computer table are *not* all listed sequentially, because the `for` loop heading line and the indented body under it are each executed repeatedly.

For compactness, the variable `items` does not get its own column, since it always has the value shown in the comment in line 1:

line	item	number	comment
1	-	-	set items to ['red', 'orange', 'yellow', 'green']
2	-	1	
3	'red'	1	start with item as first in sequence
4	'red'	1	print: 1 red
5	'red'	2	2 = 1+1
3	'orange'	2	on to the next element in sequence
4	'orange'	2	print 2 orange
5	'orange'	3	3=2+1
3	'yellow'	3	on to the next element in sequence
4	'yellow'	3	print 3 yellow
5	'yellow'	4	4=3+1
3	'green'	4	on to the last element in sequence
4	'green'	4	print 4 green
5	'green'	5	5=4+1
3	'green'	5	sequence done, end loop and code

The final value of number is never used, but that is OK. What we want gets printed.

Go through carefully and be sure you understand the meaning of each entry in the table, and the reason for the sequencing and the reason for the exact position of each entry in each step where it changes! In particular see how and why the line number for each successive row is *not* always one more than the previous row. In particular, see how *the same sequence of numbered lines may be repeated* in multiple places in the table. Without this understanding you will not be able to play computer yourself and really understand loops.

This short example illustrates a lot of ideas important to loops:

- Loops may contain several variables.
- One way a variable can change is by being the variable in a `for` loop heading, that automatically goes through the values in the `for` loop list.
- Another way to have variables change in a loop is to have an explicit statement that changes the variable inside the loop, causing *successive modifications*.

There is a general pattern to loops with successive modification of a variable like `number` above:

1. The variables to be modified need *initial* values *before* the loop (line 1 in the example above).
2. The loop heading causes the repetition. In a `for`-loop, the number of repetitions is the same as the size of the list.
3. The body of the loop generally “does something” (like `print` above in line 4) that you want done repeatedly.
4. There is code inside the body of the loop to set up for the *next* time through the loop, where the variable which needs to change gets transformed to its next value (line 5 in the example above).

This information can be put in a code outline:

Initialize variables to be modified

Loop heading controlling the repetition:

 Do the desired action with the current variables

 Modify variables to be ready for the action the next time

If you compare this pattern to the `for`-each and simple repeat loops in [Basic for Loops](#) (page 49), you see that the examples there were simpler. There was no explicit variable modification needed to prepare for the next time through the loop. We will refer to the latest, more general pattern as a *successive modification* loop.

Functions are handy for encapsulating an idea for use and reuse in a program, and also for testing. We can write a function to number a list, and easily test it with different data. Read and run the example program `numberEntries4.py`:

```
''' use a function to number the entries in any list'''

def numberList(items):
    '''Print each item in a list items, numbered in order.'''
    number = 1
    for item in items:
        print(number, item)
        number = number + 1

def main():
    numberList(['red', 'orange', 'yellow', 'green'])
    print()
    numberList(['apples', 'pears', 'bananas'])

main()
```

Make sure you can follow the whole sequence, step by step! This program has the most complicated flow of control so far, changing both for function calls and loops.

1. Execution start with the very last line, since the previous lines are definitions
2. Then `main` starts executing.
3. The first call to `numberList` effectively sets the formal parameter

```
items = ['red', 'orange', 'yellow', 'green']
```

and the function executes just like the flow followed in `numberEntries3.py`. This time, however, execution returns to `main`.

4. An empty line is printed in the second line of `main`.
5. The second call to `numberList` has a different actual parameter `['apples', 'pears', 'bananas']`, so this effectively sets the formal parameter this time

```
items = ['apples', 'pears', 'bananas']
```

and the function executes in a similar pattern as in `numberEntries3.py`, but with different data and one less time through the loop.

6. Execution returns to `main`, but there is nothing more to do.

1.13.7 Accumulation Loops

Suppose you want to add up all the numbers in a list, `nums`. Let us plan this as a function from the beginning, so *read* the code below. We can start with:

```
def sumList(nums):
    '''Return the sum of the numbers in nums.'''
```

If you do not see what to do right away, a useful thing to do is write down a *concrete* case, and think how you would solve it, in complete detail. If `nums` is `[2, 6, 3, 8]`, you would likely calculate:

```
2 + 6 is 8
8 + 3 is 11
11 + 8 is 19
19 is the answer to be returned.
```

Since the list may be arbitrarily long, you need a loop. Hence you must find a *pattern* so that you can keep reusing the *same statements* in the loop. Obviously you are using each number in the sequence in order. You also generate a sum in each step, which you reuse in the next step. The pattern is different, however, in the first line, 2+6 is 8: there is no previous sum, and you use two elements from the list. The 2 is not added to a previous sum.

Although it is not the shortest way to do the calculation *by hand*, 2 is a sum of 0 + 2: We can make the pattern consistent and calculate:

```
start with a sum of 0
0 + 2 is 2
2 + 6 is 8
8 + 3 is 11
11 + 8 is 19
19 is the answer.
```

Then the second part of each sum is a number from the list, `nums`. If we call the number from the list `num`, the main calculation line in the loop could be

```
nextSum = sum + num
```

The trick is to use the same line of code the next time through the loop. That means what *was* `nextSum` in one pass becomes the `sum` in the next pass. One way to handle that is:

```
sum = 0
for num in nums:
    nextSum = sum + num
    sum = nextSum
```

Do you see the pattern? Again it is

```
initialization
loop heading:
    main work to be repeated
    preparation for the next time through the loop
```

Sometimes the two general loop steps can be combined. This is such a case. Since `nextSum` is only used once, we can just substitute its value (`sum`) where it is used and simplify to:

```
sum = 0
for num in nums:
    sum = sum + num
```

so the whole function, with the `return` statement is:

```
1 def sumList(nums):
2     '''Return the sum of the numbers in the list nums.'''
3     sum = 0
4     for num in nums:
5         sum = sum + num
6     return sum
```

The example program `sumNums.py` has the code above with the following line added at the end to test the function (not indented). *Run* `sumNums.py`.

```
print(sumList([5, 2, 4, 7]))
```

The pattern used here is certainly successive modification (of the `sum` variable). It is useful to give a more specialized name for this version of the pattern here. It follows an *accumulation* pattern:

```

initialize the accumulation to include none of the sequence (sum = 0 here)
for item in sequence :
    new value of accumulation = result of combining item with last value of accumulation

```

This pattern will work in many other situations besides adding numbers.

English loop terminology: Of course you need to be able to go from an English description of a problem to a plan and then implement it in Python. In particular, it will be very important to realize when you will need your program to have a loop through a sequence. What are some common words or phrases that suggest a loop? After thinking for yourself, compare:⁹

Once you see this need for a loop, you need to plan your code. There are a bunch of questions you can *routinely* ask yourself about fleshing out the outline for the loop part of your code:

```

initialization
loop heading:
    main work to be repeated
    preparation for the next time through the loop

```

1. What is the sequence? What descriptive name can I give to the loop variable?
2. Write the `for` loop heading. With this decided, you no longer need to think about the whole program at once: You can *focus on what you do for one element*, with the name you gave in the loop heading.
3. What do I need to do for a single element of the sequence? Does this involve other variables? If so, how will I initialize them? Write this action into the body of the loop, using the loop variable.
4. Does the main action involve a variable, other than the loop variable, that needs to change each time through the loop? If so, how do I relate the present and next values, and change the value to be ready for the next time through the loop? Writing the sequence for a specific example may help. Finally, code this update.

Play Computer sumList Exercise

Suppose the function `sumList`, defined above, is called with the parameter `[5, 2, 4, 7]`. Play computer on this call, using the file `playComputerSumStub.rtf`, opened from an *operating system* window for the examples directory. Do *not* open in Idle. The file should come up in your usual word processor. Immediately save the file as `playComputerSum.rtf`, and fill in blank cells in the table.

Make sure there is a row in the table for each line executed in the program, with a *separate* line entry for *each time a line is executed*. In each row enter which program line is being executed, and show all changes caused to variables by the execution of that one line. Display line numbers as shown in the margin beside the example code *in the Tutorial*. (The separate Python files themselves do not show the line numbers.) A table is started for you below. The final row that you enter in your your table should be for an execution of line numbered 6 in the code, and your comment can be, “return 18”.

If the same variable value in one column repeats through several rows, it is more convenient just leave the later entries blank, rather than keep copying. With this convention, the current value of a variable is the last value recorded in a previous line in the table.

This is the first “Play Computer” exercise with a loop. Be sure to look back at the earlier play computer examples. The lines in the loop (and hence their line numbers) repeat multiple times as rows in the table, as you follow the loop one time through after another!

The original parameter, which does not change, does not have a column in the table, for compactness. The start of the table is shown below. As shown in the first comment, throughout the function call, `nums` is

⁹ “do each”, “do every”, “for all”, “process each”, “do ___ times”, ...

```
[5, 2, 4, 7]
```

Line	sum	num	comment
1	-	-	set nums to [5, 2, 4, 7]; skip line 2 doc string
3			

Test sumList Exercise

Write a program `testSumList.py` which includes a `main` function to test the `sumList` function several times. Include a test for the extreme case, with an empty list.

Join All Exercise

* Complete the following function. This starting code is in `joinAllStub.py`. Save it to the *new* name `joinAll.py`. Note the way an example is given in the documentation string. It simulates the use of the function in the Shell. This is a common convention:

```
def joinStrings(stringList):
    '''Join all the strings in stringList into one string,
    and return the result, NOT printing it. For example:

    >>> s = joinStrings(['very', 'hot', 'day']) # returns string
    >>> print(s)
    veryhotday
    '''
```

First Hint: ¹⁰ Second Hint: ¹¹

1.13.8 More Playing Computer

Testing code by running it is fine, but looking at the results does not mean you really understand what is going on, particularly if there is an error! People who do not understand what is happening are likely to make random changes to their code in an attempt to fix errors. This is a *very bad*, increasingly self-defeating practice, since you are likely to never learn where the real problem lies, and the same problem is likely to come back to bite you.

It is important to be able to predict accurately what code will do. We have illustrated playing computer on a variety of small chunks of code.

Playing computer can help you find bugs (errors in your code). Some errors are syntax errors caught by the interpreter in translation. Some errors are only caught by the interpreter during execution, like failing to have a value for a variable you use. Other errors are not caught by the interpreter at all - you just get the wrong answer. These are called *logical* errors. Earlier logical errors can also trigger an execution error later. This is when playing computer is particularly useful.

A common error in trying to write the `numberList` function would be to have the following code (extracted from `numberEntriesWRONG.py`):

```
1 def numberList(items): #WRONG code for illustration
2     '''Print each item in a list items, numbered in order.'''
3     for item in items:
4         number = 1
5         print(number, item)
6         number = number + 1
```

¹⁰ This is a form of accumulation, but not quite the same as adding numbers.

¹¹ “Start with nothing accumulated” does not mean 0, here. You are dealing with strings, not numbers. Think what is appropriate.

You can run this code and see that it produces the wrong answer. If you play computer on the call to `numberList(['apples', 'pears', 'bananas'])`, you can see the problem:

Line	item	number	comment
1	-	-	set items to ['apples', 'pears', 'bananas']
3	'apples'	-	start with item as first in sequence
4	'apples'	1	
5	'apples'	1	1 print: 1 apples
6	'apples'	2	2 = 1+1
3	'pears'	2	on to the next element in sequence
4	'pears'	1	
5	'pears'	1	print: 1 pears <i>OOPS!</i>

If you go step by step you should see where the incorrect 1 came from: the initialization is repeated each time in the loop at line 4, undoing the incrementing of `number` in line 6, messing up your count.

Warning: Always be careful that your *one-time* initialization for a loop goes *before* the loop, not in it!

Functions can also return values. Consider the Python for this mathematical sequence: define the function $m(x) = 5x$, let $y = 3$; find $m(y) + m(2y-1)$:

```

1 def m(x):      # mathematical function m
2     return 5*x
3
4 y = 3
5 print(m(y) + m(2*y-1))

```

This code is in example `mathfunc.py`. A similar example was considered in [Returned Function Values](#) (page 38), but now add the idea of playing computer and recording the sequence in a table. Like when you simplify a mathematical expression, Python must complete the innermost parts first. Tracking the changes means following the function calls carefully and using the values returned. Again a dash '-' is used in the table to indicate an undefined variable. Not only are local variables like formal parameters undefined before they are first used, they are also undefined after the termination of the function,

Line	x	y	Comment
1-3			Remember definition of m
4	-	3	
5	-	3	start on: print(m(y) + m(2*y-1)); first want m(y), which is m(3)
1	3	3	pass 3 to function m, so x=3
2	3	3	return 5*3 = 15
5	-	3	substitute result: print(15 + m(2*y-1)), want m(2*y-1), which is m(2*3-1) = m(5)
1	5	3	pass 5 to function m, so x=5
2	5	3	return 5*5 = 25
5	-	3	substitute result: print(15 + 25), so calculate and print 40

Thus far most of the code given has been motivated first, so you are likely to have an idea what to expect. You may need to read code written by someone else (or even yourself a while back!) where you are not sure what is intended. Also you might make a mistake and accidental write code that does something unintended! If you really understand how Python works, one line at a time, you should be able to play computer and follow at least short code sequences that have not been explained before. It is useful to read another person's code and try to follow it. The next exercises also provides code that has not been explained first, or has a mistake.

Play Computer Odd Loop Exercise

* Work in a word processor (not Idle!), starting from example `playComputerStub.rtf`, and save the file as `playComputer.rtf`. The file has tables set up for this and the following two exercise.

Play computer on the following code:

```
1 x = 0          # Exercise Play Computer Loop
2 y = 1
3 for n in [5, 4, 6]:
4     x = x + y*n
5     y = y + 1
6 print(x)
```

Reality check: 31 is printed when line 6 finally executes. The start of the table for this exercise is shown below.

Line	x	y	n	Comment
1	0			

Play Computer Error Exercise

* In a word processor add to the file `playComputer.rtf`, started in the previous exercise.

The following code is supposed to compute the product of the numbers in a list. For instance `product([5, 4, 6])` should calculate and return $5*4*6=120$ in steps, calculating $5, 5*4=20$ and $20*6=120$.

```
1 def product(nums):      #Play Computer Error Exercise
2     for n in nums:
3         prod = 1
4         prod = prod*n
5     return prod
```

The code for this exercise appears in the example file `numProductWrong.py`.

A major use of playing computer is to see exactly where the data that you expect gets messed up. Play computer on a call to `product([5, 4, 6])` until you see that it makes a mistake, and produces a wrong number. Then you can stop extending the table, just ending with a comment about how the error is now visible.

The table headings and the first row of the table for this exercise are shown below.

Line	n	prod	Comment
1	-	-	Set nums to [5, 4, 6]
2			

Then you can stop and fix it: First copy `numProductWrong.py` to `numProduct.py`, and fix the new file (and save again!).

Play Computer Functions Exercise

* In a word processor once again add to the file `playComputer.rtf`, started in the previous exercises.

Play computer on the following code:

```
1 def f(x):        #Play Computer Functions Exercise
2     return x+4
3 print(f(3)*f(6))
```


Reality check: 70 is printed.

The table headings and the first row of the table for this exercise are shown below.

Line	x	Comment
1-2		Remember f definition
3		

You will revisit line 3 several times, with table lines for function `f` execution interspersed. Look at the example above which has a table showing function `m` returning a value twice!

1.13.9 The `print` function keyword `end`

By default the `print` function adds a newline to the end of the string being printed. This can be overridden by including the keyword parameter `end`. The keyword `end` can be set equal to any string. The most common replacements are the empty string or a single blank. If you also use the keyword parameter `sep`, these keyword parameters may be in either order, but keyword parameters must come at the end of the parameter list. Read the illustrations:

```
print('all', 'on', 'same', 'line')
print('different line')
```

is equivalent to

```
print('all', 'on' , end=' ')
print('same', end=' ')
print('line')
print('different line')
```

This does not work directly in the shell (where you are always forced to a new line at the end). It does work in a program, but it is not very useful except in a loop!

Suppose I want to print a line with all the elements of a list, separated by spaces, but not on separate lines. I can use the `end` keyword set to a space in the loop. Can you figure out in your head what this example file `endSpace1.py` does? Then try it:

```
def listOnOneLine(items):
    for item in items:
        print(item, end=' ')

listOnOneLine(['apple', 'banana', 'pear'])
print('This may not be what you expected!')
```

If you still want to go on to a new line at the *end* of the loop, you must include a `print` function that does advance to the next line, once, *after* the loop. Try this variation, `endSpace2.py`

```
def listOnOneLine(items):
    for item in items:
        print(item, end=' ')
    print()

listOnOneLine(['apple', 'banana', 'pear'])
print('This is probably better!')
```

1.14 Decimals, Floats, and Floating Point Arithmetic

Floating point numbers like 12.345 are a basic type, but there are some complications due to their inexactness. This section may be deferred until you actually need numbers other than integers.

1.14.1 Floats, Division, Mixed Types

As you moved on in school from your first integer division to fractions and decimals, you probably thought of $6/8$ as a fraction and could convert to a decimal $.75$. Python can do decimal calculations, too, *approximately*.

Try all set-off lines in this section in the Shell:

```
6/8
6/3
2.3/25.7
```

There is more going on here than meets the eye. As you should know, decimal representations of values can be a pain. They may not be able to be expressed with a finite number of characters. Try

```
2/3
```

Also, as you may have had emphasized in science class, real number measurements are often not exact, and so the results of calculations with them are not exact. In fact there are an infinite number of real number just between 0 and 1, and a computer is finite. It cannot store all those numbers exactly! On the other hand, Python does store *integers* exactly (well at least far past the number of atoms in the universe - eventually even integers could get too big to store in a computer). The difference in the way integers and decimals are stored and processed leads to decimals and integers being different *types* in Python. Try

```
type(3.5)
```

Note that 3.5 is of type ‘float’, not ‘decimal’. There are several reasons for that name having to do with the actual way the type is stored internally. “Decimal” implies base ten, our normal way for writing numbers with ten digits 0,1,2,3,4,5,6,7,8,9. Computers actually use base two, with only two symbols 0,1. (Did you note what symbols were in the machine language in [Context](#) (page 3)?) Also floats use an encoding something like scientific notation from science class, with exponents that allow the decimal point to move or “float”, as in the decimal case: $2345.6 = (2.3456)10^3$

Try

```
type(-2)
type(-2.0)
```

Even a number that is actually an integer can be represented in the float type if a decimal point is included.

Always be sure to remember that floats may not be exact. The use of base two makes this true even in cases where decimal numbers *can* be expressed exactly! More on that in [String Formats for Float Precision](#) (page 63).

It is sometimes important to know the numeric type of the result of a binary operation. Any combination of +, -, and * with operands of type int produces an int. If there is an operation /, or if either operand is of type float, the result is float. Try each in the *Shell* (and guess the resulting type): ¹²

```
3.3 - 1.1
2.0 + 3
2*2.5
```

1.14.2 Exponentiation, Square Roots

Exponentiation is finding powers. In mathematical notation, $(3)(3)(3)(3)=3^4$. In Python there is no fancy typography with raised exponent symbols like the 4, so Python uses ** before a power: Try in the *Shell*:

¹² Python 3 does what you would expect mathematically with an expression like $(1/2) * 6.5$

Caution: This is not the case in other common languages like Java and C++ (or with Python 2). They treat the / operation with integers like the current Python //, so the result of the expression above is 0, since $1/2$ is 0.

```
3**4
5*2**3
```

If you expected 1000 for the second expression, remember exponentiation has even higher precedence than multiplication and division: $2**3$ is $2*2*2$ or 8, and $5*8$ is 40.

Exponents do not need to be integers. A useful example is the 0.5 power: it produces a square root. Try in the *Shell*:

```
9**0.5
2**0.5
```

The result of a power operation is of `int` type only if both parameters are integers and the correct result is an integer.

1.14.3 String Formats for Float Precision

You generally do not want to display a floating point result of a calculation in its raw form, often with an enormous number of digits after the decimal point, like 23.457413902458498. You are likely to prefer rounding it to something like 23.46. There are two approaches.

First there is a *format function* (not method) with a second parameter allowed to specialize the formatting of objects as strings. *Read* the following example interpreter sequence showing possibilities when a float is being formatted:

```
>>> x = 23.457413902458498
>>> s = format(x, '.5f')
>>> s
'23.45741'
>>> format(x, '.2f')
'23.46'
>>> x
23.457413902458498
```

Note that the results are rounded not *truncated*: the result to two places is 23.46, not 23.45. The formatting string `' .5f'` means round to 5 places after the decimal point. Similarly `' .2f'` means round to two decimal places.

Warning: This `format` function *returns* the formatted string. It does not change the parameters. As a *complete* statement in a *program* `format(x, '.2f')`, is useless: The `'23.46'` gets returned and *thrown away*, with no effect on `x`.

The first version, saving the formatted value to `s`, will allow the formatted string to be used again (as `s`).

This rounding notation can also be placed after a colon inside the braces of format strings, for use with the string format *method*. You can put a colon `:` and the formatting information we used in the simple format method above (like `.5f`, but with NO quotes) Recall there are many ways to indicate what values to substitute into a format string. The first way introduced is just to omit any reference to the variables and substitute the method's parameters in order as in:

```
>>> x = 2.876543
>>> y = 16.3591
>>> 'x long: {:.5f}, x short: {:.3f}, y: {:.2f}.'.format(x, x, y)
'x long: 2.87654, x short: 2.877, y: 16.36.'
```

The first part inside the formatting braces can also indicate what value to substitute, as when using a dictionary.

```
>>> x = 2.876543
>>> 'long: {x:.5f}, short: {x:.3f}.'.format(**locals())
'long: 2.87654, short: 2.877.'
```

The instructions for the data to insert can also be given by position index (from the optional end of *String Format Operation* (page 27)):

```
>>> x = 2.876543
>>> 'longer: {0:.5f}, shorter: {0:.3f}'.format(x)
'longer: 2.87654, shorter: 2.877.'
```

In each of these approaches, the colon and formatting specification come at the end of the expression inside the braces, just before the closing `}`. This follows the `{` and symbols (if any) identifying what value to use for the substitution.

There are many more fancy formatting options for the string `format` method that we will not discuss.

Going to the opposite extreme, and using formatting with many digits, you can check that Python does not necessarily remember simple decimal numbers exactly:

```
>>> format(.1, '.20f')
'0.10000000000000000555'
>>> format(.2, '.20f')
'0.20000000000000001110'
>>> format(.1 + .2, '.20f')
'0.3000000000000000441'
>>> format(.3, '.20f')
'0.29999999999999998890'
```

Python stores the numbers correctly to about 16 or 17 digits. You may not care about such slight errors, but you will be able to check in Chapter 3 that if Python tests the expressions `.1 + .2` and `.3` for equality, it decides that they are not equal! In fact, as you can see above, the approximations that Python stores for the two expressions are *not* exactly equal.

Warning: Do not depend on the exactness of floating point arithmetic, even for apparently simple expressions!

Floating point formatting code similar to this section is also in example program `floatFormat.py`.

Floating Point Exercise

Write a program, `discount.py`, that prompts the user for an original price and for a discount percentage and prints out the new price to the nearest cent. For example if the user enters 2.89 for the price and 20 for the discount percentage, the value would be

$$(1 - 20/100) * 2.89$$

rounded to two decimal places, 2.31. For price .65 with a 25 percent discount, the value would be

$$(1 - 25/100) * .65$$

rounded to two decimal places, .49.¹³

Write the general calculation code following the pattern of the calculations illustrated in the two concrete examples.

1.15 Summary

Section references in square brackets indicate where an idea was first discussed.

Where Python syntax is illustrated, the typeface continues to indicate the category of each part:

¹³ In Python 3.0+, the previous expressions make sense, but in earlier versions of Python and in other languages like C++ and Java, where there are not separate division operators `//` and `/`, these expressions would be wrong because of the multiple meanings of the operator `/` with different types. The expressions would work in these other languages if, for example, 100 were replaced by 100.0.

Typeface	Meaning
Typewriter font	Text to be written <i>verbatim</i>
<i>Emphasized</i>	A place where you can use an arbitrary expression.
Bold	A place where you can use an arbitrary identifier.
Normal text	A description of what goes in that position, without giving explicit syntax

If there are several variations on a particular part of the syntax, alternatives will be shown on successive lines.

To emphasize the successive parts of the syntax, space will generally be left around symbol and punctuation characters, but the space is not required in actual use.

1. Python Shell

- (a) A Shell window may be opened in Idle *Run* → *Python Shell* [*Windows in Idle* (page 12)]
- (b) Entering commands:
 - i. Commands may be entered at the `>>>` prompt. [*Addition and Subtraction* (page 14)]
 - ii. If the Shell detects that a command is not finished at the end of the line, a continuation line is shown with no `>>>`. [*Multiplication, Parentheses, and Precedence* (page 15)]
 - iii. Statements with a heading ending in a colon followed by an indented block, must be terminated with an empty line. [*Basic for Loops* (page 49)]
 - iv. The Shell evaluates a completed command immediately, displaying any result other than `None`, starting on the next line. [*Addition and Subtraction* (page 14)]
 - v. The Shell remembers variable and function names. [*Variables and Assignment* (page 18)]
- (c) An earlier Shell line may be copied and edited by clicking anywhere in the previously displayed line and then pressing `Enter`.

2. Idle editing

- (a) Start a new window from the File menu by selecting New, Open..., or Recent Files. [*Loading a Program in the Idle Editor, and Running It* (page 22)]
- (b) Make your Python file names end with `.py` [*Literals and Identifiers* (page 20)]

3. To run a program from an Idle Editor Window:

- (a) Select *Run* → *Run Module* or press function key `F5`. The program runs in the Shell window, after resetting the shell so all old names are forgotten. [*Loading a Program in the Idle Editor, and Running It* (page 22)]
 - i. If the program is expecting keyboard input, the text cursor should appear at the end of the Shell history. If you somehow move the cursor elsewhere, you must explicitly move it back. [*The Idle Editor and Execution* (page 22)]
 - ii. Press `Ctrl-C` to stop a running program in a long or infinite loop.
 - iii. After a program terminates, the Shell remembers function definitions and variable names defined outside of any function. [*A First Function Definition* (page 30)]

4. Errors come in three categories:

- (a) Syntax errors: text that the interpreter recognizes as illegal when first reading it. This prevents execution of your code. Python lets you know where it *realized* there was an error. Sometimes this is the exact location, but the actual error could be anywhere earlier, often on the previous line. [*Variables and Assignment* (page 18)]
- (b) Execution errors: The first illegal action is detected while running your command or program. The source of the error could be in the line where execution fails, or it could be an earlier logical error that only later forces an execution error. [*Variables and Assignment* (page 18)] Execution errors generate a traceback. [*Function Parameters* (page 34)]

- (c) Logical errors: When Python detects nothing illegal, but you do not get the results you desire. These errors are the hardest to trace down. Playing computer and additional print functions help. [[More Playing Computer](#) (page 58)]
5. Type `int`, (short for integer):
- (a) Literal integer values may not contain a decimal point. [[Floats, Division, Mixed Types](#) (page 62)]
 - (b) Integers may be arbitrarily large and are stored exactly. [[Floats, Division, Mixed Types](#) (page 62)]
 - (c) Integers have normal operations, with usual precedence (highest listed first):
 - i. `**`: exponentiation (`5**3` means `5*5*5`) [[Exponentiation, Square Roots](#) (page 62)]
 - ii. `*`, `/`, `//`, `%`: multiplication, division with float result, integer division (ignoring any remainder), just the remainder from division [[Division and Remainders](#) (page 15)]
 - iii. `+`, `-`: addition, subtraction [[Addition and Subtraction](#) (page 14)]
6. Type `float`, (short for floating point): approximations of real numbers
- (a) Literal values must contain a decimal point to distinguish them from the `int` type [[Floats, Division, Mixed Types](#) (page 62)]
 - (b) Approximates a wide range of values [[Floats, Division, Mixed Types](#) (page 62)]
 - (c) Does not dependably store numbers exactly - even numbers with simple decimal representation [[Floats, Division, Mixed Types](#) (page 62)]
 - (d) Has the same operation symbols as for integers, but always with a `float` result [[Floats, Division, Mixed Types](#) (page 62)]
 - (e) A mixed binary operation with an integer and a `float` produces a `float` result. [[Floats, Division, Mixed Types](#) (page 62)]
7. Type `str`, (short for string): Literal values contain a sequence of characters enclosed in matching quotes.
- (a) Enclosed in `'` or `"`: The string must be on one line. [[String Delimiters, Part I](#) (page 17)]
 - (b) Enclosed in `'''` or `"""`: The string may include multiple lines in the source file. [[Triple Quoted String Literals](#) (page 21)]
 - (c) Escape codes inside literals include `\'` for a single quote and `\n` for a newline. [[Escape Codes](#) (page 21)]
 - (d) Binary operations (operation symbols have the same precedence order as when the symbols are used in arithmetic) [[String Concatenation](#) (page 18)]
 - i. `stringExpression1 + stringExpression2`
concatenation (running together) of the two strings
 - ii. `stringExpression * integerExpression`
`integerExpression * stringExpression`
Repeat the string the number of times given by the integer expression.
 - (e) string format method:
 - i. `stringFormatExpression .format (parameter0 , parameter1 , parameter2 , ...)`
[[String Format Operation](#) (page 27)] where `stringFormatExpression` is any string with an arbitrary number of places for format substitutions in it. Formatted substitutions are enclosed in braces. A digit inside the braces will indicate which parameter value is substituted, counting from 0. If digits are left out, the format parameters are substituted in order. The expression inside the braces can end with a colon `:` followed by a format specifying string such as `%.#f` where `#` can be a non negative

integer: substitute a numerical value rounded to the specified number of places beyond the decimal point. [*Floats, Division, Mixed Types* (page 62)]

Example:

```
'word: {}, int: {}, formatted float: {:.3f}'.format('Joe', 23, 2.1357)
```

evaluates to:

```
'word: Joe, int: 23, formatted float: 2.136.'
```

ii. *stringFormatExpression* .format (*** dictionary*)

The format expressions are the same as above except that a key name from a *dictionary* appears inside the braces. The dictionary referenced appears in the parameter list preceded by **. Any value to be substituted is then taken from the dictionary by accessing the key. Example: If *defs* is a dictionary with *defs['name']* equaling 'Joe', *defs['num']* equaling 23, *defs['dec']* equaling 2.13579, then

```
'word: {name}, int: {num}, formatted float: {dec:.3f}'.format(**defs)
```

evaluates to the same string as in the previous example. [*Dictionaries and String Formatting* (page 44)]

In particular, the dictionary reference can be the dictionary of all local variable names, by making the parameter to *format* be ***locals()*. [*Dictionaries and Python Variables* (page 46)]

(f) Strings are a kind of sequence.

8. Type list

[*expression1* , *expression2* , and so on]

[*expression*]

[]

(a) A literal list consists of a comma separated collection of values all enclosed in square brackets. There may be many, one, or no elements in the list. [*The list Type* (page 48)]

(b) A list is a kind of sequence, so it may be used as the sequence in a *for* statement heading. [*Basic for Loops* (page 49)]

9. Type dict (short for dictionary)

dict ()

returns an empty dictionary

(a) A dictionary provides an association of each key to its value. The key can be any immutable type, with includes numbers and strings. [*Definition and Use of Dictionaries* (page 42)]

(b) *dictName* [*keyExpression*] = *valueExpression*

associates in the dictionary *dictName* the key derived from evaluating *keyExpression* with the value derived from evaluating *valueExpression*. [*Definition and Use of Dictionaries* (page 42)]

(c) Used in an expression,

dictName [*keyExpression*]

evaluates to the value in the dictionary *dictName* coming from the key obtained by evaluating *keyExpression*. [*Definition and Use of Dictionaries* (page 42)]

10. Type of `None`: This literal value has its own special type. `None` indicates the absence of a regular object.

11. Identifiers

- (a) Identifiers are names for Python objects [*Literals and Identifiers* (page 20)]
- (b) They may only contain letters, digits, and the underscore, and cannot start with a digit. They are case sensitive. [*Literals and Identifiers* (page 20)]
- (c) You cannot use a reserved word as an identifier, nor are you recommended to redefine an identifier predefined by Python. In the Idle editor you are safe if your identifier names remain colored black. [*Literals and Identifiers* (page 20)]
- (d) By convention, multi-word identifiers either [*Literals and Identifiers* (page 20)]
 - i. use underscores in place of blanks (since blanks are illegal in identifiers), as in `initial_account_balance`
 - ii. use camel-case: all lowercase except for the starting letter of the second and later words, as in `initialAccountBalance`

12. Variables are identifiers used to name Python data [*Variables and Assignment* (page 18)]

When a variable is used in an expression, its latest value is substituted. [*Variables and Assignment* (page 18)]

13. Statements

- (a) Assignment statement: [*Variables and Assignment* (page 18)]

variable = expression

- i. The expression on the right is evaluated, using the latest values of all variables, and calculating all operations or functions specified.
- ii. The expression value is associated with the variable named on the left, removing any earlier association with the name.

- (b) For-statement

for **item** in *sequence* :

consistently indented statement block, which may use the variable *item*

For each element in the sequence, repeat the statement block substituting the next element in the sequence for the variable name *item*. See Programming Patterns for patterns of use. [*Basic for Loops* (page 49)]

- (c) Return statement

return *expression*

This is used only in a function definition, causing the function to immediately terminate and return the value of expression to the calling code, effectively acting as if the function call was replaced by this returned value. [*Returned Function Values* (page 38)]

14. Function calls

functionName (*expression* , *expression* , and so on)

- (a) The number of expressions must correspond to a number of parameters allowed by the function's definition. [*Function Parameters* (page 34)]

- (b) Even if there are no parameters, the parentheses must be included to distinguish the name of the function from a request to call the function. [*A First Function Definition* (page 30)]
- (c) Each *expression* is called an *actual parameter*. Each actual parameter is evaluated and the values are passed to the code for the function, which executes its defined steps and may return a value. If the function call was a part of a larger expression, the returned value is used to evaluate the larger expression in the place where the function call was. [*Function Parameters* (page 34)]
- (d) If nothing is returned explicitly, the function returns `None`.
- (e) Function calls may also be used as statements, in which case any value that is returned is ignored (except if entered directly into the shell, which prints any returned value other than `None`).
- (f) Keyword arguments are a special case. They have been used optionally at the end of the parameter list for `print`.

15. Functions that are built-in

- (a) Print function: [*Print Function, Part I* (page 21)] [*The print function keyword end* (page 61)]

```
print ( expression )
print ( expression , expression , expression )
print ( expression , expression , ``sep=strVal, end=strVal )
print ()
```

- i. Print the value of each expression in the list to the standard place for output (usually the screen) separating each value by individual blanks unless the keyword argument `sep` is specified to change it. There can be any number of expressions (not just 1-3 as illustrated).
 - ii. The string printed ends with a newline unless the keyword argument `end` is specified to change it.
 - iii. With no expression, the statement only advances to a new line.
- (b) A type name can be used as function to do obvious conversions to the type, as in `int('234')`, `float(123)`, `str(123)`. [*Numbers and Strings of Digits* (page 26)]
- (c) `type (expression)`
Return the type of the value of the *expression*. [*String Delimiters, Part I* (page 17)]
- (d) `input (promptString)`
Print the `promptString` to the screen; wait for the user to enter a line from the keyboard, ending with Enter. Return the character sequence as a string [*The input Function* (page 25)]
- (e) `len (sequence)`
Return the number of elements in the *sequence* [*Whirlwind Introduction To Types and Functions* (page 13)]
- (f) `range (expression)`
Require expression to have a non negative integer value, call it *n*. Generate a sequence with length *n*, consisting of the numbers 0 through *n*-1. For example `range(4)` generates the sequence 0, 1, 2, 3 [*The range Function, Part I* (page 48)]
- (g) `max (expression , expression , and so on)`
Return the maximum of all the expressions listed. [*Whirlwind Introduction To Types and Functions* (page 13)]

(h) `format (expression , formatString)`

If *expression* is numeric, the format string can be in the form '`.#f`', where the `#` gets replaced by a nonnegative integer, and the result is a string with the value of the expression rounded to the specified number of digits beyond the decimal point. [*Floats, Division, Mixed Types* (page 62)]

16. Functions defined by a user:

```
def functionName ( parameter1 , parameter2 , and so on ) :  
    consistently indented statement block, which may include a return statement
```

- (a) There may be any number of parameters. The parentheses must be included even if there are no parameters. [*Function Parameters* (page 34)]
- (b) When a function is first defined, it is only remembered: its lines are not executed. [*A First Function Definition* (page 30)]
- (c) When the function is later called in other code, the actual parameters in the function call are used to initialize the local variables *parameter1*, *parameter2*, and so on in the same order as the actual parameters. [*Function Parameters* (page 34)]
- (d) The local variables of a function are independent of the local names of any function defined outside of this function. The local variables must be initialized before use, and the names lose any association with their values when the function execution terminates. [*Local Scope* (page 41)]
- (e) If a return statement is reached, any further statements in the function are ignored. [*Returned Function Values* (page 38)]
- (f) Functions should be used to:
 - i. Emphasize that the code corresponds to one idea and give an easily recognizable name. [*A First Function Definition* (page 30)]
 - ii. Avoid repetition. If a basic idea is repeated with just the data changing, it will be easier to follow and use if it is coded once as a function with parameters, that gets called with the appropriate actual parameters when needed. [*Function Parameters* (page 34)]
 - iii. It is good to separate the internal processing of data from the input and output of data. This typically means placing the processing of data and the return of the result in a function. [*Function Parameters* (page 34)]
 - iv. Separate responsibilities: The consumer of a function only needs to know the name, parameter usage, and meaning of any returned value. Only the writer of a function needs to know the implementation of a function. [*Two Roles: Writer and Consumer of Functions* (page 40)]

17. Modules (program files)

- (a) A module may start with a documentation string. [*Program Documentation String* (page 24)]
- (b) Define your functions in your module. If the module is intended as a main program called only one way, a convention is make your execution just be calling a function called `main`. [*Multiple Function Definitions* (page 32)]
- (c) Avoid defining variable outside of your functions. Names for constant (unchanging) values are a reasonable exception. [*Global Constants* (page 42)]

18. Documentation String: A string, often a multi-line (triple quoted) string that may appear in two places:

- (a) At the very beginning of a file: This should give overall introductory information about the file [*Program Documentation String* (page 24)]

- (b) As the very first entry in the body of a function: This should describe: [*Definition and Use of Dictionaries* (page 42)]
 - i. The return value of the function (if there is one)
 - ii. Anything about the parameters that is not totally obvious from the names
 - iii. Anything about the results from the function that is not obvious from the name

19. Programming Patterns

- (a) Input-calculate-Output: This is the simplest overall program model. First obtain all the data you need (for instance by prompting the user for keyboard input). Calculate what you need from this data. Output the data (for instance to the screen with print functions). [*The input Function* (page 25)]
- (b) Repetitive patterns: These patterns are all associated with loops. Loops are essential if the number of repetitions depends on dynamic data in the program. Even if you could avoid a loop by repeating code, a loop is usually a better choice to make the repetitive logic of your program clear to all.
 - i. Exact repetition some number of times: If the number of time to repeat is n :

```
for _ in range( n ) :
    actions to be repeated
```

Here the variable `_` is included only because there must be a variable name in a `for` loop. [*Simple Repeat Loop* (page 52)]

- ii. For-each loop: Do the same sort of thing for each item in a specified sequence. [*Basic for Loops* (page 49)]

```
for item in sequence :
    actions to be done with each item
```

The sequence can be a range, where item is the next integer in the range.

- iii. Successive modification loop: Repeat a basic idea, but where the data involved each time changes via a pattern that is coded in the loop to convert the previous data into the data needed the next time through the loop [*Successive Modification Loops* (page 52)]:

```
initialize all variables that will be successively modified in the loop
loop heading for the repetition :
    actions to be in each loop with the current variable values
    modify the variable values to prepare for the next time through the loop
```

- iv. Accumulation loop: A sequence of items need to be combined. This works where the accumulation of all the items can be approached incrementally, combining one after another with the accumulation so far [*Accumulation Loops* (page 55)]:

```
initialize the accumulation to include none of the sequence
for item in sequence :
```

new value of **accumulation** = partial result

where the partial result comes from combining *item* with the current value of *accumulation*

20. Playing computer: following code line by line of execution. This either tests that you understand your code (and it works right) or it helps you find where it goes wrong. [*Updating Variables* (page 47), *Successive Modification* (page 52), *More Playing Computer* (page 58)]
- (a) Make sure line numbers are labeled
 - (b) Make a table with heading for line numbers, all variables that might be changing, and comments
 - (c) Follow the order of execution, one statement at a time, being careful to update variable values and only use the latest variable values, and carefully following the flow of control through loops and into and out of function calls. With loops and user function calls, the order is not just textual sequential order!

OBJECTS AND METHODS

2.1 Strings, Part III

2.1.1 Object Orientation

Python is an *object-oriented* language. Every piece of data and even functions and types are objects. The term object-oriented is used to distinguish Python from earlier languages, classified as *procedural* languages, where types of data and the operations on them were not connected in the language. The functions we have used so far follow the older procedural programming syntax. In the newer paradigm of object-oriented programming, all data are in objects, and a core group of operations that can be done on some particular type of object are tightly bound to the object and called the object's *methods*.

For example, strings are objects, and strings “know how” to produce an uppercase version of themselves. Try in the *Shell*:

```
s = 'Hello!'
s.upper()
```

Here `upper` is a *method* associated with strings. This means `upper` is a function that is bound to the string before the dot. This function is bound both logically, and as we see in the new notation, also syntactically. One way to think about it is that each type of data knows operations (methods) that can be applied to it. The expression `s.upper()` calls the method `upper` that is bound to the string `s` and *returns* a *new* uppercase string result based on `s`.

Strings are immutable, so no string method can change the original string, it can only return a new string. Confirm this by entering each line individually in the *Shell* to see the original `s` is unchanged:

```
s
s2 = s.upper()
s2
s
```

We are using the new object syntax:

object.method ()

meaning that the *method* associated with the object's type is applied to the *object*. This is just a special syntax for a function call with an object.

Another string method is `lower`, analogous to `upper`, but producing a lowercase result.

Test yourself: How would you write the expression to produce a lowercase version of the string `s`? Answer: ¹

Try it in the *Shell*.

¹ `s.lower()`

Test yourself in the Shell: How would you use this string `s` and both the `lower` and `upper` methods to create the string `'hello!HELLO!'`? Hint: ² Answer: ³

Many methods also take additional parameters between the parentheses, using the more general syntax:

`object.method(parameters)`

The first of many such methods we will introduce is `count`:

Syntax for `count`:

`s.count(sub)`

Count and return the number of repetitions of a string `sub` that appear as substrings inside the string `s`.

Read and make sure you see the answers are correct:

```
>>> tale = 'This is the best of times.'
>>> tale.count('i')
3
>>> tale.count('is')
2
>>> tale.count('That')
0
>>> tale.count(' ')
5
```

There is a blank between the quotes in the line above. Blanks are characters like any other (except you can't see them)!

Just as the parameter can be replaced by a literal or any expression, the object to which a method is bound with the dot may also be given by a literal, or a variable name, or any expression that evaluates to the right kind of object in its place. This is true for any method call.

Technically the dot between the object and the method name is an operator, and operators have different levels of precedence. It is important to realize that this dot operator has the *highest possible* precedence. *Read* and see the difference parentheses make in the expressions:

```
>>> 'hello ' + 'there'.upper()
'hello THERE'
>>> ('hello ' + 'there').upper()
'HELLO THERE'
```

To see if you understand this precedence, predict the results of each line and then test in the *Shell*:

```
3 * 'X'.count('XXX')
(3 * 'X').count('XXX')
```

There are 0 'XXX's in 'X', but 1 'XXX' in 'XXX'.

Python lets you see all the methods that are bound to an object (and any object of its type) with the built-in function `dir`. To see all string methods, supply the `dir` function with any string. For example, try in the *Shell*:

```
dir('')
```

Many of the names in the list start and end with two underscores, like `__add__`. These are all associated with methods and pieces of data used internally by the Python interpreter. You can ignore them for now. The remaining entries in the list are all user-level methods for strings. You should see `lower` and `upper` among them. Some of the methods are much more commonly used than others.

Object notation

² Use a plus sign to concatenate the pieces.

³ `s.lower() + s.upper()`

object.method (parameters)

has been illustrated so far with just the object type `str`, but it applies to all types. Later in the tutorial methods such as the following will be discussed:

If `seq` is a list, `seq.append(element)` appends `element` to the end of the list.

If `myData` is a file, `myData.read()` will read and return the entire contents of the file....

2.1.2 String Indices

A string is a sequence of smaller components (individual characters), and it is often useful to deal with parts of strings. Python *indexes* the characters in a string, starting from 0, so for instance, the characters in the string `'computer'` have indices:

character	c	o	m	p	u	t	e	r
index	0	1	2	3	4	5	6	7

Each index is associated with a character, and you reference the individual characters much like in a dictionary. Try the following. (You can skip the comments that make the indices explicit.) Enter in the *Shell*:

```
#      01234567
s = 'computer'
s[0]
s[5]
s[8]
```

You cannot refer directly to a character that is not there. Indices only go to 7 in the example above.

Recall the `len` function, which gives the length of a sequence. It works on strings. Guess the following value, and test in the *Shell*:

```
len(s)
```

A common error is to think the last index will be the same as the length of the string, but as you saw above, that leads to an execution error. If the length of some string is 5, what is the index of its last character? What if the length is 35?

Hopefully you did not count by ones all the way from 0. The indices for a string of length `n` are the elements of the sequence `range(n)`, which goes from 0 through `n-1`, or the length of the string minus one, which is `5-1=4` or `35-1=34` in these examples.

Sometimes you are interested in the last few elements of a string and do not want to do calculations like this. Python makes it easy. You can index from the *right* end of the string. Since positive integers are used to index from the front, negative integers are used to index from the right end, so the more complete table of indices for `'computer'` gives two alternatives for each character:

character	c	o	m	p	u	t	e	r
index	0	1	2	3	4	5	6	7
index from the right end	-8	-7	-6	-5	-4	-3	-2	-1

Predict and test each individual line, continuing in the *Shell*:

```
s[-1]
s[-3]
s[-10]

it = 'horse'
len(it)
it[-1]
it[1]
```

Be careful - remember what the initial index is!

2.1.3 String Slices

It is also useful to extract larger pieces of a string than a single character. That brings us to *slices*. Try this expression using slice notation, continuing in the *Shell*:

```
s[0:4]
```

Note that `s[4]` is the first character *past* the slice. The simplest syntax for a slice of a string `s` is:

```
s[ startIndex : pastIndex ]
```

This refers to the substring of `s` starting at index `startIndex` and stopping just *before* index `pastIndex`.

Warning: It confuses many people that the index after the colon is *not* the index of the final character in the slice. The second index is *past* the end of the slice.

Predict and try each line individually in the *Shell*:

```
s[2:5]
s[1:3]
```

If you omit the first index, the slice starts from the beginning. If you omit the second index, the slice goes all the way to the end. Predict and try each line individually in the *Shell*:

```
s[:3]
s[5:]
s[:]
```

Predict and try each line individually in the *Shell*:

```
word = 'program'
word[2:4]
word[1:-3]
word[3:]
word[3:3]
word[:1] + word[4:]
```

Python evaluates slices in a more forgiving manner than when indexing single characters. In a slice, if you give an index past a limit of where it could be, Python assumes you mean the actual end. Predict and try each line individually in the *Shell*:

```
word[:9]
word[8:10]
```

Enter a slice expression using the variable `word` from above that produces `'gra'`.

A useful string method that uses the ideas of indices and slices is `find`.

Syntax options for `find` method with a string `s`:

```
s.find(sub)
s.find(sub, start)
s.find(sub, start, end)
```

Return the integer index in the string `s` of the beginning of the first complete occurrence of the substring `sub`. If `sub` does not appear inside `s`, return -1. The value -1 would be an impossible result if `sub` were found, so if -1 is returned, `sub` must not have been found. If parameters `start` and `end` are not included in the parameter list, the search is

through the whole string `s`. If an integer value is given for *start*, the search starts at index *start*. If an integer value is given for *end*, the search ends *before* index *end*. In other words if *start* and *end* appear, then the search is through the slice `s[start : end]`, but the index returned is still counted from the beginning of `s`.

For example, check that the following make sense. The comment line is just there to help you count:

```
>>> #      01234567890
>>> s = 'Mississippi'
>>> s.find('i')
1
>>> s.find('si')
3
>>> s.find('sa')
-1
>>> s.find('si', 4)
6
```

Predict and try each line in the *Shell*:

```
#      0123456789012
line = 'Hello, there!'
line.find('e')
line.find('he')
line.find('e', 10)
line.find('he', 10)
```

We will consider more string methods later, but we can already do useful things with the ones introduced.

Inside the *Shell*, you can look up documentation on any of the methods listed with the `dir` function. Here is a place that you want to *refer* to the method itself, not *invoke* the method, so note that you get help for `s.find` not for `s.find()`. Assuming you defined the string `s` in the *Shell* earlier, try in the *Shell*

```
help(s.find)
```

The Python documentation uses square brackets to indicate optional elements which get a default value if you leave them out. This shortens the syntax descriptions.

If you want method documentation when you do not have a variable of the type created, you can also use the type name. Try in the *Shell*:

```
dir(str)
help(str.capitalize)
```

In the help documentation for a function with one or more parameters, you may see what looks like a final parameter `/`. Ignore it. It documents a technical restriction on parameters. It is not actually a parameter.

Indexing and slicing works on any kind of Python sequence, so you can index or slice lists also.* Read* this *Shell* session:

```
>>> vals = [5, 7, 9, 22, 6, 8]
>>> vals[1]
7
>>> vals[-2]
6
>>> vals[1:4]
[7, 9, 22]
```

Unlike strings, lists are mutable, as you will see in [Appending to a List](#) (page 80). Indices and slices can also be used in assignment statements to change lists, but in this tutorial we not need list indexing, and we will not discuss this subject further.

2.1.4 Index Variables

All the concrete examples in the last two sections used literal numbers for the indices. That is fine for learning the idea, but in practice, variables or expressions are almost always used for indices. As usual the variable or expression is evaluated before being used. Try in Idle and see that the example program `index1.py` makes sense:

```
s = 'word'
print('The full string is: ', s)
n = len(s)
for i in range(n):
    print()
    print('i =', i)
    print('The letter at index i:', s[i])
    print('The part before index i (if any):', s[:i])
    print('The part before index i+2:', s[:i+2])
```

We will use index variables in more practical situations as we explain more operations with strings.

2.1.5 split

Syntax options for the `split` method with a string `s`:

```
s.split()
s.split(sep)
```

The first version splits `s` at any sequence of whitespace (blanks, newlines, tabs) and returns the remaining parts of `s` as a list. If a string `sep` is specified, it is the separator that gets removed from between the parts of the list.

For example, read and follow:

```
>>> tale = 'This is the best of times.'
>>> tale.split()
['This', 'is', 'the', 'best', 'of', 'times.']
>>> s = 'Mississippi'
>>> s.split('i')
['M', 'ss', 'ss', 'pp', '']
>>> s.split() # no white space
['Mississippi']
```

Predict and test each line in the *Shell*:

```
line = 'Go: Tear some strings apart!'
seq = line.split()
seq
line.split(':')
line.split('ar')
lines = 'This includes\\nsome new\\nlines.'
lines.split()
```

2.1.6 join

Join is roughly the reverse of `split`. It joins together a sequence of strings. The syntax is rather different. The separator `sep` comes first, since it has the right type (a string).

Syntax for the `join` method:

```
sep.join(sequence)
```

Return a new string obtained by joining together the *sequence* of strings into one string, interleaving the string *sep* between *sequence* elements.

For example (continuing in the Shell from the previous section, using *seq*), follow:

```
>>> ' '.join(seq)
'Go: Tear some strings apart!'
>>> ''.join(seq)
'Go:Tearsomestringsapart!'
>>> '//'.join(seq)
'Go://Tear//some//strings//apart!'
```

Predict and try each line, continuing in the *Shell*:

```
'###'.join(seq)
':'.join(['one', 'two', 'three'])
```

The methods `split` and `join` are often used in sequence:

Underscore Exercise

Write a program `underscores.py` that would input a phrase from the user and print out the phrase with the white space between words replaced by an underscore. For instance if the input is `the best one`, then it would print `the_best_one`. The conversion can be done in one or two statements using the recent string methods.

Acronym Exercise

* An *acronym* is a string of capital letters formed by taking the first letters from a phrase. For example, SADD is an acronym for ‘students against drunk driving’. Note that the acronym should be composed of all capital letters even if the original words are not. Write a program `acronym.py` that has the user input a phrase and then prints the corresponding acronym.

To get you started, here are some things you will need to do. First check that you understand the basic syntax to accomplish the different individual tasks: Indicate the proper syntax using a Python function or operation will allow you to accomplish each task. Invent appropriate variable names for the different parts. These are not complete instructions! The idea is to make sure you know the basic syntax to use in all these situations. See the questions after the list to help you put together the final program.

1. What type of data will the input be? What type of data will the output be?
2. Get the phrase from the user.
3. Convert to upper case.
4. Divide the phrase into words.
5. Initialize a new empty list, `letters`.
6. Get the first letter of each word.
7. Append the first letter to the list `letters`.
8. Join the letters together, with no space between them.
9. Print the acronym.

Which of these steps is in a loop? What `for` statement controls this loop?

Put these ideas together and write and test your program `acronym.py`. Make sure you use names for the objects that are consistent from one line to the next! (You might not have done that when you first considered the syntax and ideas needed for 1-9 above individually.)

2.1.7 Further Exploration

As the `dir('')` list showed, there are many more operations on strings than we have discussed, and there are further variations of the ones above with more parameters. Methods `startswith`, `endswith`, and `replace` are discussed later in *More String Methods* (page 137). If you want to reach a systematic reference from inside Idle, go to *Help* → *Python Docs* → *Library Reference*, and find the section *Built-in Types*, and then the subsection for type `str`. Many methods use features we have not discussed yet, but currently accessible methods are `capitalize`, `title`, `strip`, `rfind`, ...

2.2 More Classes and Methods

The classes and methods introduced here are all used in the revised `mad lib` program developed in the next section.

2.2.1 Appending to a List

Before making a version of the `madlib` program that is much easier to use with new stories, we need a couple of facts about other types of objects that are built into Python.

So far we have used lists, but we have not changed the contents of lists. The most obvious way to change a list is to add a new element onto the end. Lists have the method `append`. It *modifies* the original list. Another word for modifiable is *mutable*. Lists are *mutable*. Most of the types of object considered so far (`int`, `str`, `float`) are *immutable* or *not* mutable. *Read* and see how the list named `words` changes:

```
>>> words = list()
>>> words
[]
>>> words.append('animal')
>>> words
['animal']
>>> words.append('food')
>>> words
['animal', 'food']
>>> words.append('city')
>>> words
['animal', 'food', 'city']
```

This is particularly useful in a loop, where we can accumulate a new list. *Read* the start of this simple example:

```
def multiplyAll(numList, multiplier):
    '''Return a new list containing all of the elements of numList,
    each multiplied by multiplier. For example:

    >>> print(multiplyAll([3, 1, 7], 5))
    [15, 5, 35]

    ...
    # more to come
```

Clearly this will be repetitious. We will process each element of the list `numList`. A for-each loop with `numList` is appropriate. Also we need to create more and more elements of the new list. The accumulation pattern will work here, with a couple of wrinkles.

Test yourself: If we are going to accumulate a list. How do we initialize the list?

In earlier versions of the accumulation loop, we needed an assignment statement to change the object doing the accumulating, but now the method `append` modifies its list automatically, so we do not need an assignment statement. Read and try the example program `multiply1.py`:

```
def multiplyAll(numList, multiplier):    #1
    '''Return a new list containing all
    of the elements of numList, each
    multiplied by multiplier. For example:

    >>> print(multiplyAll([3, 1, 7], 5))
    [15, 5, 35]
    '''

    newList = list()                  #2
    for num in numList:               #3
        newList.append(num*multiplier) #4
    return newList                   #5

print(multiplyAll([3, 1, 7], 5))      #6
```

Make sure the result makes sense to you or follow the details of playing computer below.

Line	numList	multiplier	newList	num	comment
1-5	-	-	-	-	definition
6	-	-	-	-	call function
1	[3, 1, 7]	5	-	-	set formal parameters
2	[3, 1, 7]	5	[]		
3	[3, 1, 7]	5	[]	3	first in list
4	[3, 1, 7]	5	[15]	3	append 3*5 = 15
3	[3, 1, 7]	5	[15]	1	next in list
4	[3, 1, 7]	5	[15, 5]	1	append 1*5 = 5
3	[3, 1, 7]	5	[15, 5]	7	last in list
4	[3, 1, 7]	5	[15, 5, 35]	7	append 7*5 = 35
3	[3, 1, 7]	5	[15, 5, 35]	7	done with list and loop
5	[3, 1, 7]	5	[15, 5, 35]	7	return [15, 5, 35]
6	-	-	-	-	print [15, 3, 35]

Using a for-loop and `append` is a powerful and flexible way to derive a new list, but not the only way.

2.2.2 Sets

A list may contain duplicates, as in `[2, 1, 3, 2, 5, 5, 2]`. This is sometimes useful, and sometimes not. You may have learned in math class that a *set* is a collection that does not allow repetitions (a set automatically removes repetitions suggested). Python has a type `set`. Like many type names, it can be used to convert other types. In this case it makes sense to convert any collection, and the process removes duplicates. *Read* and see what happens:

```
>>> strList = ['z', 'zz', 'c', 'z', 'bb', 'z', 'a', 'c']
>>> aSet = set(strList)
>>> aSet
{'bb', 'zz', 'a', 'c', 'z'}
```

(Technically, a set is unordered, so your version of Idle may list the set in a different order.) Set literals are enclosed in braces. Like other collections, a set can be used as a sequence in a `for` loop. *Read*, and check it makes sense:

```
>>> for s in aSet:
    print(s)
```

```
bb
zz
a
c
z
```

Predict the result of the following, and then paste it into the *Shell* and test. (You may not guess Python's order, but see if you can get the right length and the right elements in *some* order.)

```
set(['animal', 'food', 'animal', 'food', 'food', 'city'])
```

2.2.3 Constructors

We have now seen several examples of the name of a type being used as a function. *Read* these earlier examples:

```
x = int('123')
s = str(123)
nums = list()
aSet = set(numberList)
```

In all such cases a new object of the specified type is constructed and returned. Such functions are called *constructors*.

2.3 Mad Libs Revisited

2.3.1 A Function to Ease the Creation of Mad Libs

The versions so far of the Mad Lib program have been fairly easy to edit to contain a different mad lib:

1. Come up with a new mad lib story as a format string
2. Produce the list of cues to prompt the user with.

The first is a creative process. The second is a pretty mechanical process of looking at the story string and copying out the embedded cues. The first is best left to humans. The second can be turned over to a Python function to do automatically, as many times as we like, with any story - if we write the code once.

Writing the Python code also takes a different sort of creativity! We shall illustrate a creative process. This is a bigger problem than any we have taken on so far. It is hard to illustrate a creative process if the overall problem is too simple.

Try and follow along. *Read* the sample code and pseudo-code.

There is nothing to try in the Shell or editor until further notice.

If we follow the last version of the mad lib program, we had a loop iterating through the keys in the story, and making a dictionary entry for each key. The main idea we follow here is to use the format string to automatically generate the sequence of keys. Let us plan this unified task as a new function:

```
def getKeys(formatString):
    '''formatString is a format string with embedded dictionary keys.
    Return a list containing all the keys from the format string.'''
    # more to come
```

The keys we want are embedded like {animal}. There may be any number of them in the format string. This indeterminacy suggests a loop to extract them. At this point we have only considered `for` loops. There is no obvious useful sequence to iterate through in the loop. (We are trying to *create* such a sequence!) The only pattern we have discussed that does not actively process each element of a significant list is a repeat-loop, where we just use the loop to

repeat the correct number of times. This will work in this case. (There is a more efficient approach after we introduce *While Statements* (page 143), suggested in *Mad Lib While Exercise* (page 157).)

First: how many times do we want to pull out a key - once for each embedded format. So how do we count those?

The `count` method is obviously a way to count. However we must count a fixed string, and the whole embedded formats vary, with different keys in the middle. A common part is `'{'`, and this should not appear in the regular text of the story, so it will serve our purpose:

```
repetitions = formatString.count('{')
for i in range(repetitions):
    ...
```

This is certainly the most challenging code to date. Before jumping into writing it all precisely, we can give an overall plan in pseudo-code. For a plan we need an idea of what quantities we are keeping track of, and name them, and outline the sequence of operations with them.

Think about data to name:

In this case we are trying to find a list. We will need to extract one element at a time and add it to the list, so we need a list, say `keyList`.

The central task is to identifying the individual keys. When we find a key we can call it `key`.

Think about identifying the text of individual keys. This may be too hard to think of in the abstract, so let us use as a concrete example, and let us keep it simple for the moment. Suppose the data in `formatString` starts off as follows. The lines with numbers are added to help us refer to the indices. *Display* of possible data:

```
#          1111111111222222222233333333
# 01234567890123456789012345678901234567
'blah {animal} blah blah {food} ...'      # start of formatString
```

The first key is `'animal'` at `formatString[6:12]`. The next key is `'food'` at `formatString[25:29]`. To identify each key as part of `formatString` we need not only the variable `formatString`, but also index variables to locate the start and end of the slices. Obvious names for the indices are `start` and `end`. We want to keep them current so the next key slice will always be

```
key = formatString[start : end]
```

Let us now put this all in an overall plan. We will have to continuously modify the start and end indices, the key, and the list. We have a basic pattern for accumulating a list, involving initializing it and appending to it. We can organize a plan, partly fleshed out, with a couple of approximations still to be worked out. The parts that are not yet in Python are *emphasized*:

```
def getKeys(formatString):
    keyList = list()
    ?? other initializations ??
    repetitions = formatString.count('{')
    for i in range(repetitions):
        find the start and end of the next key
        key = formatString[start : end]
        keyList.append(key)
    return keyList
```

We can see that the main piece left is to find the start and end indices for each key. The important word is *find*: the method we consider is `find`. As with the plan for using `count` above, the beginnings of keys are identified by the specific string `'{'`. We can look first at

```
formatString.find('{')
```

but that is not the full solution. If we look at our concrete example, the value returned is 5, not 6. How in general would we locate the beginning of the slice we want?

We do not want the position of the '{', but the position just *after* the '{'. Since the length of '{' is 1, the correct position is $5+1 = 6$. We can generalize this to

```
start = formatString.find('{') + 1
```

OK, what about end? Clearly it is at the '}'. In this example,

```
formatString.find('}')
```

gives us 12, exactly the right place for the end of the slice (one place past the actual end).

There is a subtle issue here that will be even more important later: We will keep wanting to find the *next* brace, and not keep finding the *first* brace. How do we fix that?

Recall there was an alternate syntax for `find`, specifying the first place to search! That is what we need. Where should we start? Well, the end must come after the start of the key, our variable `start`:

```
start = formatString.find('{') + 1
end = formatString.find('}', start)
```

Figuring out how to find the first key is important, but we are not home free yet. We need to come up with code that works in a loop for the *later* keys. This code will not work for the next one. Why?

As written, the search for '{' will again start from the beginning of the format string, and will find the first key again. So what code will work for the *second* search? We search for the start of the next key going from the end of the last one:

```
start = formatString.find('{', end) + 1
end = formatString.find('}', start)
```

This code will also work for later times through the loop: each time uses the `end` from the previous time through the loop.

So now what do we do for finding the first key? We could separate the treatment of the first key from all the others, but an easier approach would be to see if we can use the same code that already works for the later repetitions, and initialize variables right to make it work. If we are to find the *first* key with

```
start = formatString.find('{', end) + 1
```

then what do we need? Clearly `end` needs to have a value. (There will not be a *previous* loop to give it a value.) What value should we initialize it to? The first search starts from the beginning of the string at index 0. The initialization goes before the loop, so the full code for this function is

```
def getKeys(formatString):
    '''formatString is a format string with embedded dictionary keys.
    Return a list containing all the keys from the format string.'''

    keyList = list()
    end = 0
    repetitions = formatString.count('{')
    for i in range(repetitions):
        start = formatString.find('{', end) + 1
        end = formatString.find('}', start)
        key = formatString[start : end]
        keyList.append(key)
```



```
return keyList
```

Look the code over and see that it makes sense. See how we continuously modify `start`, `end`, `key`, and `keyList`. Since we have coded this new part as a function, it is easy to test without running a whole revised mad lib program. We can just run this function on some test data, like the original story, and see what it does. Run the example program `testGetKeys.py`:

```
'''Test the function to extract keys from a format string for a dictionary.'''

def getKeys(formatString):
    '''formatString is a format string with embedded dictionary keys.
    Return a list containing all the keys from the format string.'''

    keyList = list()
    end = 0
    repetitions = formatString.count('{')
    for i in range(repetitions):
        start = formatString.find('{', end) + 1
        end = formatString.find('}', start)
        key = formatString[start : end]
        keyList.append(key)
    return keyList

originalStory = """
Once upon a time, deep in an ancient jungle,
there lived a {animal}. This {animal}
liked to eat {food}, but the jungle had
very little {food} to offer. One day, an
explorer found the {animal} and discovered
it liked {food}. The explorer took the
{animal} back to {city}, where it could
eat as much {food} as it wanted. However,
the {animal} became homesick, so the
explorer brought it back to the jungle,
leaving a large supply of {food}.

The End
"""

print(getKeys(originalStory))
```

The functions should behave as advertised.

Look back on the process described to come up with the `getKeys` function. One way of approaching the creative process of coding this function was provided. There are many other results and approaches possible, but the discussion did illustrate a number of useful ideas which you might adapt to other problems, in different orders and proportions, that are summarized in the next section.

2.3.2 Creative Problem Solving Steps

- Clearly define the problem. Encapsulating the problem in a function is useful, with inputs as parameters and results returned. Include a complete documentation string, and a clear example (or examples) of what it is to do.
- If the problem is too complicated to just solve easily, straight away, it is often useful to construct a representative *concrete* case and write down *concrete* steps appropriate to this problem.
- Think of the data in the problem, and give names to the pieces you will need to refer to. Clearly identify the

ideas that the names correspond to. When using sequences like lists or strings, you generally need names not only for the whole collection, but also parts like items and characters or substrings, and often indices that locate parts of the collection.

- Plan the overall approach to the problem using a mixture of Python and suggestive phrases (called pseudo-code). The idea is to refine it to a place where you can fairly easily figure how to replace the phrases with Python.
- Replace your pseudo-code parts with Python. If you had a concrete example to guide you, you may want to test with one of more further concrete examples with different specific data, to make sure you come up with code for a generalization that works in all cases. This is the process of *abstraction*.
- Recognize where something is being repeated over and over, and think how to structure appropriate loops. Can you incorporate any patterns you have seen before?
- If you need to create a successive modification loop, think of how to approach the first repetition and then how to modify the data for the later times through the loop. Usually you can make the first time through the loop fit the more general pattern needed for the repetitions by making appropriate initializations before the loop.
- Check and test your code, and correct as necessary.

2.3.3 The Revised Mad Lib Program

There is still an issue for use of `getKeys` in the mad lib program: the returned list has unwanted repetitions in it. We can easily create a collection without repetitions, how?

One approach is to make a `set` from the list returned. A neater approach would be to just have the `getKeys` function return a `set` in the first place. We need to slightly change to `getKeys`' documentation string and the final `return` line. This will be included in a new version of the mad lib program, which makes it easy to substitute a new story. We will make the story's format string be a parameter to the central method, `tellStory`. We will also put the clearly identified step of filling the dictionary with the user's picks in a separate function. We will test `tellStory` with the original story. Note the changes included in `madlib2.py` and run:

```
"""
madlib2.py
Interactive display of a mad lib, which is provided as a Python format string,
with all the cues being dictionary formats, in the form {cue}.

In this version, the cues are extracted from the story automatically,
and the user is prompted for the replacements.

Original verison adapted from code of Kirby Urner
"""

def getKeys(formatString):
    '''formatString is a format string with embedded dictionary keys.
    Return a set containing all the keys from the format string.'''

    keyList = list()
    end = 0
    repetitions = formatString.count('{')
    for i in range(repetitions):
        start = formatString.find('{', end) + 1 # pass the '{'
        end = formatString.find('}', start)
        key = formatString[start : end]
        keyList.append(key) # may add duplicates

    return set(keyList) # removes duplicates: no duplicates in a set
```

```

def addPick(cue, dictionary): # from madlib.py
    '''Prompt for a user response using the cue string,
    and place the cue-response pair in the dictionary.
    '''
    promptFormat = "Enter a specific example for {name}: "
    prompt = promptFormat.format(name=cue)
    response = input(prompt)
    dictionary[cue] = response

def getUserPicks(cues):
    '''Loop through the collection of cue keys and get user choices.
    Return the resulting dictionary.
    '''
    userPicks = dict()
    for cue in cues:
        addPick(cue, userPicks)
    return userPicks

def tellStory(storyFormat):
    '''storyFormat is a string with Python dictionary references embedded,
    in the form {cue}. Prompt the user for the mad lib substitutions
    and then print the resulting story with the substitutions.
    '''
    cues = getKeys(storyFormat)
    userPicks = getUserPicks(cues)
    story = storyFormat.format(**userPicks)
    print(story)

def main():
    originalStoryFormat = '''
    Once upon a time, deep in an ancient jungle,
    there lived a {animal}. This {animal}
    liked to eat {food}, but the jungle had
    very little {food} to offer. One day, an
    explorer found the {animal} and discovered
    it liked {food}. The explorer took the
    {animal} back to {city}, where it could
    eat as much {food} as it wanted. However,
    the {animal} became homesick, so the
    explorer brought it back to the jungle,
    leaving a large supply of {food}.

    The End
    '''
    tellStory(originalStoryFormat)
    input("Press Enter to end the program.")

main()

```

Does the use of well-named functions make it easier to follow this code? We have broken the large overall problem into many smaller steps. Make sure you follow the flow of execution and data and see how all the pieces fit together.

Substring Locations Exercise

* Rename the example file `locationsStub.py` to be `locations.py`, and complete the function `printLocations`, to print the index of *each* location in the string `s` where `target` is located. For example,

```
printLocations('This is a dish', 'is')
```

would go through the string `'This is a dish'` looking for the index of places where `'is'` appears, and would print:

```
2
5
11
```

Similarly

```
printLocations('This is a dish', 'h')
```

would print:

```
1
13
```

The program stub already uses the string method `count`. You will need to add code using the more general form of `find`.

2.4 Graphics

Graphics make programming more fun for many people. To fully introduce graphics would involve many ideas that would be a distraction now. This section introduces a simplified graphics module developed by John Zelle for use with his Python Programming book. My slight elaboration of his package is `graphics.py` in the example programs.

Warning: You need the file `graphics.py` in the same folder as any graphics program you write. Be sure to save any graphics program you write in such a folder (like my examples folder). The easiest way to ensure this is to start in the desired folder, as discussed in *Starting Idle for Editing* (page 23).

Warning: To work on the most systems, this version of `graphics.py` *cannot be used from the Idle shell*. There is an issue with the use of multiple threads of execution.

2.4.1 A Graphics Introduction

Note: You will just be a *user* of the `graphics.py` code, so you do *not* need to understand the inner workings! It uses all sorts of features of Python that are way beyond these tutorials. There is *no particular need* to open `graphics.py` in the Idle editor.

Load into Idle and start running example `graphIntroSteps.py`, or start running from the operating system folder. Each time you press return, look at the screen and read the explanation for the next line(s).

Press return:

```
from graphics import *
win = GraphWin()
```

Zelle's graphics are not a part of the standard Python distribution. For the Python interpreter to find Zelle's module, it must be *imported*. The first line above makes all the types of object of Zelle's module accessible, as if they were already defined like built-in types `str` or `list`.

Look around on your screen, and possibly *underneath* other windows: There should be a new window labeled "Graphics Window", created by the second line. Bring it to the top, and preferably drag it around to make it visible beside your Shell window. A `GraphWin` is a type of object from Zelle's graphics package that automatically displays a window when it is created. The assignment statement remembers the window object as `win` for future reference. (This will be our standard name for our graphics window object.) A small window, 200 by 200 *pixels* is created. A *pixel* is the smallest little square that can be displayed on your screen. Modern screen usually have more than 1000 pixels across the whole screen.

Press return:

```
pt = Point(100, 50)
```

This creates a `Point` object and assigns it the name `pt`. Unlike when a `GraphWin` is created, *nothing is immediately displayed*: In theory you could have more than one `GraphWin`. Zelle designed the graphics module so you must tell Python into *which* `GraphWin` to draw the `Point`. A `Point` object, like each of the graphical objects that can be drawn on a `GraphWin`, has a method⁴ `draw`.

Press return:

```
pt.draw(win)
```

Now you should see the `Point` if you look hard in the Graphics Window - it shows as a single, small, black pixel. Graphics windows have a Cartesian (x,y) coordinate system. The dimensions are initially measured in pixels. The first coordinate is the horizontal coordinate, measured from left to right, so 100 is about half way across the 200 pixel wide window. The second coordinate, for the vertical direction, increases going *down* from the top of the window by default, not *up* as you are likely to expect from geometry or algebra class. The coordinate 50 out of the total 200 vertically should be about 1/4 of the way *down* from the top. We will see later that we can reorient the coordinate system to fit our taste.

Henceforth you will see a `draw` method call after each object is created, so there is something to see.

Press return:

```
cir = Circle(pt, 25)
cir.draw(win)
```

The first line creates a `Circle` object with center at the previously defined `pt` and with radius 25. This object is remembered with the name `cir`. As with all graphics objects that may be drawn within a `GraphWin`, it is only made visible by explicitly using its `draw` method.

So far, everything has been drawn in the default color black. Graphics objects like a `Circle` have methods to change their colors. Basic color name strings are recognized. You can choose the color for the circle outline as well as filling in the inside.

Press return:

```
cir.setOutline('red')
cir.setFill('blue')
```

Note the method names. They can be used with other kinds of Graphics objects, too. (We delay a discussion of fancier colors until *Color Names* (page 111) and *Custom Colors* (page 112).)

Press return:

⁴ The basic ideas of objects and methods were introduced in *Object Orientation* (page 73).

```
line = Line(pt, Point(150, 100))
line.draw(win)
```

A `Line` object is constructed with two `Points` as parameters. In this case we use the previously named `Point`, `pt`, and specify another `Point` directly. Technically the `Line` object is a *segment* between the two points.

Warning: In Python `(150, 100)` is a tuple, *not* a `Point`. To make a `Point`, you must use the full constructor: `Point(150, 100)`. Points, not tuples, must be used in the constructors for *all* graphics objects.

A rectangle is also specified by two points. The points must be diagonally opposite corners.

Press return:

```
rect = Rectangle(Point(20, 10), pt)
rect.draw(win)
```

In this simple system, a `Rectangle` is restricted to have horizontal and vertical sides. A `Polygon`, introduced in the next section, is used for all more general straight-sided shapes.

You can move objects around in a `GraphWin`. Shortly this will be handy for animation. The parameters to the `move` method are the amount to shift the `x` and `y` coordinates. See if you can guess the result before you *press return*:

```
line.move(10, 40)
```

Did you remember that the `y` coordinate increases *down* the screen?

Take your last look at the Graphics Window, and make sure that all the steps make sense. Then destroy the window `win` with the `GraphWin` method `close`.

Press return:

```
win.close()
```

The example program `graphIntro.py` starts with the same graphics code as `graphIntroSteps.py`, but without the need for pressing returns.

An addition I have made to Zelle's package is the ability to print a string value of graphics objects for debugging purposes. If some graphics object isn't visible because it is underneath something else or off the screen, temporarily adding this sort of output might be a good reality check.

At the end of `graphIntro.py`, I added print lines to illustrate the debugging possibilities:

```
print('cir:', cir)
print('line:', line)
print('rect:', rect)
```

You can load `graphIntro.py` into `Idle`, run it, and add further lines to experiment if you like. Of course you will not see their effect until you run the whole program! Unfortunately the graphics do not work when entered directly into the Shell.

2.4.2 Sample Graphics Programs

In `graphIntro.py`, a prompt to end the graphics program appeared in the Shell window, requiring you to pay attention to two windows. Instead consider a very simple example program, `face.py`, where all the action takes place in the graphics window. The only interaction is to click the mouse to close the graphics window.

In Windows, have a folder window open to the Python examples folder containing `face.py`, where your operating system setup may allow you to just double click on the icon for `face.py` to run it. If that does not work on your system, you can always run from inside Idle.

After you have checked out the picture, click with the mouse inside the picture, as requested, to terminate the program.

After you have run the program, you can examine the program in Idle or look below. The whole program is shown first; smaller pieces of it are discussed later:

```
'''A simple graphics example constructs a face from basic shapes.
'''

from graphics import *

def main():
    win = GraphWin('Face', 200, 150) # give title and dimensions
    win.yUp() # make right side up coordinates!

    head = Circle(Point(40,100), 25) # set center and radius
    head.setFill("yellow")
    head.draw(win)

    eye1 = Circle(Point(30, 105), 5)
    eye1.setFill('blue')
    eye1.draw(win)

    eye2 = Line(Point(45, 105), Point(55, 105)) # set endpoints
    eye2.setWidth(3)
    eye2.draw(win)

    mouth = Oval(Point(30, 90), Point(50, 85)) # set corners of bounding box
    mouth.setFill("red")
    mouth.draw(win)

    label = Text(Point(100, 120), 'A face')
    label.draw(win)

    message = Text(Point(win.getWidth()/2, 20), 'Click anywhere to quit.')
    message.draw(win)
    win.getMouse()
    win.close()

main()
```

Let us look at individual parts.

Until further notice the set-off code is for you to read and have explained.

```
from graphics import *
```

Immediately after the documentation string, always have the import line in your graphics program, to allow easy access to the `graphics.py` module.

```
win = GraphWin('Face', 200, 150) # give title and dimensions
win.yUp() # make right side up coordinates!
```

The first line shows the more *general* parameters for constructing a new `GraphWin`, a window title plus width and height in pixels. The second line shows how to turn the coordinate system right-side-up, so the y coordinate increases up the screen, using the `yUp` method. (This is one of my additions to Zelle's graphics.) Thereafter, all coordinates are

given in the new coordinate system. All the lines of code up to this point in the program are my *standard* graphics program starting lines (other than the specific values for the title and dimensions). You will likely start your programs with similar code.

```
head = Circle(Point(40,100), 25) # set center and radius
head.setFill('yellow')
head.draw(win)

eye1 = Circle(Point(30, 105), 5)
eye1.setFill('blue')
eye1.draw(win)
```

The lines above create two circles, in each case specifying the centers directly. They are filled in and made visible. Also note, that because the earlier `win.yUp` call put the coordinates in the normal orientation, the y coordinate, 100 and 105, are above the middle of the 150 pixel high window.

If the code was switched to put the head part second, the eye would become hidden. The most recent thing drawn is on top.

```
eye2 = Line(Point(45, 105), Point(55, 105)) # set endpoints
eye2.setWidth(3)
eye2.draw(win)
```

The code above draws and displays a line, and illustrates another method available to graphics object, `setWidth`, making a *thicker* line.

```
mouth = Oval(Point(30, 90), Point(50, 85)) # set corners of bounding box
mouth.setFill('red')
mouth.draw(win)
```

The code above illustrates another kind of graphics object, an `Oval` (or ellipse). There are several ways an oval could be specified. Zelle chose to have you specify the corners of the bounding box that is just as high and as wide as the oval. This rectangle is only imagined, not actually drawn. (If you want to see such a rectangle, create a `Rectangle` object with the same two `Points` as parameters....)

```
label = Text(Point(100, 120), 'A face')
label.draw(win)
```

The code above illustrates how a `Text` object is used to place text on the window. The parameters to construct the `Text` object are the point at the *center* of the text, and the text string itself.

The exact coordinates for the parts were determined by a number of trial-and-error refinements to the program. An advantage of graphics is that you can *see* the results of your programming, and make changes if you do not like the results! In this simple system, there is not a good way to predict the dimensions of text on the screen.

The final action is to have the user signal to close the window. Just as with waiting for keyboard input from `input`, it is important to *prompt* the user before waiting for a response! In a `GraphWin`, that means using `prompt` must be made with a `Text` object displayed explicitly before the response is expected.

```
message = Text(Point(win.getWidth()/2, 20), 'Click anywhere to quit.')
message.draw(win)
win.getMouse()
win.close()
```

The new addition to the `Text` parameters here is `win.getWidth()` to obtain the window width. (There is also a `win.getHeight()`.) Using `win.getWidth()/2` means the horizontal position is set up to be centered, half way across the window's width.

After the first two lines draw the prompting text, the line `win.getMouse()` *waits* for a mouse click. In this program, the position of the mouse click is not important. (In the next example the position of this mouse click will be used.)

As you have seen before, `win.close()` closes the graphics window.

While our earlier text-based Python programs have automatically terminated after the last line finishes executing, that is not true for programs that create new windows: The graphics window must be explicitly closed. The `win.close()` is necessary.

We will generally want to prompt the user to finally close the graphics window. Because such a sequence is so common, I have added another method for Zelle's `GraphWin` objects, `promptClose`, so the last four lines can be reduced to

```
win.promptClose(win.getWidth()/2, 20)
```

where the only specific data needed is the coordinates of the center of the prompt.

The modified program is in `face2.py`. You can copy the form of this program for other simple programs that just draw a picture. The size and title on the window will change, as well as the specific graphical objects, positions, and colors. Something like the last line can be used to terminate the program.

Warning: If you write a program with a bug, and the program bombs out while there is a `GraphWin` on the screen, a dead `GraphWin` lingers. The best way to clean things up is to make the Shell window be the current window and select from the menu *Shell* → *Restart Shell*.

Another simple drawing example is `balloons.py`. Feel free to run it and look at the code in Idle. Note that the steps for the creation of all three balloons are identical, except for the location of the center of each balloon, so a loop over a list of the centers makes sense.

The next example, `triangle.py`, illustrates similar starting and ending code. In addition it explicitly interacts with the user. Rather than the code specifying literal coordinates for all graphical objects, the program remembers the Points where the user clicked the mouse. They are used as the vertices of a triangle.

Return to the directory window for the Python examples. In Windows you may be able to double click on the icon for `triangle.py` to run it. Or on a Mac, you can run it using the Python Launcher, rather than Idle.

While running the program, follow the prompts in the graphics window and click with the mouse as requested.

After you have run the program, you can examine the program in Idle or look below:

```
'''Program: triangle.py or triangle.pyw (best name for Windows)
Interactive graphics program to draw a triangle,
with prompts in a Text object and feedback via mouse clicks.
'''

from graphics import *

def main():
    win = GraphWin('Draw a Triangle', 350, 350)
    win.yUp() # right side up coordinates
    win.setBackground('yellow')
    message = Text(Point(win.getWidth()/2, 30), 'Click on three points')
    message.setTextColor('red')
    message.setStyle('italic')
    message.setSize(20)
    message.draw(win)

    # Get and draw three vertices of triangle
    p1 = win.getMouse()
    p1.draw(win)
    p2 = win.getMouse()
    p2.draw(win)
    p3 = win.getMouse()
```

```
p3.draw(win)
vertices = [p1, p2, p3]

# Use Polygon object to draw the triangle
triangle = Polygon(vertices)
triangle.setFill('gray')
triangle.setOutline('cyan')
triangle.setWidth(4) # width of boundary line
triangle.draw(win)

message.setText('Click anywhere to quit') # change text message
win.getMouse()
win.close()

main()
```

Let us look at individual parts.

The lines *before* the new line:

```
win.setBackground('yellow')
```

are standard starting lines (except for the specific values chosen for the width, height, and title). The background color is a property of the whole graphics window that you can set.

```
message = Text(Point(win.getWidth()/2, 20), 'Click on three points')
message.setTextColor('red')
message.setStyle('italic')
message.setSize(20)
message.draw(win)
```

Again a `Text` object is created. This is the prompt for user action. These lines illustrate most of the ways the appearance of a `Text` object may be modified, with results like in most word processors. The reference pages for `graphics.py` give the details. This reference is introduced shortly in *The Documentation for graphics.py* (page 96).

After the prompt, the program looks for a response:

```
# Get and draw three vertices of triangle
p1 = win.getMouse()
p1.draw(win)

p2 = win.getMouse()
p2.draw(win)

p3 = win.getMouse()
p3.draw(win)
```

The `win.getMouse()` method (with no parameters), waits for you to click the mouse inside `win`. Then the `Point` where the mouse was clicked is *returned*. In this code three mouse clicks are waited for, remembered in variables `p1`, `p2`, and `p3`, and the points are drawn.

Next we introduce a very versatile type of graphical object, a `Polygon`, which may have any number of vertices specified in a list as its parameter. We see that the methods `setFill` and `setOutline` that we used earlier on a `Circle`, and the `setWidth` method we used for a `Line`, also apply to a `Polygon`, (and also to other `graphics` objects).

```
vertices = [p1, p2, p3]
triangle = Polygon(vertices)
triangle.setFill('gray')
triangle.setOutline('cyan')
```

```
triangle.setWidth(4)
triangle.draw(win)
```

Besides changing the style of a Text object, the text itself may be changed:

```
message.setText('Click anywhere to quit')
```

Then lines responding to this prompt:

```
win.getMouse()
win.close()
```

If you want to use an existing Text object to display the quitting prompt, as I did here, I provide a variation on my window closing method that could replace the last three lines:

```
win.promptClose(message)
```

An existing Text object may be given as parameter rather than coordinates for a new text object. The complete code with that substitution is in `triangle2.py`.

If you want to make regular polygons or stars, you need some trigonometry, *not required for this tutorial*, but you can see its use in example `polygons.py`.

2.4.3 A Windows Operating System Specialization: .pyw

This Windows-specific section is not essential. It does describe how to make some Windows graphical programs run with less clutter.

If you ran the `triangle.py` program by double clicking its icon under Windows, you might have noticed a console window first appearing, followed by the graphics window. For this program, there was no keyboard input or screen output through the console window, so the console window was unused and unnecessary. In such cases, under Windows, you can change the source file extension from `.py` to `.pyw`, suppressing the display of the console window. If you are using Windows, change the filename `triangle.py` to `triangle.pyw`, double click on the icon in its directory folder, and check it out.

The distinction is irrelevant inside Idle, which always has its Shell window.

2.4.4 Graphics.py vs. Event Driven Graphics

This optional section only looks forward to more elaborate graphics systems than are used in this tutorial.

One limitation of the `graphics.py` module is that it is not robust if a graphics window is closed by clicking on the standard operating system close button on the title bar. If you close a graphics window that way, you are likely to get a Python error message. On the other hand, if your program creates a graphics window and then terminates abnormally due to some *other* error, the graphics window may be left orphaned. In this case the close button on the title bar is important: it is the easiest method to clean up and get rid of the window!

This lack of robustness is tied to the simplification designed into the `graphics` module. Modern graphics environments are *event driven*. The program can be interrupted by input from many sources including mouse clicks and key presses. This style of programming has a considerable learning curve. In Zelle's `graphics` package, the complexities of the event driven model are pretty well hidden. If the programmer wants user input, only one type can be specified at a time (either a mouse click in the graphics window via the `getMouse` method, or via the `input` keyboard entry methods into the Shell window).

2.4.5 The Documentation for `graphics.py`

Thus far various parts of Zelle's graphics package have been introduced by example. A systematic reference to Zelle's graphics package with the form of all function calls is at <http://mcsp.wartburg.edu/zelle/python/graphics/graphics/index.html>. We have introduced most of the important concepts and methods.

One special graphics input object type, `Entry`, will be discussed later. You might skip it for now. Another section of the reference that will not be pursued in the tutorials is the `Image` class.

Meanwhile you can look at <http://mcsp.wartburg.edu/zelle/python/graphics/graphics/index.html>. It is important to pay attention to the organization of the reference: Most graphics object share a number of common methods. Those methods are described together, first. Then, under the headings for specific types, only the specialized additional methods are discussed.

The version for this Tutorial has a few elaborations. Here is all their documentation together:

GraphWin method `yUp` (y increases upward) When you first create a `GraphWin`, the y coordinates increase down the screen. To reverse to the normal orientation use my `GraphWin yUp` method.

```
win = Graphwin('Right side up', 300, 400)
win.yUp()
```

GraphWin method `promptClose` (Prompt and Close Graphics Window) You generally want to continue displaying your graphics window until the user chooses to have it closed. The `GraphWin promptClose` method posts a prompt, waits for a mouse click, and closes the `GraphWin`. There are two ways to call it, depending on whether you want to use an existing `Text` object, or just specify a location for the center of the prompt.

```
win.promptClose(win.getWidth()/2, 30) # specify x, y coordinates of prompt
```

or

```
msg = Text(Point(100, 50), 'Original message...')
msg.draw(win)
# ...
# ... just important that there is a drawn Text object
win.promptClose(msg) # use existing Text object
```

String Representations of all Graphics Object Types Each graphical type can be converted to a string or printed, and a descriptive string is produced (for debugging purposes). It only shows position, not other parts of the state of the object.

```
>>> pt = Point(30, 50)
>>> print(pt)
Point(30, 50)
>>> ln = Line(pt, Point(100, 150))
>>> print(ln)
Line(Point(30, 50), Point(100, 150))
```

Scene Exercise

Make a program `scene.py` creating a scene with the graphics methods. You are likely to need to adjust the positions of objects by trial and error until you get the positions you want. *Make sure you have `graphics.py` in the same directory as your program.*

Changing Scene Exercise

Elaborate the scene program above so it becomes `changeScene.py`, and changes one or more times when you click the mouse (and use `win.getMouse()`). You may use the position of the mouse click to affect the result, or it may just indicate you are ready to go on to the next view.

2.4.6 Issues with Mutable Objects

Zelle chose to have the constructor for a `Rectangle` take diagonally opposite corner points as parameters. Suppose you prefer to specify only one corner and also specify the width and height of the rectangle. You might come up with the following function, `makeRect`, to return such a new `Rectangle`. *Read* the following attempt:

```
def makeRect(corner, width, height):
    '''Return a new Rectangle given one corner Point and the dimensions.'''
    corner2 = corner
    corner2.move(width, height)
    return Rectangle(corner, corner2)
```

The second corner must be created to use in the `Rectangle` constructor, and it is done above in two steps. Start `corner2` from the given `corner` and shift it by the dimensions of the `Rectangle` to the other corner. With both corners specified, you can use Zelle's version of the `Rectangle` constructor.

Unfortunately this is an *incorrect* argument. Run the example program `makeRectBad.py`:

```
'''Program: makeRectBad.py
Attempt a function makeRect (incorrectly),
which takes a takes a corner point and dimensions to construct a Rectangle.
'''

from graphics import *

def makeRect(corner, width, height): # Incorrect!
    '''Return a new Rectangle given one corner Point and the dimensions.'''
    corner2 = corner
    corner2.move(width, height)
    return Rectangle(corner, corner2)

def main():
    win = GraphWin('Draw a Rectangle (NOT!)', 300, 300)
    win.yUp()

    rect = makeRect(Point(20, 50), 250, 200)
    rect.draw(win)

    win.promptClose(win.getWidth()/2, 20)

main()
```


By stated design, this program should draw a rectangle with one corner at the point (20,50) and the other corner at (20+250,50+200) or the point (270,250), and so the rectangle should take up most of the 300 by 300 window. When you run it however that is not what you see. Look carefully. You should just see one `Point` toward the upper right corner, where the second corner *should* be. Since a `Rectangle` was being drawn, it looks like it is the tiniest of Rectangles, where the opposite corners are at the same point! Hm, well the program *did* make the corners be the same *initially*. Recall we set

```
corner2 = corner
```


What happens after that?

Read and follow the details of what happens.

We need to take a much more careful look at what naming an object means. A good way to visualize this association between a name and an object is to draw an arrow from the name to the object associated with it. The object here is a `Point`, which has an `x` and `y` coordinate describing its state, so when the `makeRect` method is started the parameter name `corner` is associated with the actual parameter, a `Point` with coordinates (20, 50).




Next, the assignment statement associates the name `corner2` with the same object. It is another name, or *alias*, for the original `Point`.



The next line,

```
corner2.move(width, height)
```

internally changes or *mutates* the `Point` object, and since in this case `width` is 250 and `height` is 200, the coordinates of the `Point` associated with the name `corner2` change to $20+250=270$ and $50+200=250$:



Look! The name `corner` is still associated with the same object, but that object has changed internally! That is the problem: we wanted to keep the name `corner` associated with the point with *original* coordinates, but it has been *modified*.


The solution is to use the `clone` method that is defined for all the graphical objects in `graphics.py`. It creates a *separate* object, which is a copy with an equivalent state. We just need to change the line

```
corner2 = corner
```

to

```
corner2 = corner.clone()
```


A diagram of the situation after the cloning is:



Though `corner` and `corner2` refer to points with equivalent coordinates, they do not refer to the same *object*. Then after

```
corner2.move(width, height)
```

we get:



No conflict: `corner` and `corner2` refer to the corners we want. Run the corrected example program, `makeRectangle.py`.

2.4.7 More on Mutable and Immutable Types

Read this section if you want a deeper understanding of the significance of mutable and immutable objects.


This alias problem only came up because a `Point` is mutable. We had no such problems with the immutable types `int` or `str`.

Read and follow the discussion of the following code.


Just for comparison, consider the corresponding diagrams for code with `ints` that looks superficially similar:

```
a = 2
b = a
b = b + 3
```

After the first two lines we have an alias again:



The third line does not change the `int` object 2. The result of the addition operation refers to a *different* object, 5, and the name `b` is assigned to it:



Hence `a` is still associated with the integer 2 - no conflict.

It is not technically correct to think of `b` as *being* the number 2, and then 5, but a little sloppiness of thought does not get you in trouble with *immutable* types. With mutable types, however, be very careful of aliases. Then it is very important to remember the indirectness: that a name is not the same thing as the object it refers to.

Another mutable type is `list`. A list can be cloned with the slice notation: `[:]`. Try the following in the *Shell*:⁵

```
nums = [1, 2, 3]
numsAlias = nums
numsClone = nums[:]
nums.append(4)
numsAlias.append(5)
nums
numsAlias
numsClone
```

2.4.8 Animation

Run the example program, `backAndForth0.py`. The whole program is shown below for convenience. Then each individual new part of the code is discussed individually:

```
'''Test animation and depth.
'''

from graphics import *
import time
```

⁵ Actually, lists are even trickier, because individual elements of a `list` may be *mutable*: Each mutable element in the cloned list is an *alias* of the corresponding element in the original list, so if you *mutate* its state in the cloned list, you also make a change to the original list. This is distinct from the situation if you *replace* an element in the cloned list by a totally different one: then you do not change the original list.


```
def main():
    win = GraphWin('Back and Forth', 300, 300)
    win.yUp() # make right side up coordinates!

    rect = Rectangle(Point(200, 90), Point(220, 100))
    rect.setFill("blue")
    rect.draw(win)

    cir1 = Circle(Point(40,100), 25)
    cir1.setFill("yellow")
    cir1.draw(win)

    cir2 = Circle(Point(150,125), 25)
    cir2.setFill("red")
    cir2.draw(win)

    for i in range(46):
        cir1.move(5, 0)
        time.sleep(.05)

    for i in range(46):
        cir1.move(-5, 0)
        time.sleep(.05)

    win.promptClose(win.getWidth()/2, 20)

main()
```

Read the discussion below of pieces of the code from the program above. Do not try to execute fragments alone.

There are both an old and a new form of import statement:

```
from graphics import *
import time
```

The program uses a function from the time module. The syntax used for the time module is actually the safer and more typical way to import a module. As you will see later in the program, the `sleep` function used from the `time` module will be referenced as `time.sleep()`. This tells the Python interpreter to look in the `time` module for the `sleep` function.

If we had used the `import` statement

```
from time import *
```

then the `sleep` function could just be referenced with `sleep()`. This is obviously easier, but it obscures the fact that the `sleep` function is not a part of the current module. Also several modules that a program imports might have functions with the same name. With the individual module name prefix, there is no ambiguity. Hence the form `import moduleName` is actually safer than `from moduleName import *`.

You might think that all modules could avoid using any of the same function names with a bit of planning. To get an idea of the magnitude of the issue, have a look at the number of modules available to Python. Try the following in the *Shell* (and likely wait a number of seconds):

```
help('modules')
```

Without module names to separate things out, it would be very hard to totally avoid name collisions with the enormous number of modules you see displayed, that are all available to Python!

Back to the current example program: The main program starts with standard window creation, and then makes three objects:

```
rect = Rectangle(Point(200, 90), Point(220, 100))
rect.setFill('blue')
rect.draw(win)

cir1 = Circle(Point(40,100), 25)
cir1.setFill('yellow')
cir1.draw(win)

cir2 = Circle(Point(150,125), 25)
cir2.setFill('red')
cir2.draw(win)
```

Zelle's reference pages do not mention the fact that the *order* in which these object are first *drawn* is significant. If objects overlap, the ones which used the draw method later appear on top. Other object methods like `setFill` or `move` do not alter which are in front of which. This becomes significant when `cir1` moves. The moving `cir1` goes over the rectangle and behind `cir2`. (Run the program again if you missed that.)

The animation starts with the code for a simple repeat loop:

```
for i in range(46): # animate cir1 to the right
    cir1.move(5, 0)
    time.sleep(.05)
```

This very simple loop animates `cir1` moving in a straight line to the right. As in a movie, the illusion of continuous motion is given by jumping only a short distance each time (increasing the horizontal coordinate by 5). The `time.sleep` function, mentioned earlier, takes as parameter a time in seconds to have the program sleep, or delay, before continuing with the iteration of the loop. This delay is important, because modern computers are so fast, that the intermediate motion would be invisible without the delay. The delay can be given as a decimal, to allow the time to be a fraction of a second.

The next three lines are almost identical to the previous lines, and move the circle to the left (-5 in the horizontal coordinate each time).

```
for i in range(46): # animate cir1 to the left
    cir1.move(-5, 0)
    time.sleep(.05)
```

The next example program, `backAndForth1.py`, is just a slight variation, looking to the user just like the last version. Only the small changes are shown below. This version was written after noticing how similar the two animation loops are, suggesting an improvement to the program: Animating any object to move in a straight line is a logical abstraction well expressed via a function.

The loop in the initial version of the program contained a number of arbitrarily chosen constants, which make sense to turn into parameters. Also, the object to be animated does not need to be `cir1`, it can be any of the drawable objects in the graphics package. The name `shape` is used to make this a parameter:

```
def moveOnLine(shape, dx, dy, repetitions, delay):
    for i in range(repetitions):
        shape.move(dx, dy)
        time.sleep(delay)
```

Then in the main function the two similar animation loops are reduced to a line for each direction:

```
moveOnLine(cir1, 5, 0, 46, .05)
moveOnLine(cir1, -5, 0, 46, .05)
```

Make sure you see these two lines with function calls behave the same way as the two animation loops in the main program of the original version.

Run the next example version, `backAndForth2.py`. The changes are more substantial here, and the display of the whole program is followed by display and discussion of the individual changes:

```
'''Test animation of a group of objects making a face.
'''

from graphics import *
import time

def moveAll(shapeList, dx, dy):
    ''' Move all shapes in shapeList by (dx, dy).'''
    for shape in shapeList:
        shape.move(dx, dy)

def moveAllOnLine(shapeList, dx, dy, repetitions, delay):
    '''Animate the shapes in shapeList along a line.
    Move by (dx, dy) each time.
    Repeat the specified number of repetitions.
    Have the specified delay (in seconds) after each repeat.
    '''
    for i in range(repetitions):
        moveAll(shapeList, dx, dy)
        time.sleep(delay)

def main():
    win = GraphWin('Back and Forth', 300, 300)
    win.yUp() # make right side up coordinates!

    rect = Rectangle(Point(200, 90), Point(220, 100))
    rect.setFill("blue")
    rect.draw(win)

    head = Circle(Point(40,100), 25)
    head.setFill("yellow")
    head.draw(win)

    eye1 = Circle(Point(30, 105), 5)
    eye1.setFill('blue')
    eye1.draw(win)

    eye2 = Line(Point(45, 105), Point(55, 105))
    eye2.setWidth(3)
    eye2.draw(win)

    mouth = Oval(Point(30, 90), Point(50, 85))
    mouth.setFill("red")
    mouth.draw(win)

    faceList = [head, eye1, eye2, mouth]

    cir2 = Circle(Point(150,125), 25)
    cir2.setFill("red")
    cir2.draw(win)

    moveAllOnLine(faceList, 5, 0, 46, .05)
    moveAllOnLine(faceList, -5, 0, 46, .05)
```

```
win.promptClose(win.getWidth()/2, 20)

main()
```

Read the following discussion of program parts.

Moving a single elementary shape is rather limiting. It is much more interesting to compose a more complicated combination, like the face from the earlier example `face.py`. To animate such a combination, you cannot use the old `moveOnLine` function, because we want all the parts to move *together*, not one eye all the way across the screen and then have the other eye catch up! A variation on `moveOnLine` is needed where all the parts move together. We need all the parts of the face to move one step, then sleep *once*, and all move again, sleep *once*, This could all be coded in a single method, but there are really two ideas here:

1. Moving a group of objects one step.
2. Animating a number of moves for the group.

This suggests two functions. Another issue is how to handle a group of elementary graphics objects. The most basic combination of objects in Python is a `list`, so we assume a parameter `shapeList`, which is a `list` of elementary graphics objects. For the first function, `moveAll`, just move all the objects in the `list` one step. Since we assume a `list` of objects and we want to move *each*, this suggests a `for`-each loop:

```
def moveAll(shapeList, dx, dy):
    ''' Move all shapes in shapeList by (dx, dy).'''
    for shape in shapeList:
        shape.move(dx, dy)
```

Having this function, we can easily write the second function `moveAllOnLine`, with a simple change from the `moveOnLine` function, substituting the `moveAll` function for the line with the `move` method:

```
def moveAllOnLine(shapeList, dx, dy, repetitions, delay):
    '''Animate the shapes in shapeList along a line.
    Move by (dx, dy) each time.
    Repeat the specified number of repetitions.
    Have the specified delay (in seconds) after each repeat.
    '''
    for i in range(repetitions):
        moveAll(shapeList, dx, dy)
        time.sleep(delay)
```

The code in `main` to construct the face is the same as in the earlier example `face.py`. Once all the pieces are constructed and colored, they must be placed in a `list`, for use in `moveAllOnLine`:

```
faceList = [head, eye1, eye2, mouth]
```

Then, later, the animation uses the `faceList` to make the face go back and forth:

```
moveAllOnLine(faceList, 5, 0, 46, .05)
moveAllOnLine(faceList, -5, 0, 46, .05)
```

This version of the program has encapsulated and generalized the moving and animating by creating functions and adding parameters that can be substituted. Again, make sure you see how the functions communicate to make the whole program work. This is an important and non-trivial use of functions.

In fact all parts of the face do *not* actually move at once: The `moveAll` loop code moves each part of the face separately, in sequence. Depending on your computer setup, all the parts of the face may *appear* to move together. Again, the computer is much faster than our eyes. On a computer that repaints the screen fast enough, the only images we notice are the *ones on the screen when the animation is sleeping*.

Note: On a fast enough computer you can make many consecutive changes to an image before the next sleep statement, and they all *appear* to happen at once in the animation.

Optional refinement: Not all computers are set up for the same graphics speed in Python. One machine that I use animates `backAndForth2.py` quite well. Another seems to have the mouth wiggle. On the latter sort of machine, during animation it is useful not to have visible screen changes for every individual move. Instead you can explicitly tell the computer when it is the right time to redraw the screen. The computer can store changes and then *update* the screen. Withholding updates is controlled by `win.autoflush`. It starts as `True`, but can be changed to `False` before animation. When set to `False`, you must call `update()` every time you want the screen refreshed. That is going to be just before the `time.sleep()` in an animation. In `backAndForth2Update.py` this is illustrated, with `moveAllOnLine` replaced by `moveAllOnLineUpdate`:

```

                                #NEW update version, added win param
def moveAllOnLineUpdate(shapeList, dx, dy, repetitions, delay, win):
    '''Animate the shapes in shapeList along a line in win.
    Move by (dx, dy) each time.
    Repeat the specified number of repetitions.
    Have the specified delay (in seconds) after each repeat.
    '''
    win.autoflush = False          # NEW: set before animation
    for i in range(repetitions):
        moveAll(shapeList, dx, dy)
        update()                  # NEW needed to make all the changes appear
        time.sleep(delay)
    win.autoflush = True          # NEW: set after animation

```

Run the next example program `backAndForth3.py`.

The final version, `backAndForth3.py` and its variant, `backAndForth3Update.py`, use the observation that the code to make a face embodies one unified idea, suggesting encapsulation inside a function. Once you have encapsulated the code to make a face, we can make several faces! Then the problem with the original code for the face is that all the positions for the facial elements are hard-coded: The face can only be drawn in one position. The full listing of `backAndForth3.py` below includes a `makeFace` function with a parameter for the position of the center of the face.

Beneath the listing of the whole program is a discussion of the individual changes:

```

'''Test animation of a group of objects making a face.
Combine the face elements in a function, and use it twice.
Have an extra level of repetition in the animation.

This version may be wobbly and slow on some machines:
Then see backAndForthFlush.py.
'''

from graphics import *
import time

def moveAll(shapeList, dx, dy):
    ''' Move all shapes in shapeList by (dx, dy).'''
    for shape in shapeList:
        shape.move(dx, dy)

def moveAllOnLine(shapeList, dx, dy, repetitions, delay):
    '''Animate the shapes in shapeList along a line.

```

```
Move by (dx, dy) each time.
Repeat the specified number of repetitions.
Have the specified delay (in seconds) after each repeat.
'''
for i in range(repetitions):
    moveAll(shapeList, dx, dy)
    time.sleep(delay)

def makeFace(center, win):
    '''display face centered at center in window win.
    Return a list of the shapes in the face.
    '''

    head = Circle(center, 25)
    head.setFill("yellow")
    head.draw(win)

    eye1Center = center.clone() # face positions are relative to the center
    eye1Center.move(-10, 5)     # locate further points in relation to others
    eye1 = Circle(eye1Center, 5)
    eye1.setFill('blue')
    eye1.draw(win)

    eye2End1 = eye1Center.clone()
    eye2End1.move(15, 0)
    eye2End2 = eye2End1.clone()
    eye2End2.move(10, 0)

    eye2 = Line(eye2End1, eye2End2)
    eye2.setWidth(3)
    eye2.draw(win)

    mouthCorner1 = center.clone()
    mouthCorner1.move(-10, -10)
    mouthCorner2 = mouthCorner1.clone()
    mouthCorner2.move(20, -5)

    mouth = Oval(mouthCorner1, mouthCorner2)
    mouth.setFill("red")
    mouth.draw(win)

    return [head, eye1, eye2, mouth]

def main():
    win = GraphWin('Back and Forth', 300, 300)
    win.yUp() # make right side up coordinates!

    rect = Rectangle(Point(200, 90), Point(220, 100))
    rect.setFill("blue")
    rect.draw(win)

    faceList = makeFace(Point(40, 100), win)
    faceList2 = makeFace(Point(150, 125), win)

    stepsAcross = 46
    dx = 5
    dy = 3
```

```

wait = .05
for i in range(3):
    moveAllOnLine(faceList, dx, 0, stepsAcross, wait)
    moveAllOnLine(faceList, -dx, dy, stepsAcross//2, wait)
    moveAllOnLine(faceList, -dx, -dy, stepsAcross//2, wait)

win.promptClose(win.getWidth()/2, 20)

main()

```

Read the following discussion of program parts.

As mentioned above, the face construction function allows a parameter to specify where the center of the face is. The other parameter is the GraphWin that will contain the face.

```
def makeFace(center, win):
```

then the head is easily drawn, using this center, rather than the previous `circ1` with its specific center point (40, 100):

```

head = Circle(center, 25)
head.setFill('yellow')
head.draw(win)

```

For the remaining Points used in the construction there is the issue of keeping the right relation to the center. This is accomplished much as in the creation of the second corner point in the `makeRectangle` function in Section *Issues with Mutable Objects* (page 97). A clone of the original center Point is made, and then moved by the *difference* in the positions of the originally specified Points. For instance, in the original face, the center of the head and first eye were at (40, 110) and (30, 115) respectively. That means a shift between the two coordinates of (-10, 5), since $30-40 = -10$ and $130-110 = 20$.

```

eyelCenter = center.clone() # face positions are relative to the center
eyelCenter.move(-10, 5)     # locate further points in relation to others
eyel = Circle(eyelCenter, 5)
eyel.setFill('blue')
eyel.draw(win)

```

The only other changes to the face are similar, cloning and moving Points, rather than specifying them with explicit coordinates.

```

eye2End1 = eyelCenter.clone()
eye2End1.move(15, 0)
eye2End2 = eye2End1.clone()
eye2End2.move(10, 0)
eye2 = Line(eye2End1, eye2End2)
eye2.setWidth(3)
eye2.draw(win)

mouthCorner1 = center.clone()
mouthCorner1.move(-10, -10)
mouthCorner2 = mouthCorner1.clone()
mouthCorner2.move(20, -5)
mouth = Oval(mouthCorner1, mouthCorner2)
mouth.setFill('red')
mouth.draw(win)

```

Finally, the list of elements for the face must be returned to the caller:

```
return [head, eye1, eye2, mouth]
```

Then in the main function, the program creates a face in exactly the same place as before, but using the `makeFace` function, with the original center of the face `Point(40, 100)` as parameter. Now with the `makeFace` function, with its center parameter, it is also easy to replace the old `cir2` with a whole face!

```
faceList = makeFace(Point(40, 100), win)
faceList2 = makeFace(Point(150,125), win)
```

The animation section is considerably elaborated in this version.

```
stepsAcross = 46
dx = 5
dy = 3
wait = .01
for i in range(3):
    moveAllOnLine(faceList, dx, 0, stepsAcross, wait)
    moveAllOnLine(faceList, -dx, dy, stepsAcross//2, wait)
    moveAllOnLine(faceList, -dx, -dy, stepsAcross//2, wait)
```

The unidentified numeric literals that were used before are replaced by named values that easily identify the meaning of each one. This also allows the numerical values to be stated only once, allowing easy modification.

The whole animation is repeated three times by the use of a simple repeat loop. Since `moveAllOnLine` has a for-loop inside it, it illustrates nesting of loops.

The animations in the loop body illustrate that the straight line of motion does not need to be horizontal. The second and third lines use a non-zero value of both `dx` and `dy` for the steps, and move diagonally.

Make sure you see now how the whole program works together, including all the parameters for the moves in the loop.

By the way, the documentation of the functions in a module you have just run in the Shell is directly available. Try in the *Shell*:

```
help(moveAll)
```

Nose in Face Exercise

* Save `backAndForth3.py` or `backAndForth3Update.py` to the new name `backAndForth4.py`. Add a triangular nose in the middle of the face in the `makeFace` function. Like the other features of the face, make sure the position of the nose is *relative* to the `center` parameter. Make sure the nose is included in the final list of elements of the face that get returned!

Faces Exercise

* Make a program `faces.py` that asks the user to click the mouse, and then draws a face at the point where the user clicked. Copy the `makeFace` function definition *from the previous exercise*, and use it! Elaborate this with a [Simple Repeat Loop](#) (page 52), so this is repeated six times: After each of 6 mouse clicks, a face immediately appears at the location of the latest click. Think how you can reuse your code each time through the loop!

Moving Faces Exercise

* Animate two faces moving in different directions *at the same time* in a program `move2Faces.py`. You *cannot* use the `moveAllOnLine` function. You will have to make a variation of your own. You *can* use the `moveAll` function separately for each face.

Hint: imagine the old way of making an animated cartoon. If each face was on a separate piece of paper, and you wanted to animate them moving together, you would place them separately, record one frame, move them each a bit toward each other, record another frame, move each another bit toward each other, record another frame, In our animations “record a frame” is replaced by a short sleep to make the position visible to the user. Make a loop to incorporate the repetition of the moves.

2.4.9 Entry Objects

(Optional section) Read this section if you want to allow the user to enter text directly into a graphics window.

When using a graphics window, the shell window is still available. Keyboard input can be done in the normal text fashion, waiting for a response, and going on after the user presses the Enter key. It is annoying to make a user pay attention to two windows, so the graphics module provides a way to enter text inside a graphics window, with the `Entry` type. The entry is a *partial* replacement for the `input` function.

Run the simple example, `greet.py`, which is copied below:

```
"""Simple example with Entry objects.
Enter your name, click the mouse, and see greetings.
"""

from graphics import *

def main():
    win = GraphWin("Greeting", 300, 300)
    win.yUp()

    instructions = Text(Point(win.getWidth()/2, 40),
                          "Enter your name.\nThen click the mouse.")
    instructions.draw(win)

    entry1 = Entry(Point(win.getWidth()/2, 200), 10)
    entry1.draw(win)

    Text(Point(win.getWidth()/2, 230), 'Name:').draw(win) # label for the Entry

    win.getMouse() # To know the user is finished with the text.

    name = entry1.getText()

    greeting1 = 'Hello, ' + name + '!'
    Text(Point(win.getWidth()/3, 150), greeting1).draw(win)

    greeting2 = 'Bonjour, ' + name + '!'
    Text(Point(2*win.getWidth()/3, 100), greeting2).draw(win)

    win.promptClose(instructions)

main()
```

The only part of this with new ideas is:

```
entry1 = Entry(Point(win.getWidth()/2, 200), 10)
entry1.draw(win)
Text(Point(win.getWidth()/2, 230), 'Name:').draw(win) # label for the Entry

win.getMouse() # To know the user is finished with the text.
name = entry1.getText()
```

The first line of this excerpt creates an Entry object, supplying its center point and a number of characters to leave space for (10 in this case).

As with other places where input is requested, a separate static label is added.

The way the underlying events are hidden in graphics.py, there is no signal when the user is done entering text in an Entry box. To signal the program, a mouse press is used above. In this case the location of the mouse press is not relevant, but once the mouse press is processed, execution can go on and read the Entry text. The method name `getText` is the same as that used with a Text object.

Run the next example, `addEntries.py`, also copied below:

```
"""Example with two Entry objects and type conversion.
Do addition.
"""

from graphics import *

def main():
    win = GraphWin("Addition", 300, 300)
    win.yUp()

    instructions = Text(Point(win.getWidth()/2, 30),
                          "Enter two numbers.\nThen click the mouse.")
    instructions.draw(win)

    entry1 = Entry(Point(win.getWidth()/2, 250), 25)
    entry1.setText('0')
    entry1.draw(win)

    Text(Point(win.getWidth()/2, 280), 'First Number:').draw(win)

    entry2 = Entry(Point(win.getWidth()/2, 180), 25)
    entry2.setText('0')
    entry2.draw(win)

    Text(Point(win.getWidth()/2, 210), 'Second Number:').draw(win)

    win.getMouse() # To know the user is finished with the text.

    numStr1 = entry1.getText()
    num1 = int(numStr1)

    numStr2 = entry2.getText()
    num2 = int(numStr2)
    sum = num1 + num2

    result = "The sum of\n{num1}\nplus\n{num2}\nis {sum}.".format(**locals())
    Text(Point(win.getWidth()/2, 110), result).draw(win)

    win.promptClose(instructions)

main()
```

As with the `input` statement, you can only read *strings* from an Entry. With conversions, it is still possible to work with numbers.

Only one new graphical method has been included above:

```
entry1.setText('0')
```

Again the same method name is used as with a `Text` object. In this case I chose not to leave the `Entry` initially blank. The 0 value also reinforces that a numerical value is expected.

There is also an `entry2` with almost identical code. After waiting for a mouse click, both entries are read, and the chosen names emphasizes they are strings. The strings must be converted to integers in order to do arithmetic and display the result.

The almost identical code for the two entries is a strong suggestion that this code could be written more easily with a function. You may look at the identically functioning example program `addEntries2.py`. The only changes are shown below. First there is a function to create an `Entry` and a centered static label over it.

```
def makeLabeledEntry(entryCenterPt, entryWidth, initialStr, labelText, win):
    '''Return an Entry object with specified center, width in characters, and
    initial string value. Also create a static label over it with
    specified text. Draw everything in the GraphWin win.
    '''

    entry = Entry(entryCenterPt, entryWidth)
    entry.setText(initialStr)
    entry.draw(win)
    labelCenter = entryCenterPt.clone()
    labelCenter.move(0, 30)
    Text(labelCenter, labelText).draw(win)
    return entry
```

In case I want to make more `Entries` with labels later, and refer to this code again, I put some extra effort in, making things be parameters even if only one value is used in this program. The position of the label is made 30 units above the entry by using the `clone` and `move` methods. Only the `Entry` is returned, on the assumption that the label is static, and once it is drawn, I can forget about it. Since I do not refer later to the `Text` object, I do not bother to name it, but just draw it immediately.

Then the corresponding change in the main function is just two calls to this function:

```
entry1 = makeLabeledEntry(Point(win.getWidth()/2, 250), 25,
                           '0', 'First Number:', win)
entry2 = makeLabeledEntry(Point(win.getWidth()/2, 180), 25,
                           '0', 'Second Number:', win)
```

These lines illustrate that a statement may take more than one line. In particular, as in the Shell, Python is smart enough to realize that there must be a continuation line if the parentheses do not match.

While I was improving things, I also changed the conversions to integers. In the first version I wanted to emphasize the existence of both the string and integer data as a teaching point, but the `num1Str` and `num2Str` variables were only used once, so a more concise way to read and convert the values is to eliminate them:

```
num1 = int(entry1.getText())
num2 = int(entry2.getText())
```

2.4.10 Color Names

Thus far we have only used common color names. In fact there are a very large number of allowed color names, and also the ability to draw with custom colors.

First, the graphics package is built on an underlying graphics system, Tkinter, which has a large number of color names defined. Each of the names can be used by itself, like 'red', 'salmon' or 'aquamarine' or with a lower intensity by specifying with a trailing number 2, 3, or 4, like 'red4' for a dark red.

Though the ideas for the coding have not all been introduced, it is still informative to *run* the example program `colors.py`. As you click the mouse over and over, you see the names and appearances of a wide variety of built-in color names. The names must be placed in quotes, but capitalization is ignored.

2.4.11 Custom Colors

Custom colors can also be created. To do that requires some understanding of human eyes and color (and the Python tools). The only colors detected directly by the human eyes are red, green, and blue. Each amount is registered by a different kind of cone cell in the retina. As far as the eye is concerned, all the other colors we see are just combinations of these three colors. This fact is used in color video screens: they only directly display these three colors. A common scale to use in labeling the intensity of each of the basic colors (red, green, blue) is from 0 to 255, with 0 meaning none of the color, and 255 being the most intense. Hence a color can be described by a sequence of red, green, and blue intensities (often abbreviated RGB). The graphics package has a function, `color_rgb`, to create colors this way. For instance a color with about half the maximum red intensity, no green, and maximum blue intensity would be

```
aColor = color_rgb(128, 0, 255)
```

Such a creation can be used any place a color is used in the graphics, (i.e. `circle.setFill(aColor)`).

2.4.12 Random Colors

Another interesting use of the `color_rgb` function is to create random colors. Run example program `randomCircles.py`. The code also is here:

```
"""Draw random circles.
"""
from graphics import *
import random, time

def main():
    win = GraphWin("Random Circles", 300, 300)
    for i in range(75):
        r = random.randrange(256)
        b = random.randrange(256)
        g = random.randrange(256)
        color = color_rgb(r, g, b)

        radius = random.randrange(3, 40)
        x = random.randrange(5, 295)
        y = random.randrange(5, 295)

        circle = Circle(Point(x,y), radius)
        circle.setFill(color)
        circle.draw(win)
        time.sleep(.05)

    win.promptClose(win.getWidth()/2, 20)

main()
```

Read the fragments of this program and their explanations:

To do random things, the program needs a function from the random module. This example shows that imported modules may be put in a comma separated list:

```
import random, time
```

You have already seen the built-in function `range`. To generate a sequence of all the integers 0, 1, ... 255, you would use

```
range(256)
```

This is the full list of possible values for the red, green or blue intensity parameter. For this program we randomly choose any *one* element from this sequence. Instead of the `range` function, use the `random` module's `randrange` function, as in

```
r = random.randrange(256)
b = random.randrange(256)
g = random.randrange(256)
color = color_rgb(r, g, b)
```

This gives randomly selected values to each of `r`, `g`, and `b`, which are then used to create the random `color`.

I want a random circle radius, but I do not want a number as small as 0, making it invisible. The `range` and `randrange` functions both refer to a possible sequence of values starting with 0 when a *single* parameter is used. It is also possible to add a different starting value as the *first* parameter. You still must specify a value *past* the end of the sequence. For instance

```
range(3, 40)
```

would refer to the sequence 3, 4, 5, ... , 39 (starting with 3 and not quite reaching 40). Similarly

```
random.randrange(3, 40)
```

randomly selects an arbitrary element of `range(3, 40)`.

I use the two-parameter version to select random parameters for a Circle:

```
radius = random.randrange(3, 40)
x = random.randrange(5, 295)
y = random.randrange(5, 295)

circle = Circle(Point(x,y), radius)
```

What are the smallest and largest values I allow for `x` and `y`? ⁶

Random values are often useful in games.

Ranges Exercise

Write a program `ranges.py` in three parts. (Test after each added part.)

This problem is *not a graphics program*. It is just a regular text program to illustrate your understanding of ranges and loops.

For simplicity each of the requested number sequences can just be printed with one number per line. Print a label for each number sequence before you print the sequence, like Numbers 1-4, Numbers 1-n, Five random numbers in 1-n.

1. First *use the range function* and a for-loop to produce the sequence 1, 2, 3, 4, and then print the numbers, one number per line.
2. Prompt the user to input an integer `n` and print the sequence 1, 2, 3, ... , `n` - *including* `n`, using a for-loop. Hint: ⁷

⁶ 5 and 294 (one less than 295).

⁷ If 4 or `n` is the last number, what is the first number *past* the end of the sequence?

3. Use a [Simple Repeat Loop](#) (page 52) to find and print five randomly chosen numbers from the range 1, 2, 3, ... , n. Use the same value of n that the user chose earlier in the program. It should be possible that the number n is printed sometimes.

Text Triangle Exercise

* Write a program `texttriangle.py`.

This, too, is *not a graphics program*. Prompt the user for a small positive integer value, that I'll call n. Then use a *for-loop with a range function call* to make a triangular arrangement of '#' characters, with n '#' characters in the last line. Hint: ⁸

Then leave a blank line. Then make a similar triangle, except *start* with the line with n '#' characters. To make the second triangle, you can use a for-loop of the form discussed so far, but that is trickier than looking ahead to [The Most General range Function](#) (page 145) and using a for-loop where a range function call has a *negative* step size.

Here is the screen after a possible run with user input 4:

```
Enter a small positive integer: 4
#
##
###
####

####
###
##
#
```

And another possible run with user input 2:

```
Enter a small positive integer: 2
#
##

##
#
```

2.5 Files

This section fits here logically (as an important built-in type of object) but it is not needed for the next chapter, [More On Flow of Control](#) (page 121).

Thus far you have been able to save programs, but anything produced during the execution of a program has been lost when the program ends. Data has not *persisted* past the end of execution. Just as programs live on in files, you can generate and read data files in Python that persist after your program has finished running.

As far as Python is concerned, a file is just a string (often very large!) stored on your file system, that you can read or write, gradually or all together.

Directory is an old name for a folder. These ideas go back far enough to the time before directories got a graphical folder representation. For this section we use the word directory to mean the same thing as folder.

⁸ A row of '#' characters is easiest if you remember the string multiplication operator *.

2.5.1 Writing Files

Open a directory window for your Python program directory. First note that there is no file named `sample.txt`.

Make sure you have started Idle so the current directory is your Python program directory.

Run the example program `firstFile.py`, shown below:

```
outFile = open('sample.txt', 'w')
outFile.write('My first output file!')
outFile.close()
```

The first line creates a file object, which links Python to your computer's file system. The first parameter in the file constructor gives the file name, `sample.txt`. The second parameter indicates how you use the file. The `'w'` is short for **w**rite, so you will be creating and *w*riting to a file.

Warning: If the file already existed, the old contents are *destroyed*.

If you do not use any operating system directory separators in the name (`'\'` or `'/'` depending on your operating system), then the file will lie in the current directory. The assignment statement gives the Python file object the name `outFile`.

The second line writes the specified string to the file.

The last line is important to clean up. Until this line, this Python program controls the file, and nothing may be actually written to an operating system file yet: Since initiating a file operation is thousands of times slower than memory operations, Python *buffers* data, saving small amounts and writing a larger chunk all at once.

Warning: The `close` line is essential for Python to make sure everything is really written, and to relinquish control of the file.

It is a common bug to write a program where you have the code to add all the data you want to a file, but the program does not end up creating a file. Usually this means you forgot to close the file.

Now switch focus and look at a directory window for the current directory. You should now see a file `sample.txt`. You can open it in Idle (or your favorite word processor) and see its contents.

For the next example, run the example program `nextFile.py`, shown below, which has two calls to the write method:

```
outFile = open('sample2.txt', 'w')
outFile.write('My second output file!')
outFile.write('Write some more.')
outFile.close()
```

Now look at the file, `sample2.txt`. Open it in Idle. It may not be what you expect! The write method for the file is not quite like a `print` function. It does not add anything to the file except *exactly* the data you tell it to write. If you want a newline, you must indicate it *explicitly*. Recall the newline code `'\n'`. Run the example program `revisedFile.py`, shown below, which adds newline codes:

```
outFile = open('sample3.txt', 'w')
outFile.write('A revised output file!\n')
outFile.write('Write some more.\n')
outFile.close()
```

Check the contents of `sample3.txt`.

2.5.2 Reading Files

Run the example program `printFile.py`, shown below:

```
'''Quick illustration of reading a file.
(needs revisedFile.py run first to create sample3.txt)
'''

inFile = open('sample3.txt', 'r')
contents = inFile.read()
print(contents)
```

Now you have come full circle: what one Python program has written into the file `sample3.txt`, another has read and displayed.

In the first line of the program an operating system file (`sample3.txt`) is associated again with a Python variable name (`inFile`). The second parameter again gives the mode of operation, but this time it is `'r'`, short for read. This file, `sample3.txt`, should already exist, and the intention is to read from it. This is the most common mode for a file, so the `'r'` parameter is actually *optional*.

The `read` method returns all the file's data as a single string, here assigned to the variable `contents`. Using the `close` method is generally optional with files being read. There is nothing to lose if a program ends without closing a file that was being read.⁹

Note: There are three related but distinct concepts related to files. Beginners often get confused and try to merge several in their head or substitute one for another:

1. The *file name* is a string that identifies the file in your computer's file system.
2. You need the file name to `open` a file creating a *file* object, but the file object (that I tend to call `inFile` or `outFile`) is not the same as the name of the file on your hard drive. You assign it to a variable name just for use inside your program.
3. There is still one more step to the most important part, the *contents* of the file. The `read` method for a file object reads and *returns* existing content, while the `write` method writes new content into the file.

There are other methods to read just parts of files (that you can look up in the Python documentation), but for this tutorial, reading the whole file with the `read` method is sufficient.

PrintUpper Exercise

Make the following programs in sequence. Be sure to save the programs in the same directory as where you start the idle shortcut and where you have all the sample text files:

1. `printUpper.py`: read the contents of the `sample2.txt` file and print the contents out in upper case. (This should use file operations and should work no matter what the contents are in `sample2.txt`. Do not assume the particular string written by `nextFile.py`!)
2. `fileUpper.py`: *prompt* the user for a file name, read and print the contents of the requested file in upper case.
3. `*copyFileUpper.py`: modify `fileUpper.py` to write the upper case contents string to a new file rather than printing it. Have the name of the new file be dynamically derived from the old name by prepending `'UPPER'` to the name. For example, if the user specified the file `sample.txt` (from above), the program would create a file `UPPERsample.txt`, containing `'MY FIRST OUTPUT FILE!'`. When the user specifies the file name `stuff.txt`, the resulting file would be named `UPPERstuff.txt`.

⁹ If, for some reason, you want to reread this same file while the same program is running, you need to close it and reopen it.

Mad Lib File Exercise

Write `madlib3.py`, a small modification of `madlib2.py`, requiring only a modification to the `main` function of `madlib2.py`. (Even better is to start from `madlib2a.py` if you did the exercise in *Unique List Exercise* (page 132)). Also create a file `myMadlib.txt`, as described below.

Your `madlib3.py` should

- *Prompt* the user for the name of a file that should contain a madlib format string as text (with no quotes around it).
- Read in this file and use it as the format string in the `tellStory` function.

This is unlike in `madlib2.py`, where the story is a *literal* string coded directly into the program, assigned to the variable `originalStory`. The `tellstory` function and particularly the `getKeys` function were developed and described in detail in this tutorial, but for this exercise there is no need to follow their inner workings - you are just a *user* of the `tellstory` function (and the functions that it calls). You do not need to mess with the code for the definition of `tellStory` or any of the earlier supporting functions - just keep them from the copy you made of `madlib2.py` for your `madlib3.py`. The original madlib string is already placed in a file `jungle.txt` as an example of the story file format expected. With the Idle editor, write another madlib format string into a file `myMadlib.txt`. If you earlier created a program `myMadlib.py`, then you can easily extract the story from there (without the quotes around it). Test your program `madlib3.py` twice, using `jungle.txt` and then your new madlib story file `myMadlib.txt`.

2.6 Summary

The same typographical conventions will be used as in the Chapter 1 *Summary* (page 64).

1. Object notation

- (a) When the name of a type of object is used as a function call, it is called a *constructor*, and a new object of that type is constructed and implicitly returned (no return statement). The meanings of any parameters to the constructor depend on the type. [*Constructors* (page 82)]

- (b) `object.methodName (parameters)`

Objects have special operations associated with them, called methods. They are functions automatically applied to the *object* before the dot. Further parameters may be expected, depending on the particular method. [*Object Orientation* (page 73)]

2. String (`str`) indexing and methods

See the Chapter 1 *Summary* (page 64) for string literals and symbolic string operations.

- (a) String Indexing. [*String Indices* (page 75)]

`stringReference [intExpression]`

Individual characters in a string may be chosen. If the string has length `L`, then the indices start from 0 for the initial character and go to `L-1` for the rightmost character. Negative indices may also be used to count from the right end, `-1` for the rightmost character through `-L` for the leftmost character. Strings are immutable, so individual characters may be read, but not set.

- (b) String Slices [*String Slices* (page 76)]

`stringReference [start : pastEnd]`

`stringReference [: pastEnd]`

`stringReference [start :]`

`stringReference [:]`

A substring or *slice* of 0 or more consecutive characters of a string may be referred to by specifying a starting index and the index one *past* the last character of the substring. If the starting or ending index is left out Python uses 0 and the length of the string respectively. Python assumes indices that would be beyond an end of the string actually mean the end of the string.

(c) String Methods: Assume *s* refers to a string

i. `s.upper()`

Returns an uppercase version of the string *s*. [[Object Orientation](#) (page 73)]

ii. `s.lower()`

Returns a lowercase version of the string *s*. [[Object Orientation](#) (page 73)]

iii. `s.count(sub)`

Returns the number of repetitions of the substring *sub* inside *s*. [[Object Orientation](#) (page 73)]

iv. `s.find(sub)`

`s.find(sub, start)`

`s.find(sub, start, end)`

Returns the index in *s* of the first character of the first occurrence of the substring *sub* within the part of the string *s* indicated, respectively the whole string *s*, or *s[start :]*, or *s[start : end]*, where *start* and *end* have integer values. [[Object Orientation](#) (page 73)]

v. `s.split()`

`s.split(sep)`

The first version splits *s* at any sequence of whitespace (blanks, newlines, tabs) and returns the remaining parts of *s* as a list. If a string *sep* is specified, it is the separator that gets removed from between the parts of the list. [[split](#) (page 78)]

vi. `sep.join(sequence)`

Return a new string obtained by joining together the *sequence* of strings into one string, interleaving the string *sep* between *sequence* elements. [[join](#) (page 78)]

vii. Further string methods are discussed in the Python Reference Manual, in the section on built-in types. [[Further Exploration](#) (page 80)]

3. Sets

A set is a collection of elements with no repetitions. It can be used as a sequence in a `for` loop. A set constructor can take any other sequence as a parameter, and convert the sequence to a set (with no repetitions). Nonempty set literals are enclosed in braces. [[Sets](#) (page 81)]

4. List method `append`

`aList.append(element)`

Add an arbitrary *element* to the end of the list *aList*, *mutating* the list, not returning any list. [[Appending to a List](#) (page 80)]

5. Files [[Files](#) (page 114)]

(a) `open(nameInFileSystem)`

`open(nameInFileSystem, 'r')`

returns a file object for reading, where *nameInFileSystem* must be a string referring to an existing file.

(b) `open(nameInFileSystem, 'w')`

returns a file object for writing, where the string *nameInFileSystem* will be the name of the file. If it did not exist before, it is created. If it *did* exist before, all previous contents are **erased**.

- (c) If *infile* is a file opened for reading, and *outfile* is a file opened for writing, then

```
infile.read()
```

returns the entire file contents of the file as a string.

```
infile.close()
```

closes the file in the operating system (generally not needed, unless the file is going to be modified later, while your program is *still* running).

```
outfile.write( stringExpression )
```

writes the string to the file, with no extra newline.

```
outfile.close()
```

closes the file in the operating system (*important* to make sure the whole file gets written and to allow other access to the file).

6. Mutable objects [*Issues with Mutable Objects* (page 97)] Care must be taken whenever a second name is assigned to a mutable object. It is an *alias* for the original name, and refers to the exact same object. A mutating method applied to either name changes the one object referred to by *both* names. Many types of mutable object have ways to make a copy that is a distinct object. Zelle's graphical objects have the `clone` method. A copy of a list may be made with a full slice: *someList*[:]. Then direct mutations to one list (like appending an element) do not affect the other list, but still, each list is indirectly changed if a common mutable element in the lists is changed.

7. Graphics

A systematic reference to Zelle's graphics package, `graphics.py`, is at <http://mcspr.wartburg.edu/zelle/python/graphics/graphics/index.html>.

- (a) Introductory examples of using `graphics.py` are in [*A Graphics Introduction* (page 88)], [*Sample Graphics Programs* (page 90)], and [*Entry Objects* (page 109)]

- (b) Windows operating system `.pyw`

In windows, a graphical program that take no console input and generates no console output, may be given the extension `.pyw` to suppress the generation of a console window. [*A Windows Operating System Specialization: .pyw* (page 95)]

- (c) Event-driven programs

Graphical programs are typically event-driven, meaning the next operation done by the program can be in response to a large number of possible operations, from the keyboard or mouse for instance, without the program knowing which kind of event will come next. For simplicity, this approach is pretty well hidden under Zelle's graphics package, allowing the illusion of simpler sequential programming. [*Graphics.py vs. Event Driven Graphics* (page 95)]

- (d) Custom computer colors are expressed in terms of the amounts of red, green, and blue. [*Custom Colors* (page 112)]

- (e) See also Animation under the summary of Programming Techniques.

8. Additional programming techniques

These techniques extend those listed in the *Summary* (page 64) of the previous chapter.

- (a) Sophisticated operations with substrings require careful setting of variables used as an index. [*Index Variables* (page 78)]

- (b) There are a number of techniques to assist creative programming, including pseudo-code and gradual generalization from concrete examples. [*Creative Problem Solving Steps* (page 85)]
- (c) Animation: a loop involving small moves followed by a short delay (assumes the time module is imported): [*Animation* (page 100)]
 - loop heading :
 - move all objects a small step in the proper direction
 - time.sleep(delay)
- (d) Example of a practical successive modification loop: [*A Function to Ease the Creation of Mad Libs* (page 82)]
- (e) Examples of encapsulating ideas in functions and reusing them: [*A Function to Ease the Creation of Mad Libs* (page 82)], [*The Revised Mad Lib Program* (page 86)], [*Animation* (page 100)]
- (f) Random results can be introduced into a program using the random module. [*Random Colors* (page 112)]

MORE ON FLOW OF CONTROL

You have varied the normal forward sequence of operations with functions and `for` loops. To have full power over your programs, you need two more constructions that changing the flow of control: decisions choosing between alternatives (`if` statements), and more general loops that are not required to be controlled by the elements of a collection (`while` loops).

3.1 If Statements

3.1.1 Simple Conditions

The statements introduced in this chapter will involve tests or *conditions*. More syntax for conditions will be introduced later, but for now consider simple arithmetic comparisons that directly translate from math into Python. Try each line separately in the *Shell*

```
2 < 5
3 > 7
x = 11
x > 10
2 * x < x
type(True)
```

You see that conditions are either `True` or `False`. These are the only possible *Boolean* values (named after 19th century mathematician George Boole). In Python the name Boolean is shortened to the type `bool`. It is the type of the results of true-false conditions or tests.

Note: The Boolean values `True` and `False` have no quotes around them! Just as `'123'` is a string and `123` without the quotes is not, `'True'` is a string, not of type `bool`.

3.1.2 Simple `if` Statements

Run this example program, `suitcase.py`. Try it at least twice, with inputs: 30 and then 55. As you can see, you get an extra result, depending on the input. The main code is:

```
weight = float(input("How many pounds does your suitcase weigh? "))
if weight > 50:
    print("There is a $25 charge for luggage that heavy.")
print("Thank you for your business.")
```

The middle two lines are an `if` statement. It reads pretty much like English. If it is true that the weight is greater than 50, then print the statement about an extra charge. If it is not true that the weight is greater than 50, then don't do

the indented part: skip printing the extra luggage charge. In any event, when you have finished with the `if` statement (whether it actually does anything or not), go on to the next statement that is *not* indented under the `if`. In this case that is the statement printing “Thank you”.

The general Python syntax for a simple `if` statement is

```
if condition :  
    indentedStatementBlock
```

If the condition is true, then do the indented statements. If the condition is not true, then skip the indented statements.

Another fragment as an example:

```
if balance < 0:  
    transfer = -balance  
    # transfer enough from the backup account:  
    backupAccount = backupAccount - transfer  
    balance = balance + transfer
```

As with other kinds of statements with a heading and an indented block, the block can have more than one statement. The assumption in the example above is that if an account goes negative, it is brought back to 0 by transferring money from a backup account in several steps.

In the examples above the choice is between doing something (if the condition is `True`) or nothing (if the condition is `False`). Often there is a choice of two possibilities, only one of which will be done, depending on the truth of a condition.

3.1.3 `if-else` Statements

Run the example program, `clothes.py`. Try it at least twice, with inputs 50 and then 80. As you can see, you get different results, depending on the input. The main code of `clothes.py` is:

```
temperature = float(input('What is the temperature? '))  
if temperature > 70:  
    print('Wear shorts.')  
else:  
    print('Wear long pants.')  
print('Get some exercise outside.')
```

The middle four lines are an `if-else` statement. Again it is close to English, though you might say “otherwise” instead of “else” (but else is shorter!). There are two indented blocks: One, like in the simple `if` statement, comes right after the `if` heading and is executed when the condition in the `if` heading is true. In the `if-else` form this is followed by an `else:` line, followed by another indented block that is only executed when the original condition is *false*. In an `if-else` statement exactly one of two possible indented blocks is executed.

A line is also shown **dedented** next, removing indentation, about getting exercise. Since it is dedented, it is not a part of the `if-else` statement: Since its amount of indentation matches the `if` heading, it is always executed in the normal forward flow of statements, after the `if-else` statement (whichever block is selected).

The general Python `if-else` syntax is

```
if condition :  
    indentedStatementBlockForTrueCondition  
else:  
    indentedStatementBlockForFalseCondition
```

These statement blocks can have any number of statements, and can include about any kind of statement.

See [Graduate Exercise](#) (page 125)

3.1.4 More Conditional Expressions

All the usual arithmetic comparisons may be made, but many do not use standard mathematical symbolism, mostly for lack of proper keys on a standard keyboard.

Meaning	Math Symbol	Python Symbols
Less than	<	<
Greater than	>	>
Less than or equal	\leq	<=
Greater than or equal	\geq	>=
Equals	=	==
Not equal	\neq	!=

There should not be space between the two-symbol Python substitutes.

Notice that the obvious choice for *equals*, a single equal sign, is *not* used to check for equality. An annoying second equal sign is required. This is because the single equal sign is already used for *assignment* in Python, so it is not available for tests.

Warning: It is a common error to use only one equal sign when you mean to *test* for equality, and not make an assignment!

Tests for equality do not make an assignment, and they do not require a variable on the left. Any expressions can be tested for equality or inequality (!=). They do not need to be numbers! Predict the results and try each line in the *Shell*:

```
x = 5
x
x == 5
x == 6
x
x != 6
x = 6
6 == x
6 != x
'hi' == 'h' + 'i'
'HI' != 'hi'
[1, 2] != [2, 1]
```

An equality check does not make an assignment. Strings are case sensitive. Order matters in a list.

Try in the *Shell*:

```
'a' > 5
```

When the comparison does not make sense, an Exception is caused.¹

Following up on the discussion of the *inexactness* of float arithmetic in *String Formats for Float Precision* (page 63), confirm that Python does not consider `.1 + .2` to be equal to `.3`: Write a simple condition into the *Shell* to test.

Here is another example: Pay with Overtime. Given a person's work hours for the week and regular hourly wage, calculate the total pay for the week, taking into account overtime. Hours worked over 40 are overtime, paid at 1.5 times the normal rate. This is a natural place for a function enclosing the calculation.

Read the setup for the function:

```
def calcWeeklyWages(totalHours, hourlyWage):
    '''Return the total weekly wages for a worker working totalHours,
```

¹ This is an improvement that is new in Python 3.

```
with a given regular hourlyWage. Include overtime for hours over 40.
'''
```

The problem clearly indicates two cases: when no more than 40 hours are worked or when more than 40 hours are worked. In case more than 40 hours are worked, it is convenient to introduce a variable `overtimeHours`. You are encouraged to think about a solution before going on and examining mine.

You can try running my complete example program, `wages.py`, also shown below. The format operation at the end of the main function uses the floating point format (*String Formats for Float Precision* (page 63)) to show two decimal places for the cents in the answer:

```
def calcWeeklyWages(totalHours, hourlyWage):
    '''Return the total weekly wages for a worker working totalHours,
    with a given regular hourlyWage. Include overtime for hours over 40.
    '''
    if totalHours <= 40:
        totalWages = hourlyWage*totalHours
    else:
        overtime = totalHours - 40
        totalWages = hourlyWage*40 + (1.5*hourlyWage)*overtime
    return totalWages

def main():
    hours = float(input('Enter hours worked: '))
    wage = float(input('Enter dollars paid per hour: '))
    total = calcWeeklyWages(hours, wage)
    print('Wages for {hours} hours at ${wage:.2f} per hour are ${total:.2f}.'
          .format(**locals()))

main()
```

Here the input was intended to be numeric, but it could be decimal so the conversion from string was via `float`, not `int`.

Below is an equivalent alternative version of the body of `calcWeeklyWages`, used in `wages1.py`. It uses just one general calculation formula and sets the parameters for the formula in the `if` statement. There are generally a number of ways you might solve the same problem!

```
if totalHours <= 40:
    regularHours = totalHours
    overtime = 0
else:
    overtime = totalHours - 40
    regularHours = 40
return hourlyWage*regularHours + (1.5*hourlyWage)*overtime
```

The `in` boolean operator: There are also Boolean operators that are applied to types others than numbers. A useful Boolean operator is `in`, checking membership in a sequence:

```
>>> vals = ['this', 'is', 'it']
>>> 'is' in vals
True
>>> 'was' in vals
False
```

It can also be used with `not`, as `not in`, to mean the opposite:

```
>>> vals = ['this', 'is', 'it']
>>> 'is' not in vals
False
```



```
>>> 'was' not in vals
True
```

In general the two versions are:

```
item in sequence
item not in sequence
```

Detecting the need for `if` statements: Like with planning programs needing “for” statements, you want to be able to translate English descriptions of problems that would naturally include `if` or `if-else` statements. What are some words or phrases or ideas that suggest the use of these statements? Think of your own and then compare to a few I gave: ²

Graduate Exercise

Write a program, `graduate.py`, that prompts students for how many credits they have. Print whether or not they have enough credits for graduation. (At Loyola University Chicago 120 credits are needed for graduation.)

Head or Tails Exercise

Write a program `headstails.py`. It should include a function `flip()`, that simulates a *single* flip of a coin: It randomly prints either Heads or Tails. Accomplish this by choosing 0 or 1 arbitrarily with `random.randrange(2)`, and use an `if-else` statement to print Heads when the result is 0, and Tails otherwise.

In your main program have a simple repeat loop that calls `flip()` 10 times to test it, so you generate a random sequence of 10 Heads and Tails.

Strange Function Exercise

Save the example program `jumpFuncStub.py` as `jumpFunc.py`, and complete the definitions of functions `jump` and `main` as described in the function documentation strings in the program. In the `jump` function definition use an `if-else` statement (hint ³). In the `main` function definition use a `for-each` loop, the `range` function, and the `jump` function.

The `jump` function is introduced for use in *Strange Sequence Exercise* (page 148), and others after that.

3.1.5 Multiple Tests and `if-elif` Statements

Often you want to distinguish between more than two distinct cases, but conditions only have two possible results, `True` or `False`, so the only direct choice is between two options. As anyone who has played “20 Questions” knows, you can distinguish more cases by further questions. If there are more than two choices, a single test may only reduce the possibilities, but further tests can reduce the possibilities further and further. Since most any kind of statement can be placed in an indented statement block, one choice is a further `if` statement. For instance consider a function to convert a numerical grade to a letter grade, ‘A’, ‘B’, ‘C’, ‘D’ or ‘F’, where the cutoffs for ‘A’, ‘B’, ‘C’, and ‘D’ are 90, 80, 70, and 60 respectively. One way to write the function would be test for one grade at a time, and resolve all the remaining possibilities inside the next `else` clause:

² “In this case do `___`; otherwise”, “if `___`, then”, “when `___` is true, then”, “`___` depends on whether”,

³ If you divide an even number by 2, what is the remainder? Use this idea in your `if` condition.

```
def letterGrade(score):
    if score >= 90:
        letter = 'A'
    else:    # grade must be B, C, D or F
        if score >= 80:
            letter = 'B'
        else:    # grade must be C, D or F
            if score >= 70:
                letter = 'C'
            else:    # grade must D or F
                if score >= 60:
                    letter = 'D'
                else:
                    letter = 'F'
    return letter
```

This repeatedly increasing indentation with an `if` statement as the `else` block can be annoying and distracting. A preferred alternative in this situation, that avoids all this indentation, is to combine each `else` and `if` block into an `elif` block:

```
def letterGrade(score):
    if score >= 90:
        letter = 'A'
    elif score >= 80:
        letter = 'B'
    elif score >= 70:
        letter = 'C'
    elif score >= 60:
        letter = 'D'
    else:
        letter = 'F'
    return letter
```

The most elaborate syntax for an `if-elif-else` statement is indicated in general below:

```
if condition1 :
    indentedStatementBlockForTrueCondition1
elif condition2 :
    indentedStatementBlockForFirstTrueCondition2
elif condition3 :
    indentedStatementBlockForFirstTrueCondition3
elif condition4 :
    indentedStatementBlockForFirstTrueCondition4
else:
    indentedStatementBlockForEachConditionFalse
```

The `if`, each `elif`, and the final `else` lines are all aligned. There can be any number of `elif` lines, each followed by an indented block. (Three happen to be illustrated above.) With this construction *exactly one* of the indented blocks is executed. It is the one corresponding to the *first* `True` condition, or, if all conditions are `False`, it is the block after the final `else` line.

Be careful of the strange Python contraction. It is `elif`, not `elseif`. A program testing the `letterGrade` function is in example program `grade1.py`.

See [Grade Exercise](#) (page 127).

A final alternative for `if` statements: `if-elif-....` with *no* `else`. This would mean changing the syntax for `if-elif-else` above so the final `else:` and the block after it would be omitted. It is similar to the basic `if` statement

without an `else`, in that it is possible for *no* indented block to be executed. This happens if *none* of the conditions in the tests are true.

With an `else` included, *exactly* one of the indented blocks is executed. Without an `else`, at *most* one of the indented blocks is executed.

```
if weight > 120:
    print('Sorry, we can not take a suitcase that heavy.')
elif weight > 50:
    print('There is a $25 charge for luggage that heavy.')
```

This `if-elif` statement only prints a line if there is a problem with the weight of the suitcase.

Sign Exercise

Write a program `sign.py` to ask the user for a number. Print out which category the number is in: `'positive'`, `'negative'`, or `'zero'`.

Grade Exercise

In Idle, load `grade1.py` and save it as `grade2.py`. Modify `grade2.py` so it has an equivalent version of the `letterGrade` function that tests in the opposite order, first for F, then D, C, Hint: How many tests do you need to do?⁴

Be sure to run your new version and test with different inputs that test all the different paths through the program. Be careful to test around cut-off points. What does a grade of 79.6 imply? What about exactly 80?

Wages Exercise

* Modify the `wages.py` or the `wages1.py` example to create a program `wages2.py` that assumes people are paid double time for hours over 60. Hence they get paid for at most 20 hours overtime at 1.5 times the normal rate. For example, a person working 65 hours with a regular wage of \$10 per hour would work at \$10 per hour for 40 hours, at 1.5 * \$10 for 20 hours of overtime, and 2 * \$10 for 5 hours of double time, for a total of

$$10*40 + 1.5*10*20 + 2*10*5 = \$800.$$

You may find `wages1.py` easier to adapt than `wages.py`.

Be sure to test all paths through the program! Your program is likely to be a modification of a program where some choices worked before, but once you change things, retest for all the cases! Changes can mess up things that worked before.

3.1.6 Nesting Control-Flow Statements

The power of a language like Python comes largely from the variety of ways basic statements can be *combined*. In particular, `for` and `if` statements can be nested inside each other's indented blocks. For example, suppose you want to print only the positive

numbers from an arbitrary list of numbers in a function with the following heading. *Read* the pieces for now.

```
def printAllPositive(numberList):
    '''Print only the positive numbers in numberList.'''
```

⁴ 4 tests to distinguish the 5 cases, as in the previous version

For example, suppose `numberList` is `[3, -5, 2, -1, 0, 7]`. You want to process a list, so that suggests a for-each loop,

```
for num in numberList:
```

but a for-each loop runs the *same* code body for each element of the list, and we only want

```
print(num)
```

for *some* of them. That seems like a major obstacle, but think closer at what needs to happen concretely. As a human, who has eyes of amazing capacity, you are drawn immediately to the actual correct numbers, 3, 2, and 7, but clearly a computer doing this systematically will have to *check every* number. In fact, there is a *consistent* action required: Every number must be tested to see *if* it should be printed. This suggests an `if` statement, with the condition `num > 0`. Try loading into Idle and running the example program `onlyPositive.py`, whose code is shown below. It ends with a line testing the function:

```
def printAllPositive(numberList):
    '''Print only the positive numbers in numberList.'''
    for num in numberList:
        if num > 0:
            print(num)

printAllPositive([3, -5, 2, -1, 0, 7])
```

This idea of nesting `if` statements enormously expands the possibilities with loops. Now different things can be done at different times in loops, as long as there is a *consistent test* to allow a choice between the alternatives. Shortly, `while` loops will also be introduced, and you will see `if` statements nested inside of them, too.

The rest of this section deals with graphical examples.

Run example program `bounce1.py`. It has a red ball moving and bouncing obliquely off the edges. If you watch several times, you should see that it starts from random locations. Also you can repeat the program from the Shell prompt after you have run the script. For instance, right after running the program, try in the *Shell*

```
bounceBall(-3, 1)
```

The parameters give the amount the shape moves in each animation step. You can try other values in the *Shell*, preferably with magnitudes less than 10.

For the remainder of the description of this example, *read* the extracted text pieces.

The animations before this were totally scripted, saying exactly how many moves in which direction, but in this case the direction of motion changes with every bounce. The program has a graphic object `shape` and the central animation step is

```
shape.move(dx, dy)
```

but in this case, `dx` and `dy` have to change when the ball gets to a boundary. For instance, imagine the ball getting to the left side as it is moving to the left and up. The bounce obviously alters the horizontal part of the motion, in fact reversing it, but the ball would still continue up. The reversal of the horizontal part of the motion means that the horizontal shift changes direction and therefore its sign:

```
dx = -dx
```

but `dy` does not need to change. This switch does not happen at each animation step, but only when the ball reaches the edge of the window. It happens only some of the time - suggesting an `if` statement. Still the condition must be determined. Suppose the center of the ball has coordinates `(x, y)`. When `x` reaches some particular `x` coordinate, call it `xLow`, the ball should bounce.



The edge of the window is at coordinate 0, but `xLow` should not be 0, or the ball would be half way off the screen before bouncing! For the edge of the ball to hit the edge of the screen, the `x` coordinate of the center must be the length of the radius away, so actually `xLow` is the radius of the ball.

Animation goes quickly in small steps, so I cheat. I allow the ball to take one (small, quick) step past where it really should go (`xLow`), and then we reverse it so it comes back to where it belongs. In particular

```
if x < xLow:
    dx = -dx
```

There are similar bounding variables `xHigh`, `yLow` and `yHigh`, all the radius away from the actual edge coordinates, and similar conditions to test for a bounce off each possible edge. Note that whichever edge is hit, one coordinate, either `dx` or `dy`, reverses. One way the collection of tests could be written is

```
if x < xLow:
    dx = -dx
if x > xHigh:
    dx = -dx
if y < yLow:
    dy = -dy
if y > yHigh:
    dy = -dy
```

This approach would cause there to be some extra testing: If it is true that `x < xLow`, then it is impossible for it to be true that `x > xHigh`, so we do not need both tests together. We avoid unnecessary tests with an `elif` clause (for both `x` and `y`):

```
if x < xLow:
    dx = -dx
elif x > xHigh:
    dx = -dx
if y < yLow:
    dy = -dy
elif y > yHigh:
    dy = -dy
```

Note that the middle `if` is *not* changed to an `elif`, because it is possible for the ball to reach a *corner*, and need both `dx` and `dy` reversed.

The program also uses several methods to read part of the state of graphics objects that we have not used in examples yet. Various graphics objects, like the circle we are using as the shape, know their center point, and it can be accessed with the `getCenter()` method. (Actually a clone of the point is returned.) Also each coordinate of a `Point` can be accessed with the `getX()` and `getY()` methods.

This explains the new features in the central function defined for bouncing around in a box, `bounceInBox`. The animation arbitrarily goes on in a simple repeat loop for 600 steps. (A later example will improve this behavior.)

```
def bounceInBox(shape, dx, dy, xLow, xHigh, yLow, yHigh):
    ''' Animate a shape moving in jumps (dx, dy), bouncing when
        its center reaches the low and high x and y coordinates.
    '''
    delay = .005
    for i in range(600):
        shape.move(dx, dy)
```

```
center = shape.getCenter()
x = center.getX()
y = center.getY()
if x < xLow:
    dx = -dx
elif x > xHigh:
    dx = -dx
if y < yLow:
    dy = -dy
elif y > yHigh:
    dy = -dy
time.sleep(delay)
```

The program starts the ball from an arbitrary point inside the allowable rectangular bounds. This is encapsulated in a utility function included in the program, `getRandomPoint`. The `getRandomPoint` function uses the `randrange` function from the module `random`. Note that in parameters for both the functions `range` and `randrange`, the end stated is *past* the last value actually desired:

```
def getRandomPoint(xLow, xHigh, yLow, yHigh):
    '''Return a random Point with coordinates in the range specified.'''
    x = random.randrange(xLow, xHigh+1)
    y = random.randrange(yLow, yHigh+1)
    return Point(x, y)
```

The full program is listed below, repeating `bounceInBox` and `getRandomPoint` for completeness. Several parts that may be useful later, or are easiest to follow as a unit, are separated out as functions. Make sure you see how it all hangs together or ask questions!

```
'''
Show a ball bouncing off the sides of the window.
'''

from graphics import *
import time, random

def bounceInBox(shape, dx, dy, xLow, xHigh, yLow, yHigh):
    ''' Animate a shape moving in jumps (dx, dy), bouncing when
    its center reaches the low and high x and y coordinates.
    '''
    delay = .005
    for i in range(600):
        shape.move(dx, dy)
        center = shape.getCenter()
        x = center.getX()
        y = center.getY()
        if x < xLow:
            dx = -dx
        elif x > xHigh:
            dx = -dx
        if y < yLow:
            dy = -dy
        elif y > yHigh:
            dy = -dy
        time.sleep(delay)

def getRandomPoint(xLow, xHigh, yLow, yHigh):
    '''Return a random Point with coordinates in the range specified.'''
    x = random.randrange(xLow, xHigh+1)
```

```

y = random.randrange(yLow, yHigh+1)
return Point(x, y)

def makeDisk(center, radius, win):
    '''return a red disk that is drawn in win with given center and radius.'''
    disk = Circle(center, radius)
    disk.setOutline("red")
    disk.setFill("red")
    disk.draw(win)
    return disk

def bounceBall(dx, dy):
    '''Make a ball bounce around the screen, initially moving by (dx, dy)
    at each jump.'''
    win = GraphWin('Ball Bounce', 290, 290)
    win.yUp()

    radius = 10
    xLow = radius # center is separated from the wall by the radius at a bounce
    xHigh = win.getWidth() - radius
    yLow = radius
    yHigh = win.getHeight() - radius

    center = getRandomPoint(xLow, xHigh, yLow, yHigh)
    ball = makeDisk(center, radius, win)

    bounceInBox(ball, dx, dy, xLow, xHigh, yLow, yHigh)
    win.close()

bounceBall(3, 5)

```

Short String Exercise

Write a program `short.py` with a function `printShort` with heading:

```

def printShort(strings):
    '''Given a list of strings,
    print the ones with at most three characters.
    >>> printShort(['a', 'long', 'one'])
    a
    one
    '''

```

In your main program, test the function, calling it several times with different lists of strings. Hint: Find the length of each string with the `len` function.

The function documentation here models a common approach: illustrating the behavior of the function with a Python Shell interaction. This part begins with a line starting with `>>>`. Other exercises and examples will also document behavior in the Shell.

Even Print Exercise

Write a program `even1.py` with a function `printEven` with heading:

```

def printEven(nums):
    '''Given a list of integers nums,

```

```
print the even ones.  
  
>>> printEven([4, 1, 3, 2, 7])  
4  
2  
'''
```

In your main program, test the function, calling it several times with different lists of integers. Hint: A number is even if its remainder, when dividing by 2, is 0.

Even List Exercise

Write a program `even2.py` with a function `chooseEven` with heading:

```
def chooseEven(nums):  
    '''Given a list of integers, nums,  
    return a list containing only the even ones.  
  
    >>> chooseEven([4, 1, 3, 2, 7])  
    [4, 2]  
    '''
```

In your main program, test the function, calling it several times with different lists of integers and printing the results in the main program. (The documentation string illustrates the function call in the Python shell, where the return value is automatically printed. Remember, that in a program, you only print what you explicitly say to print.) Hint: In the function, create a new list, and append the appropriate numbers to it, before returning the result.

Unique List Exercise

* The `madlib2.py` program has its `getKeys` function, which first generates a list of each occurrence of a cue in the story format. This gives the cues in order, but likely includes repetitions. The original version of `getKeys` uses a quick method to remove duplicates, forming a **set** from the list. There is a disadvantage in the conversion, though: Sets are not ordered, so when you iterate through the resulting set, the order of the cues will likely bear no resemblance to the order they first appeared in the list. That issue motivates this problem:

Copy `madlib2.py` to `madlib2a.py`, and add a function with this heading:

```
def uniqueList(aList):  
    ''' Return a new list that includes the first occurrence of each value  
    in aList, and omits later repeats. The returned list should include  
    the first occurrences of values in aList in their original order.  
  
    >>> vals = ['cat', 'dog', 'cat', 'bug', 'dog', 'ant', 'dog', 'bug']  
    >>> uniqueList(vals)  
    ['cat', 'dog', 'bug', 'ant']  
    '''
```

Hint: Process `aList` in order. Use the `in` syntax to only append elements to a new list that are not already in the new list.

After perfecting the `uniqueList` function, replace the last line of `getKeys`, so it uses `uniqueList` to remove duplicates in `keyList`.

Check that your `madlib2a.py` prompts you for cue values in the order that the cues first appear in the `madlib` format string.

3.1.7 Compound Boolean Expressions

To be eligible to graduate from Loyola University Chicago, you must have 120 credits *and* a GPA of at least 2.0. This translates directly into Python as a *compound condition*:

```
credits >= 120 and GPA >= 2.0
```

This is true if both `credits >= 120` is true and `GPA >= 2.0` is true. A short example program using this would be:

```
credits = float(input('How many units of credit do you have? '))
GPA = float(input('What is your GPA? '))
if credits >= 120 and GPA >= 2.0:
    print('You are eligible to graduate!')
else:
    print('You are not eligible to graduate.')
```

The new Python syntax is for the operator and:

condition1 and condition2

The compound condition is true if both of the component conditions are true. It is false if *at least* one of the conditions is false.

See *Congress Exercise* (page 137).

In the last example in the previous section, there was an `if-elif` statement where both tests had the same block to be done if the condition was true:

```
if x < xLow:
    dx = -dx
elif x > xHigh:
    dx = -dx
```

There is a simpler way to state this in a sentence: If `x < xLow` or `x > xHigh`, switch the sign of `dx`. That translates directly into Python:

```
if x < xLow or x > xHigh:
    dx = -dx
```

The word `or` makes another compound condition:

condition1 or condition2

is true if *at least* one of the conditions is true. It is false if both conditions are false. This corresponds to *one* way the word “or” is used in English. Other times in English “or” is used to mean *exactly one* alternative is true.

Warning: When translating a problem stated in English using “or”, be careful to determine whether the meaning matches Python’s `or`.

It is often convenient to encapsulate complicated tests inside a function. Think how to complete the function starting:

```
def isInside(rect, point):
    '''Return True if the point is inside the Rectangle rect.'''
    pt1 = rect.getP1()
    pt2 = rect.getP2()
```

Recall that a `Rectangle` is specified in its constructor by two diagonally oppose `Points`. This example gives the first use in the tutorials of the `Rectangle` methods that recover those two corner points, `getP1` and `getP2`. The

program calls the points obtained this way `pt1` and `pt2`. The `x` and `y` coordinates of `pt1`, `pt2`, and `point` can be recovered with the methods of the `Point` type, `getX()` and `getY()`.

Suppose that I introduce variables for the `x` coordinates of `pt1`, `point`, and `pt2`, calling these `x`-coordinates `end1`, `val`, and `end2`, respectively. On first try you might decide that the needed mathematical relationship to test is

```
end1 <= val <= end2
```

Unfortunately, this is not enough: The only requirement for the two corner points is that they be diagonally opposite, not that the coordinates of the second point are higher than the corresponding coordinates of the first point. It could be that `end1` is 200; `end2` is 100, and `val` is 120. In this latter case `val` is between `end1` and `end2`, but substituting into the expression above

```
200 <= 120 <= 100
```

is `False`. The 100 and 200 need to be reversed in this case. This makes a complicated situation. Also this is an issue which must be revisited for both the `x` and `y` coordinates. I introduce an auxiliary function `isBetween` to deal with one coordinate at a time. It starts:

```
def isBetween(val, end1, end2):  
    '''Return True if val is between the ends.  
    The ends do not need to be in increasing order.'''
```

Clearly this is true if the original expression, `end1 <= val <= end2`, is true. You must also consider the possible case when the order of the ends is reversed: `end2 <= val <= end1`. How do we combine these two possibilities? The Boolean connectives to consider are `and` and `or`. Which applies? You only need one to be true, so `or` is the proper connective:

A correct but redundant function body would be:

```
if end1 <= val <= end2 or end2 <= val <= end1:  
    return True  
else:  
    return False
```

Check the meaning: if the compound expression is `True`, return `True`. If the condition is `False`, return `False` – in either case return the *same* value as the test condition. See that a much simpler and neater version is to just return the value of the condition itself!

```
return end1 <= val <= end2 or end2 <= val <= end1
```

Note: In general you should *not* need an `if-else` statement to choose between true and false values! Operate directly on the boolean expression.

A side comment on expressions like

```
end1 <= val <= end2
```

Other than the two-character operators, this is like standard math syntax, *chaining* comparisons. In Python any number of comparisons can be *chained* in this way, closely approximating mathematical notation. Though this is good Python, be aware that if you try other high-level languages like Java and C++, such an expression is gibberish. Another way the expression can be expressed (and which translates directly to other languages) is:

```
end1 <= val and val <= end2
```

So much for the auxiliary function `isBetween`. Back to the `isInside` function. You can use the `isBetween` function to check the `x` coordinates,

```
isBetween(point.getX(), p1.getX(), p2.getX())
```

and to check the y coordinates,

```
isBetween(point.getY(), p1.getY(), p2.getY())
```

Again the question arises: how do you combine the two tests?

In this case we need the point to be both between the sides *and* between the top and bottom, so the proper connector is *and*.

Think how to finish the `isInside` method. Hint: ⁵

Sometimes you want to test the opposite of a condition. As in English you can use the word `not`. For instance, to test if a `Point` was not inside `Rectangle Rect`, you could use the condition

```
not isInside(rect, point)
```

In general,

`not condition`

is `True` when *condition* is `False`, and `False` when *condition* is `True`.

The example program `chooseButton1.py`, shown below, is a complete program using the `isInside` function in a simple application, choosing colors. Pardon the length. Do check it out. It will be the starting point for a number of improvements that shorten it and make it more powerful in the next section. First a brief overview:

The program includes the functions `isBetween` and `isInside` that have already been discussed. The program creates a number of colored rectangles to use as buttons and also as picture components. Aside from specific data values, the code to create each rectangle is the same, so the action is encapsulated in a function, `makeColoredRect`. All of this is fine, and will be preserved in later versions.

The present main function is long, though. It has the usual graphics starting code, draws buttons and picture elements, and then has a number of code sections prompting the user to choose a color for a picture element. Each code section has a long `if-elif-else` test to see which button was clicked, and sets the color of the picture element appropriately.

```
'''Make a choice of colors via mouse clicks in Rectangles --
A demonstration of Boolean operators and Boolean functions.'''

from graphics import *

def isBetween(x, end1, end2):
    '''Return True if x is between the ends or equal to either.
    The ends do not need to be in increasing order.'''

    return end1 <= x <= end2 or end2 <= x <= end1

def isInside(point, rect):
    '''Return True if the point is inside the Rectangle rect.'''

    pt1 = rect.getP1()
    pt2 = rect.getP2()
    return isBetween(point.getX(), pt1.getX(), pt2.getX()) and \
           isBetween(point.getY(), pt1.getY(), pt2.getY())

def makeColoredRect(corner, width, height, color, win):
    ''' Return a Rectangle drawn in win with the upper left corner
    and color specified.'''

    corner2 = corner.clone()
    corner2.move(width, -height)
```

⁵ Once again, you are calculating and returning a Boolean result. You do not need an `if-else` statement.

```
rect = Rectangle(corner, corner2)
rect.setFill(color)
rect.draw(win)
return rect

def main():
    win = GraphWin('pick Colors', 400, 400)
    win.yUp() # right side up coordinates

    redButton = makeColoredRect(Point(310, 350), 80, 30, 'red', win)
    yellowButton = makeColoredRect(Point(310, 310), 80, 30, 'yellow', win)
    blueButton = makeColoredRect(Point(310, 270), 80, 30, 'blue', win)

    house = makeColoredRect(Point(60, 200), 180, 150, 'gray', win)
    door = makeColoredRect(Point(90, 150), 40, 100, 'white', win)
    roof = Polygon(Point(50, 200), Point(250, 200), Point(150, 300))
    roof.setFill('black')
    roof.draw(win)

    msg = Text(Point(win.getWidth()/2, 375), 'Click to choose a house color.')
    msg.draw(win)
    pt = win.getMouse()

    if isInside(pt, redButton):
        color = 'red'
    elif isInside(pt, yellowButton):
        color = 'yellow'
    elif isInside(pt, blueButton):
        color = 'blue'
    else :
        color = 'white'
    house.setFill(color)

    msg.setText('Click to choose a door color.')
    pt = win.getMouse()

    if isInside(pt, redButton):
        color = 'red'
    elif isInside(pt, yellowButton):
        color = 'yellow'
    elif isInside(pt, blueButton):
        color = 'blue'
    else :
        color = 'white'
    door.setFill(color)

    win.promptClose(msg)

main()
```

The only further new feature used is in the long return statement in `isInside`.

```
return isBetween(point.getX(), pt1.getX(), pt2.getX()) and \
       isBetween(point.getY(), pt1.getY(), pt2.getY())
```

Recall that Python is smart enough to realize that a statement continues to the next line if there is an unmatched pair of parentheses or brackets. Above is another situation with a long statement, but there are no unmatched parentheses on a line. For readability it is best *not* to make an enormous long line that would run off your screen or paper.

Continuing to the next line is recommended. You can make the *final* character on a line be a backslash (`'\\'`) to indicate the statement continues on the next line. This is not particularly neat, but it is a rather rare situation. Most statements fit neatly on one line, and the creator of Python decided it was best to make the syntax simple in the most common situation. (Many other languages require a special statement terminator symbol like `';`' and pay no attention to newlines). Extra parentheses here would not hurt, so an alternative would be

```
return (isBetween(point.getX(), pt1.getX(), pt2.getX()) and
        isBetween(point.getY(), pt1.getY(), pt2.getY()) )
```

The `chooseButton1.py` program is long partly because of repeated code. The next section gives another version involving lists.

Congress Exercise

A person is eligible to be a US Senator who is at least 30 years old and has been a US citizen for at least 9 years. Write an initial version of a program `congress.py` to obtain age and length of citizenship from the user and print out if a person is eligible to be a Senator or not.

A person is eligible to be a US Representative who is at least 25 years old and has been a US citizen for at least 7 years. Elaborate your program `congress.py` so it obtains age and length of citizenship and prints out just the *one* of the following three statements that is accurate:

- You are eligible for both the House and Senate.
- You eligible only for the House.
- You are ineligible for Congress.

3.1.8 More String Methods

Here are a few more string methods useful in the next exercises, assuming the methods are applied to a string `s`:

- `s.startswith(pre)`

returns True if string `s` starts with string `pre`: Both `'-123'.startswith('-')` and `'downstairs'.startswith('down')` are True, but `'1 - 2 - 3'.startswith('-')` is False.

- `s.endswith(suffix)`

returns True if string `s` ends with string `suffix`: Both `'whoever'.endswith('ever')` and `'downstairs'.endswith('airs')` are True, but `'1 - 2 - 3'.endswith('-')` is False.

- `s.replace(sub, replacement, count)`

returns a new string with up to the first `count` occurrences of string `sub` replaced by `replacement`. The `replacement` can be the empty string to delete `sub`. For example:

```
s = '-123'
t = s.replace('-', '', 1) # t equals '123'
t = t.replace('-', '', 1) # t is still equal to '123'
u = '.2.3.4.'
v = u.replace('.', '', 2) # v equals '23.4.'
w = u.replace('.', ' dot ', 5) # w equals '2 dot 3 dot 4 dot '
```

Article Start Exercise

In library alphabetizing, if the initial word is an *article* (“The”, “A”, “An”), then it is ignored when ordering entries. Write a program completing this function, and then testing it:

```
def startsWithArticle(title):  
    '''Return True if the first word of title is "The", "A" or "An".'''
```

Be careful, if the title starts with “There”, it does not start with an article. What should you be testing for?

Is Number String Exercise

** In the later *Safe Number Input Exercise* (page 148), it will be important to know if a string can be converted to the desired type of number. Explore that here. Save example `isNumberStringStub.py` as `isNumberString.py` and complete it. It contains headings and documentation strings for the functions in both parts of this exercise.

A legal whole number string consists entirely of digits. Luckily strings have an `isdigit` method, which is true when a nonempty string consists entirely of digits, so `'2397'.isdigit()` returns `True`, and `'23a'.isdigit()` returns `False`, exactly corresponding to the situations when the string represents a whole number!

In both parts be sure to test carefully. Not only confirm that all appropriate strings return `True`. Also be sure to test that you return `False` for *all* sorts of bad strings.

1. Recognizing an integer string is more involved, since it can start with a minus sign (or not). Hence the `isdigit` method is not enough by itself. This part is the most straightforward if you have worked on the sections *String Indices* (page 75) and *String Slices* (page 76). An alternate approach works if you use the count method from *Object Orientation* (page 73), and some methods from this section.

Complete the function `isIntStr`.

2. Complete the function `isDecimalStr`, which introduces the possibility of a decimal point (though a decimal point is not required). The string methods mentioned in the previous part remain useful.

3.2 Loops and Tuples

This section will discuss several improvements to the `chooseButton1.py` program from the last section that will turn it into example program `chooseButton2.py`.

First an introduction to *tuples*, which we will use for the first time in this section:

A tuple is similar to a list except that a literal tuple is enclosed in parentheses rather than square brackets, and a tuple is immutable. In particular you cannot change the length or substitute elements, unlike a list. Examples are

```
(1, 2, 3)  
( 'yes', 'no' )
```

Making a tuple is another way to make several items into a single object. You can refer to individual parts with indexing, like with lists, but a more common way is with multiple assignment. A silly simple example:

```
tup = (1, 2)  
(x, y) = tup  
print(x)  # prints 1  
print(y)  # prints 2
```

Now back to improving the `chooseButton1.py` program, which has similar code repeating in several places. Imagine how much worse it would be if there were more colors to choose from and more parts to color!

First consider the most egregious example:

```

if isInside(pt, redButton):
    color = 'red'
elif isInside(pt, yellowButton):
    color = 'yellow'
elif isInside(pt, blueButton):
    color = 'blue'
else :
    color = 'white'

```

Not only is this exact `if` statement repeated several times, all the conditions within the `if` statement are very similar! Part of the reason I did not put this all in a function was the large number of separate variables. On further inspection, the particular variables `redButton`, `yellowButton`, `blueButton`, all play a similar role, and their names are not really important, it is their *associations* that are important: that `redButton` goes with 'red', When there is a sequence of things all treated similarly, it suggests a list and a loop. An issue here is that the changing data is *paired*, a rectangle with a color string. There are a number of ways to handle such associations. A very neat way in Python to package a pair (or more things together) is a *tuple*, turning several things into one object, as in (`redButton`, 'red'). Objects such as this tuple can be put in a larger list:

```

choicePairs = [(redButton, 'red'), (yellowButton, 'yellow'),
               (blueButton, 'blue')]

```

Such tuples may be neatly handled in a `for` statement. You can imagine a function to encapsulate the color choice starting:

```

def getChoice(choicePairs, default, win):
    '''Given a list choicePairs of tuples, with each tuple in the form
    (rectangle, choice), return the choice that goes with the rectangle
    in win where the mouse gets clicked, or return default if the click
    is in none of the rectangles.'''

    point = win.getMouse()
    for (rectangle, choice) in choicePairs:
        #....

```

This is the first time we have had a `for` loop going through a list of *tuples*. Recall that we can do multiple assignments at once with tuples. This also works in a `for` loop heading. The `for` loop goes through one tuple in the list `choicePairs` at a time. The first time through the loop the tuple taken from the list is (`redButton`, 'red'). This `for` loop does a multiple assignment to (`rectangle`, `choice`) each time through the loop, so the first time `rectangle` refers to `redButton` and `choice` refers to 'red'. The next time through the loop, the second tuple from the list is used, (`yellowButton`, 'yellow') so this time inside the loop `rectangle` will refer to `yellowButton` and `choice` refers to 'yellow' This is a neat Python feature.⁶

There is still a problem. We could test each rectangle in the `for`-each loop, but the original `if-elif ...` statement in `chooseButton1.py` stops when the *first* condition is true. However `for`-each statements are designed to go all the way *through* the sequence. There is a simple way out of this in a function: A `return` statement always stops the execution of a function. When we have found the rectangle containing the point, the function can `return` the desired choice immediately!

```

def getChoice(choicePairs, default, win):
    '''Given a list of tuples (rectangle, choice), return the choice
    that goes with the rectangle in win where the mouse gets clicked,
    or return default if the click is in none of the rectangles.'''

    point = win.getMouse()

```

⁶ Particularly in other object-oriented languages where lists and tuples are way less easy to use, the preferred way to group associated objects, like `rectangle` and `choice`, is to make a custom object type containing them all. This is also possible and often useful in Python. In some relatively simple cases, like in the current example, use of tuples can be easier to follow, though the approach taken is a matter of taste. The topic of creating custom type of objects will not be taken up in this tutorial.

```
for (rectangle, choice) in choicePairs:
    if isInside(point, rectangle):
        return choice
return default
```

Note that the `else` part in `chooseButton1.py` corresponds to the statement *after* the loop above. If execution gets past the loop, then none of the conditions tested in the loop was true.

With appropriate parameters, the looping function is a complete replacement for the original `if-elif` statement! The replacement has further advantages.

- There can be an arbitrarily long list of pairs, and the exact same code works.
- This code is clearer and easier to read, since there is no need to read through a long sequence of similar `if-elif` clauses.
- The names of the rectangles in the tuples in the list are never referred to. They are unnecessary here. Only a list needs to be specified. That could be useful earlier in the program

Are individual names for the rectangles needed earlier? No, the program only needs to end up with the pairs of the form `(rectangle, color)` in a list. The statements in the original program, below, have a similar form which will allow them to be rewritten:

```
redButton = makeColoredRect(Point(310, 350), 80, 30, 'red', win)
yellowButton = makeColoredRect(Point(310, 310), 80, 30, 'yellow', win)
blueButton = makeColoredRect(Point(310, 270), 80, 30, 'blue', win)
```

As stated earlier, we could use the statements above and then make a list of pairs with the statement

```
choicePairs = [(redButton, 'red'), (yellowButton, 'yellow'),
               (blueButton, 'blue')]
```

Now I will look at an alternative that would be particularly useful if there were considerably more buttons and colors.

All the assignment statements with `makeColorRect` have the same format, but differing data for several parameters. I use that fact in the alternate code:

```
choicePairs = list()
buttonSetup = [(310, 350, 'red'), (310, 310, 'yellow'),
               (310, 270, 'blue')]
for (x, y, color) in buttonSetup:
    button = makeColoredRect(Point(x, y), 80, 30, color, win)
    choicePairs.append((button, color))
```

I extract the changing data from the creation of the rectangles into a list, `buttonSetup`. Since more than one data items are different for each of the original lines, the list contains a tuple of data from each of the original lines. Then I loop through this list and not only create the rectangles for each color, but also accumulates the `(rectangle, color)` pairs for the list `choicePairs`.

Note the double parentheses in the last line of the code. The outer ones are for the method call. The inner ones create a single tuple as the parameter.

Assuming I do not need the original individual names of the Rectangles, this code with the loop will completely substitute for the previous code with its separate lines with the separate named variables and the recurring formats.

This code has advantages similar to those listed above for the `getChoice` code.

Now look at what this new code means for the interactive part of the program. The interactive code directly reduces to

```
msg = Text(Point(win.getWidth()/2, 375), 'Click to choose a house color.')
msg.draw(win)
color = getChoice(colorPairs, 'white', win)
```



```
house.setFill(color)

msg.setText('Click to choose a door color.')
color = getChoice(colorPairs, 'white', win)
door.setFill(color)
```

In the original version with the long `if-elif` statements, the interactive portion only included portions for the user to set the color of two shapes in the picture (or you would have been reading code forever). Looking now at the similarity of the code for the two parts, we can imagine another loop, that would easily allow for many more parts to be colored interactively.

There are still several differences to resolve. First the message `msg` is *created* the first time, and only the text is *set* the next time. That is easy to make consistent by splitting the first part into an initialization and a separate call to `setText` like in the second part:

```
msg = Text(Point(win.getWidth()/2, 375), '')
msg.draw(win)

msg.setText('Click to choose a house color.')
```

Then look to see the differences between the code for the two choices. The `shape` object to be colored and the name used to describe the shape change: two changes in each part. Again tuples can store the changes of the form (shape, description). This is another place appropriate for a loop driven by tuples. The (shape, description) tuples should be explicitly written into a list that can be called `shapePairs`. We could easily extend the list `shapePairs` to allow more graphics objects to be colored. In the code below, the roof is added.

The new interactive code can start with:

```
shapePairs = [(house, 'house'), (door, 'door'), (roof, 'roof')]
msg = Text(Point(win.getWidth()/2, 375), '')
msg.draw(win)
for (shape, description) in shapePairs:
    prompt = 'Click to choose a ' + description + ' color.'
    # ....
```

Can you finish the body of the loop? Look at the original version of the interactive code. When you are done thinking about it, go on to my solution. The entire code is in example program `chooseButton2.py`, and also below. The changes from `chooseButton1.py` are in three blocks, each labeled `#NEW` in the code. The new parts are the `getChoice` function and the two new sections of `main` with the loops:

```
'''Make a choice of colors via mouse clicks in Rectangles --
Demonstate loops using lists of tuples of data.'''

from graphics import *

def isBetween(x, end1, end2):
    '''Return True if x is between the ends or equal to either.
    The ends do not need to be in increasing order.'''

    return end1 <= x <= end2 or end2 <= x <= end1

def isInside(point, rect):
    '''Return True if the point is inside the Rectangle rect.'''

    pt1 = rect.getP1()
    pt2 = rect.getP2()
    return isBetween(point.getX(), pt1.getX(), pt2.getX()) and \
           isBetween(point.getY(), pt1.getY(), pt2.getY())
```

```
def makeColoredRect(corner, width, height, color, win):
    ''' Return a Rectangle drawn in win with the upper left corner
    and color specified.'''

    corner2 = corner.clone()
    corner2.move(width, -height)
    rect = Rectangle(corner, corner2)
    rect.setFill(color)
    rect.draw(win)
    return rect

def getChoice(choicePairs, default, win):      #NEW
    '''Given a list choicePairs of tuples with each tuple in the form
    (rectangle, choice), return the choice that goes with the rectangle
    in win where the mouse gets clicked, or return default if the click
    is in none of the rectangles.'''

    point = win.getMouse()
    for (rectangle, choice) in choicePairs:
        if isInside(point, rectangle):
            return choice
    return default

def main():
    win = GraphWin('pick Colors', 400, 400)
    win.yUp()

    #NEW
    choicePairs = list()
    buttonSetup = [(310, 350, 'red'), (310, 310, 'yellow'), (310, 270, 'blue')]
    for (x, y, color) in buttonSetup:
        button = makeColoredRect(Point(x, y), 80, 30, color, win)
        choicePairs.append((button, color))

    house = makeColoredRect(Point(60, 200), 180, 150, 'gray', win)
    door = makeColoredRect(Point(90, 150), 40, 100, 'white', win)
    roof = Polygon(Point(50, 200), Point(250, 200), Point(150, 300))
    roof.setFill('black')
    roof.draw(win)

    #NEW
    shapePairs = [(house, 'house'), (door, 'door'), (roof, 'roof')]
    msg = Text(Point(win.getWidth()/2, 375), '')
    msg.draw(win)
    for (shape, description) in shapePairs:
        prompt = 'Click to choose a ' + description + ' color.'
        msg.setText(prompt)
        color = getChoice(choicePairs, 'white', win)
        shape.setFill(color)

    win.promptClose(msg)

main()
```

Run it.

With the limited number of choices in `chooseButton1.py`, the change in length to convert to `chooseButton2.py` is not significant, but the change in organization is significant if you try to extend the pro-

gram, as in the exercise below. See if you agree!

3.2.1 Exercises

Choose Button Exercise

1. Write a program `chooseButton3.py`, modifying `chooseButton2.py`. Look at the format of the list `buttonSetup`, and extend it so there is a larger choice of buttons and colors. Add at least one button and color.
2. Further extend the program `chooseButton3.py` by adding some further graphical object shape to the picture, and extend the list `shapePairs`, so they can all be interactively colored.
3. (Optional) If you would like to carry this further, also add a prompt to change the outline color of each shape, and then carry out the changes the user desires.
4. (Optional Challenge) ** Look at the pattern within the list `buttonSetup`. It has a consistent x coordinate, and there is a regular pattern to the change in the y coordinate (a consistent decrease each time). The only data that is arbitrary each time is the sequence of colors. Write a further version `chooseButton4.py` with a function `makeButtonSetup`, that takes a list of color names as a parameter and uses a loop to create the list used as `buttonSetup`. End by returning this list. Use the function to initialize `buttonSetup`. If you like, make the function more general and include parameters for the x coordinate, the starting y coordinate and the regular y coordinate change.

3.3 While Statements

3.3.1 Simple while Loops

Other than the trick with using a `return` statement inside of a `for` loop, all of the loops so far have gone all the way through a *specified* list. In any case the `for` loop has required the use of a specific list. This is often too restrictive. A Python `while` loop behaves quite similarly to common English usage. If I say

While your tea is too hot, add a chip of ice.

Presumably you would test your tea. If it were too hot, you would add a little ice. If you test again and it is still too hot, you would add ice again. *As long as* you tested and found it was true that your tea was too hot, you would go back and add more ice. Python has a similar syntax:

while condition : indentedBlock

Setting up the English example in a similar format would be:

while your tea is too hot : add a chip of ice

To make things concrete and numerical, suppose the following: The tea starts at 115 degrees Fahrenheit. You want it at 112 degrees. A chip of ice turns out to lower the temperature one degree each time. You test the temperature each time, and also print out the temperature before reducing the temperature. In Python you could write and run the code below, saved in example program `cool.py`:

```

1 temperature = 115
2 while temperature > 112: # first while loop code
3     print(temperature)
4     temperature = temperature - 1
5
6 print('The tea is cool enough.')
```

I added a final line after the while loop to remind you that execution follows sequentially after a loop completes.

If you play computer and follow the path of execution, you could generate the following table. Remember, that each time you reach the end of the indented block after the `while` heading, execution returns to the `while` heading for another test:

Line	temperature	Comment
1	115	
2		115 > 112 is true, do loop
3		prints 115
4	114	115 - 1 is 114, loop back
2		114 > 112 is true, do loop
3		prints 114
4	113	114 - 1 is 113, loop back
2		113 > 112 is true, do loop
3		prints 113
4	112	113 - 1 is 112, loop back
2		112 > 112 is false, skip loop
6		prints that the tea is cool

Each time the end of the indented loop body is reached, execution returns to the `while` loop heading for another test. When the test is finally false, execution jumps past the indented body of the `while` loop to the next sequential statement.

A `while` loop generally follows the pattern of the successive modification loop introduced with `for`-each loops:

```
initialization
while continuationCondition :
    do main action to be repeated
    prepare variables for the next time through the loop
```

Test yourself: Following the code. Figure out what is printed. :

```
i = 4
while i < 9:
    print(i)
    i = i+2
```

Check yourself by running the example program `testWhile.py`.

Note: In Python, `while` is not used *quite* like in English. In English you could mean to stop *as soon as* the condition you want to test becomes false. In Python the test is *only* made when execution for the loop starts (or starts again), *not* in the middle of the loop.

Predict what will happen with this slight variation on the previous example, switching the order in the loop body. Follow it carefully, one step at a time.

```
1 i = 4 # variation on testWhile.py
2 while (i < 9):
3     i = i+2
4     print(i)
```

Check yourself by running the example program `testWhile2.py`.

The sequence order is important. The variable `i` is increased before it is printed, so the first number printed is 6. Another common error is to assume that 10 will *not* be printed, since 10 is *past* 9, but the test that may stop the loop is *not* made in the middle of the loop. Once the body of the loop is started, it continues to the end, even when `i` becomes 10.

Line	i	Comment
1	4	
2		4 < 9 is true, do loop
3	6	4+2=6
4		print 6
2		6 < 9 is true, do loop
3	8	6+2= 8
4		print 8
2		8 < 9 is true, do loop
3	10	8+2=10 <i>No test here</i>
4		print 10
2		10 < 9 is false, skip loop

Predict what happens in this related little program:

```
nums = list()
i = 4
while (i < 9):
    nums.append(i)
    i = i+2
print(nums)
```

Check yourself by running the example program `testWhile3.py`.

3.3.2 The Most General `range` Function

There is actually a much simpler way to generate the previous sequences like in `testWhile3.py`, using a further variation of the `range` function. Enter these lines separately in the *Shell*. As in the simpler applications of `range`, the values are only generated one at a time, as needed. To see the entire sequence at once, convert the sequence to a list before printing:

```
nums = range(4, 9, 2)
print(list(nums))
```

The third parameter for the `range` function is the step size. It is needed when the step size from one element to the next is not 1.

The most general syntax is

```
range( start , pastEnd , step )
```

The value of the second parameter is always *past* the final element of the list. Each element after the first in the list is *step* more than the previous one. Predict and try in the *Shell*:

```
list(range(4, 10, 2))
```

Actually the `range` function is even more sophisticated than indicated by the `while` loop above. The step size can be negative. Try in the *Shell*:

```
list(range(10, 0, -1))
```

Do you see how 0 is *past* the end of the list?

Try it: Make up a `range` function call to generate the list of temperatures printed in the tea example, 115, 114, 113. Test it in the *Shell*.

These ranges, like the simpler ranges that we used earlier, are most often used as the sequence in a `for` loop heading:

```
for i in range(10, 0, -1): # countdown...
    print(i)
print('Blastoff!')
```

3.3.3 Interactive while Loops

The earlier examples of while loops were chosen for their simplicity. Obviously they could have been rewritten with range function calls. Now let's try a more interesting example. Suppose you want to let a user enter a sequence of lines of text, and want to remember each line in a list. This could easily be done with a simple repeat loop *if you knew the number of lines to enter*. For example, in `readLines0.py`, the user is prompted for the exact number of lines to be entered:

```
lines = list()
n = int(input('How many lines do you want to enter? '))
for i in range(n):
    line = input('Next line: ')
    lines.append(line)

print('Your lines were:') # check now
for line in lines:
    print(line)
```

The user may want to enter a bunch of lines and not count them all ahead of time. This means the number of repetitions would not be known ahead of time. A while loop is appropriate here. There is still the question of how to test whether the user wants to continue. An obvious but verbose way to do this is to ask before every line if the user wants to continue, as shown below and in the example file `readLines1.py`. Read it and then run it:

```
lines = list()
testAnswer = input('Press y if you want to enter more lines: ')
while testAnswer == 'y':
    line = input('Next line: ')
    lines.append(line)
    testAnswer = input('Press y if you want to enter more lines: ')

print('Your lines were:')
for line in lines:
    print(line)
```

See the *two* statements setting `testAnswer`: one before the while loop and one at the bottom of the loop body.

Note: The data must be initialized *before* the loop, in order for the first test of the while condition to work. Also the test must work when you loop back from the end of the loop body. This means the data for the test must also be set up a second time, *in* the loop body (commonly as the action in the last line of the loop). It is easy to forget the second time!

The `readLines1.py` code works, but it may be more annoying than counting ahead! Two lines must be entered for every one you actually want! A practical alternative is to use a *sentinel*: a piece of data that would *not* make sense in the regular sequence, and which is used to indicate the *end* of the input. You could agree to use the line `DONE!` Even simpler: if you assume all the real lines of data will actually have some text on them, use an *empty* line as a sentinel. (If you think about it, the Python Shell uses this approach when you enter a statement with an indented body.) This way you only need to enter one extra (very simple) line, no matter how many lines of real data you have.

What should the while condition be now? Since the sentinel is an empty line, you might think `line == ''`, but that is the *termination* condition, not the *continuation* condition: You need the *opposite* condition. To negate a condition in Python, you may use `not`, like in English,

```
not line == ''
```

Of course in this situation there is a shorter way,

```
line != ''
```

Run the example program `readLines2.py`, shown below:

```
lines = list()
print('Enter lines of text.')
print('Enter an empty line to quit.')

line = input('Next line: ') # initialize before the loop
while line != '':          # while NOT the termination condition
    lines.append(line)
    line = input('Next line: ') # !! reset value at end of loop!

print('Your lines were:')
for line in lines:
    print(line)
```

Again the data for the test in the `while` loop heading must be initialized before the first time the `while` statement is executed and the test data must *also* be made ready inside the loop for the test after the body has executed. Hence you see the statements setting the variable `line` both before the loop and at the end of the loop body. It is easy to forget the second place inside the loop!

After reading the rest of this paragraph, comment the last line of the loop out, and run it again: It will never stop! The variable `line` will forever have the initial value you gave it! You actually can stop the program by entering `Ctrl-C`. That means hold the `Ctrl` key and press `c`.

Note: As you finish coding a `while` loop, it is good practice to always double-check: Did I make a change to the variables, *inside* the loop, that will eventually make the loop condition `False`?

The earliest `while` loop examples had numerical tests and the code to get ready for the next loop just incremented a numerical variable by a fixed amount. Those were simple examples but `while` loops are much more general! In the interactive loop we have seen a continuation condition with a string test, and getting ready for the next time through the loop involves input from the user.

Some of the exercises that follow involve interactive `while` loops. Others were delayed until here just because they have a wider variety of continuation condition tests and ways to prepare for the next time through the loop. What is *consistent* is the general steps to think of and questions to ask yourself. They keep on applying! Keep these in mind!

- the need to see whether there *is* a kind of repetition, even without a fixed collection of values to work through
- to think from the specific situation and figure out the continuation condition that makes sense for your loop
- to think what specific processing or results you want each time through the loop, using the *same* code
- to figure out what supporting code you need to make you ready for the next time through the loop: how to make the *same* results code have *new* data values to process each time through, and eventually reach a stopping point.

Detecting the need for `while` statements: Like with planning programs needing “`for`” or `if` statements, you want to be able to translate English descriptions of problems that would naturally include `while` statements. What are some words or phrases or ideas that suggest the use of these statements? Think of your own and then compare to a few I gave: ⁷

⁷ “while ____”, “do ____ while”, “repeat while”, “repeat until”, “as long as ____ do”, “keep doing ____ as long as”

Interactive Sum Exercise

Write a program `sumAll.py` that prompts the user to enter numbers, one per line, ending with a line containing only 0, and keep a running sum of the numbers. Only print out the sum after all the numbers are entered (at least in your *final* version). Do *not* create a list! Each time you read in a number, you can immediately use it for your sum, and then be done with the number just entered.

Safe Number Input Exercise

* There is an issue with reading in numbers with the input statement. If you make a typo and enter something that cannot be converted from a string to the right kind of number, a naive program will bomb. This is avoidable if you test the string and repeat if the string is illegal. In this exercise write safe utility function replacements for the input function that work to read in a whole number, an integer or a decimal number.

All parts refer to the previous *Is Number String Exercise* (page 138). Part a. refers to the introduction in the previous exercise. Parts b. and c. refer to functions in the solution, `isNumberStr.py`, of the previous exercise. Make sure you look back at these first.

Save the example `safeNumberInputStub.py` as `safeNumberInput.py`, and complete it. It contains headings and documentation strings for the functions in each part of this exercise.

1. This part considers the simplest case, where you are trying to enter a whole number. Complete the definition of the function `safeWholeNumber`.
2. Complete the function `safeInt`. This easily parallels part a. if you copy in and use the function (not method) `isIntegerStr`.
3. Complete the function `safeDecimal`. This easily parallels part b. if you copy in and use the function `isDecimalStr`.

Savings Exercise

The idea here is to see how many years it will take a bank account to grow to at least a given value, assuming a fixed annual interest. Write a program `savings.py`. Prompt the user for three numbers: an initial balance, the annual percentage for interest as a decimal, like .04 for 4%, and the final balance desired.

All the monetary amounts that you print should be rounded to *exactly* two decimal places. Start by printing the initial balance this way. For example, if the initial balance was entered as 123.5, it should be reprinted by your program as 123.50. Also print the balance each year until the desired amount is reached or passed. The first balance at or past the target should be the last one printed.

The math: The amount next year is the amount now times (1 + interest fraction), so if I have \$500 now and the interest rate is .04, I have $500 \times (1.04) = 520$ after one year and after two years I have, $520 \times (1.04) = 540.80$...

For example, if I respond to the prompts, and enter into the program a \$500 starting balance, .04 interest rate and a target of \$550, the program prints:

```
500.00
520.00
540.80
562.43
```

Strange Sequence Exercise

* Recall *Strange Function Exercise* (page 125) and its `jumpFunc.py` which contains the function `jump`: For any integer `n`, `jump(n)` is $n/2$ if `n` is even, and $3*n+1$ if `n` is odd.

You can start with one number, say $n = 3$, and *keep* applying the jump function to the *last* number given, and see how the numbers jump around!

```
jump(3) = 3*3+1 = 10; jump(10) = 10//2 = 5;
jump(5) = 3*5+1 = 16; jump(16) = 16//2 = 8;
jump(8) = 8//2 = 4; jump(4) = 4//2 = 2;
jump(2) = 2//2 = 1
```

This process of repeatedly applying the same function to the most recent result is called function *iteration*. In this case you see that iterating the jump function, starting from $n=3$, eventually reaches the value 1.

It is an open research question whether iterating the jump function from an integer n will eventually reach 1, for *every* starting integer n greater than 1. Researchers have only found *examples* of n where it is true. Still, no general argument has been made to apply to the *infinite* number of possible starting integers.

In this exercise you iterate the jump function for specific starting values n , until the result is 1.

1. Save example `jumpSeqStub.py` as `jumpSeq.py` and complete the missing function bodies. If you coded the function `jump` before in `jumpFunc.py`, you can copy it. You can complete either `printJumps` or `listJumps` first, and test before completing the other. Hint ⁸
2. After you have finished and saved `jumpSeq.py` copy it and save the file as `jumpSeqLengths.py`.

First modify the main method so it prompts the user for a value of n , and then prints just the length of the iterative sequence from `listJumps(n)`. Hint ⁹

Then elaborate the program so it prompts the user for two integers: a lowest starting value of n and a highest starting value of n . For all integers n in the range from the lowest start through the highest start, including the highest, print a sentence giving the starting value of n and the length of the list from `listJumps(n)`. An example run:

```
Enter lowest start: 3
Enter highest start: 6
Starting from 3, jump sequence length 8.
Starting from 4, jump sequence length 3.
Starting from 5, jump sequence length 6.
Starting from 6, jump sequence length 9.
```

3.3.4 Graphical Applications

Another place where a `while` loop could be useful is in interactive graphics. Suppose you want the user to be able to create a Polygon by clicking on vertices they choose interactively, but you do not want them to have to count the number of vertices ahead of time. A `while` loop is suggested for such a repetitive process. As with entering lines of text interactively, there is the question of how to indicate that you are done (or how to indicate to continue). If you make only a certain region be allowed for the Polygon, then the sentinel can be a mouse click outside the region. The earlier interactive color choice example already has a method to check if a mouse click is inside a Rectangle, so that method can be copied and reused.

Creating a polygon is a unified activity with a clear result, so let's define a function. It involves a boundary rectangle and mouse clicks in a `GraphWin`, and may as well return the Polygon constructed. *Read* the following start:

```
def polyHere(rect, win):
    ''' Draw a polygon interactively in Rectangle rect, in GraphWin win.
        Collect mouse clicks inside rect into the vertices of a Polygon,
```

⁸ You will need a loop. You can print/append almost all the numbers in the loop. You are likely to omit one number with just this code, but after looking at what you produce, it is easy to separately include the remaining number. There are several ways to do this.

⁹ Recall the built-in `len` function! It applies to lists.

```
and always draw the Polygon created so far.  
When a click goes outside rect, stop and return the final polygon.  
The Polygon ends up drawn. The method draws and undraws rect.  
'''
```

It is useful to start by thinking of the objects needed, and give them names.

- A Polygon is needed. Call it `poly`.
- A list of vertices is needed. Call it `vertices`. I need to append to this list. It must be initialized first.
- The latest mouse click point is needed. Call it `pt`.

Certainly the overall process will be repetitious, choosing point after point. Still it may not be at all clear how to make an effective Python loop. In challenging situations like this it is often useful to imagine a concrete situation with a limited number of steps, so each step can be written in sequence without worrying about a loop.

For instance to get up to a triangle (3 vertices in our list and a fourth mouse click for the sentinel), you might imagine the following sequence, undrawing each old polygon before the next is displayed with the latest mouse click included:

```
rect.setOutline('red')  
rect.draw(win)  
vertices = list()  
pt = win.getMouse()  
vertices.append(pt)  
poly = Polygon(vertices)  
poly.draw(win)           # with one point  
pt = win.getMouse()  
poly.undraw()             # missing latest point  
vertices.append(pt)  
poly = Polygon(vertices)  
poly.draw(win)           # with two points  
pt = win.getMouse()  
poly.undraw()             # missing latest point  
vertices.append(pt)  
poly = Polygon(vertices)  
poly.draw(win)           # with three points  
pt = win.getMouse()      # assume outside the region  
  
rect.undraw()  
return poly
```

There is a fine point here that I missed the first time. The vertices of an existing Polygon do not get mutated in this system. A new Polygon gets created each time with the new vertex list. The old Polygon does not go away automatically, and extraneous lines appear in the picture if the old polygon is not explicitly undrawn each time before a new version is redrawn with an extra vertex. The last Polygon you draw should be visible at the end, so in the example above where I was assuming the third click was the last for the triangle, I did not undraw the Polygon.

The timing for each `undraw` needs to be after the next mouse click and presumably before the revised Polygon is created, so it could be before or after the line `vertices.append(pt)`. I arbitrarily chose for it to go before the vertices list is changed. The rest of the order of the lines is pretty well fixed by the basic logic.

If you think of the repetitions through a large number of loops, the process is essentially circular (as suggested by the word ‘loop’). The body of a loop in Python, however, is written as a *linear* sequence: one with a first line and a last line, a beginning and an end. We can cut a circular loop *anywhere* to get a piece with a beginning and an end. In practice, the place you cut the loop for Python has one main constraint: The processing in Python from the end of one time through the loop to the beginning of the next loop is separated by the test of the condition in the heading. The *continuation condition in the while heading must make sense where you cut the loop*.

It can help to look at a concrete example sequence, like the steps listed above for creating a triangle, only now assuming

we do not know how many vertices will be chosen. The continuation condition is for `pt` to be in the rectangle, so using the previously written function `isInside`, the loop heading will be

```
while isInside(pt, rect):
```

With this condition in mind, look for where to split to loop. It needs to be after a new `pt` is clicked (so it can be tested) and before the next Polygon is created (so it does not include the sentinel point by mistake). In particular, with the sequence above, look and see that the split could go before or after the `poly.undraw()` line. *Exercise Moving Undraw* (page 156) considers the case where the split goes before this line. I will proceed with the choice of splitting into a Python loop *after* the `undraw` line. This makes the loop be

```
while isInside(pt, rect):
    vertices.append(pt)
    poly = Polygon(vertices)
    poly.draw(win)
    pt = win.getMouse()
    poly.undraw()
```

If you follow the total sequence of required steps above for making the concrete triangle, you see that this *full* sequence for the loop is only repeated twice. The last time there is no `poly.undraw()` step. I could redo the loop moving the `undraw` line to the top, which caused different issues (*Exercise Moving Undraw* (page 156) below). Instead *think* how to make it work at the end of the final time through the loop....

There are several possible approaches. You want the `undraw` line every time except for the last time. Hence it is a statement you want sometimes and not others. That suggests an `if` statement. The times you want the `undraw` are when the loop will repeat again. This is the same as the continuation condition for the loop, and you have just read the next value for `pt`! You could just add a condition in front of the last line of the loop:

```
if isInside(pt, rect):
    poly.undraw()
```

I find this option unaesthetic: it means duplicating the continuation test twice in every loop.

Instead of *avoiding* the `undraw` as you exit the loop, another option in this case is to *undo* it: just **redraw** the polygon one final time *beyond* the loop. This only needs to be done once, not repeatedly in the loop. Then the repetitious lines collapse neatly into the loop.

If you look at the overall concrete sequence for the triangle, not all the lines are in the loop. You must carefully include the lines both that come before the loop and those that come after the loop. Make sure these lines are not put *in* the loop, but before or after, as indicated by the concrete sequence in the example. In the end the entire function is:

```
def polyHere(rect, win):
    ''' Draw a polygon interactively in Rectangle rect, in GraphWin win.
    Collect mouse clicks inside rect into the vertices of a Polygon,
    and always draw the Polygon created so far.
    When a click goes outside rect, stop and return the final polygon.
    The Polygon ends up drawn. The method draws and undraws rect.
    '''
    rect.setOutline("red")
    rect.draw(win)
    vertices = list()
    pt = win.getMouse()
    while isInside(pt, rect):
        vertices.append(pt)
        poly = Polygon(vertices)
        poly.draw(win)
        pt = win.getMouse()
        poly.undraw()
    poly.draw(win)
```

```
rect.undraw()  
return poly
```

Make sure you understand: Follow this code through, imagining three mouse clicks inside `rect` and then one click outside of `rect`. Compare the steps to the ones in the concrete sequence written out above and see that the match (aside from the last canceling `undraw` and `draw` of `poly`).

This function is illustrated in the example program `makePoly.py`. Other than standard graphics example code, the main program contains:

```
rect1 = Rectangle(Point(5, 55), Point(200, 120))  
poly1 = polyHere(rect1, win)  
poly1.setFill('green')  
rect2 = Rectangle(Point(210, 50), Point(350, 350))  
poly2 = polyHere(rect2, win)  
poly2.setOutline('orange')
```

As you can see, the returned polygons are used to make color changes, just as an illustration.

In earlier animation examples a `while` loop would also have been useful. Rather than continuing the animation a fixed number of times, it would be nice for the user to indicate by a mouse click when she has watched long enough. Thus far the only way to use the mouse has been with `getMouse()`. This is not going to work in an animation, because the computer stops and *waits* for a click with `getMouse()`, whereas the animation should *continue until* the click.

In full-fledged graphical systems that respond to events, this is no problem. Zelle's graphics is built on top of a capable event-driven system, and in fact, all mouse clicks are registered, even outside calls to `getMouse()`.

As an example, run example program `randomCirclesWhile.py`. Be sure to follow the prompt saying to click to start *and* to end.

Aside from the prompts, the difference from the previous `randomCircles.py` program is the replacement of the original simple repeat loop heading

```
for i in range(75):
```

by the following initialization and while loop heading:

```
while win.checkMouse() == None:           #NEW*
```

The graphics module remembers the last mouse click, whether or not it occurred during a call to `getMouse()`. A way to check if the mouse has been clicked since the last call to `getMouse()` is `checkMouse()`. It does not *wait* for the mouse as in `getMouse()`. Instead it returns the *remembered* mouse click - the most recent mouse click in the *past*, unless there has been no mouse click since the last call to `getMouse()` or `checkMouse()`. In that case `checkMouse()` returns `None` (the special object used to indicate the lack of a regular object).

The `checkMouse` method allows for a loop that does not stop while waiting for a mouse click, but goes on until the heading test detects that the mouse *was* clicked.

A similar elaboration can be made for the other examples of animation, like `bounce1.py`. In `bounceWhile.py` I modified `bounce1.py` to have a while loop in place of the for-loop repeating 600 times. Run it. The only slight added modification here was that `win` was not originally a parameter to `bounceInBox`, so I included it. Look at the source code for `bounceWhile.py`, with the few changes marked NEW.

In `bounce2.py` I also made a more interesting change to the initialization, so the initial direction and speed of the mouse are determined graphically by the user, with a mouse click. Try example program `bounce2.py`.

The program includes a new utility function to help determine the initial `(dx, dy)` for the animation. This is done by calculating the move necessary to go from one point (where the ball is in this program) to another (specified by a user's mouse click in this program). :

```
def getShift(point1, point2): # NEW utility function
    '''Returns a tuple (dx, dy) which is the shift from point1 to point2.'''
    dx = point2.getX() - point1.getX()
    dy = point2.getY() - point1.getY()
    return (dx, dy)
```

Since the function calculates both a change in x and y, it returns a tuple.

A straightforward interactive method, `getUserShift`, is wrapped around this function to get the user's choice, which ultimately returns the same tuple:

```
def getUserShift(point, prompt, win): #NEW direction selection
    '''Return the change in position from the point to a mouse click in win.
    First display the prompt string under point.'''

    text = Text(Point(point.getX(), 60), prompt)
    text.draw(win)
    userPt = win.getMouse()
    text.undraw()
    return getShift(point, userPt)
```

In the new version of the main driver, `bounceBall`, excerpted below, this interactive setting of (dx, dy) is used. Note the multiple assignment statement to both dx and dy, set from the tuple returned from `getUserShift`. This shift would generally be much too much for a single animation step, so the actual values passed to `bounceBall` are scaled way down by a factor `scale`.

```
center = Point(win.getWidth()/2, win.getHeight()/2) #NEW central starting point
ball = makeDisk(center, radius, win)

#NEW interactive direction and speed setting
prompt = ''
Click to indicate the direction and
speed of the ball: The further you
click from the ball, the faster it starts.'''
(dx, dy) = getUserShift(center, prompt, win)
scale = 0.01 # to reduce the size of animation steps
bounceInBox(ball, dx*scale, dy*scale, xLow, xHigh, yLow, yHigh, win)
```

The `bounceInBox` method has the same change to the loop as in the `randomCircles.py` example. The method then requires the `GraphWin`, `win`, as a further parameter, since `checkMouse` is a `GraphWin` method.

You can look in Idle at the full source code for `bounce2.py` if you like. The changes from `bounce1.py` are all marked with a comment starting with `#NEW`, and all the major changes have been described above.

In the examples so far of the use of `checkMouse()`, we have only used the fact that a point was clicked, not *which* point. The next example version, `bounce3.py`, does use the location of mouse clicks that are read with `checkMouse()` to change the direction and speed of the ball. Try it.

This version only slightly modifies the central animation function, `bounceInBox`, but wraps it in another looping function that makes the direction and speed of the ball change on *each* mouse click. Hence the mouse clicks detected in `bounceInBox` need to be remembered and then returned after the main animation loop finishes. That requires a name, `pt`, to be given to the last mouse click, so it can be remembered. This means modifying the main animation loop to initialize the variable `pt` before the loop and reset it at the end of the loop, much as in the use of `getMouse()` for the interactive polygon creation. That explains the first three NEW lines and the last two NEW lines in the revised `bounceInBox`:

```
def bounceInBox(shape, dx, dy, xLow, xHigh, yLow, yHigh, win):
    ''' Animate a shape moving in jumps (dx, dy), bouncing when
```

```

    its center reaches the low and high x and y coordinates.
    The animation stops when the mouse is clicked, and the
    last mouse click is returned.'''

    delay = .001
    pt = None #NEW
    while pt == None: #NEW
        shape.move(dx, dy)
        center = shape.getCenter()
        x = center.getX()
        y = center.getY()
        isInside = True #NEW
        if x < xLow or x > xHigh:
            dx = -dx
            isInside = False #NEW
        if y < yLow or y > yHigh:
            dy = -dy
            isInside = False #NEW
        time.sleep(delay)
        if isInside: # NEW don't mess with dx, dy when outside
            pt = win.checkMouse() #NEW
    return pt #NEW

def moveInBox(shape, stopHeight, xLow, xHigh, yLow, yHigh, win): #NEW
    '''Shape bounces in win so its center stays within the low and high
    x and y coordinates, and changes direction based on mouse clicks,
    terminating when there is a click above stopHeight.'''

    scale = 0.01
    pt = shape.getCenter() # starts motionless
    while pt.getY() < stopHeight:
        (dx, dy) = getShift(shape.getCenter(), pt)
        pt = bounceInBox(shape, dx*scale, dy*scale,
                        xLow, xHigh, yLow, yHigh, win)

def makeDisk(center, radius, win):
    '''Return a red disk that is drawn in win with given center and radius.'''
    disk = Circle(center, radius)
    disk.setOutline("red")
    disk.setFill("red")
    disk.draw(win)
    return disk

def getShift(point1, point2):
    '''Returns a tuple (dx, dy) which is the shift from point1 to point2.'''
    dx = point2.getX() - point1.getX()
    dy = point2.getY() - point1.getY()
    return (dx, dy)

def bounceBall():
    '''Make a ball bounce around the screen, and react to mouse clicks.'''

    win = GraphWin('Ball Bounce 3', 290, 290)
    win.yUp()

    #NEW to mark and label the area where a click stops the program
    lineHeight = win.getHeight() - 40
    textHeight = win.getHeight() - 20

```

```

Line(Point(0, lineHeight), Point(win.getWidth(), lineHeight)).draw(win)
prompt = 'Click above the line to stop\nor below to move toward the click.'
Text(Point(win.getWidth()/2, textHeight), prompt).draw(win)

radius = 10
xLow = radius # center is separated from the wall by the radius at a bounce
xHigh = win.getWidth() - radius
yLow = radius
yHigh = lineHeight - radius #NEW lower top to bouncing limits

center = Point(win.getWidth()/2, lineHeight/2)
ball = makeDisk(center, radius, win)

moveInBox(ball, lineHeight, xLow, xHigh, yLow, yHigh, win) #NEW

win.close()

bounceBall()

```

I initially made only the changes discussed so far (not the ones involving the new variable `isInside`). The variable `isInside` was in response to a bug that I will discuss after introducing the simple function that wraps around `bounceInBox`:

Each time the mouse is clicked, the ball is to switch direction and move toward the last click, until the stopping condition occurs, when there is a click above the stop line. This is clearly repetitive and needs a while loop. The condition is simply to test the y coordinate of the mouse click against the the height of the stop line. The body of the loop is very short, since we already have the utility function `getShift`, to figure out (dx, dy) values.

```

def moveInBox(shape, stopHeight, xLow, xHigh, yLow, yHigh, win): #NEW
    '''Shape bounces in win so its center stays within the low and high
    x and y coordinates, and changes direction based on mouse clicks,
    terminating when there is a click above stopHeight.'''

    scale = 0.01
    pt = shape.getCenter() # starts motionless
    while pt.getY() < stopHeight:
        (dx, dy) = getShift(shape.getCenter(), pt)
        pt = bounceInBox(shape, dx*scale, dy*scale,
                        xLow, xHigh, yLow, yHigh, win)

```

The variable `pt` for the last mouse click needed to be initialized some way. I chose to make the value be the same as the initial position of the ball, so both `dx` and `dy` are initially 0, and the ball does not start in motion. (Alternatives are in [Random Start Exercise](#) (page 157) below.)

I occasionally detected a bug when using the program. The ball would get stuck just outside the boundary and stay there. The fact that it was slightly beyond the boundary was a clue: For simplicity I had cheated, and allowed the ball to go just one animation step beyond the intended boundary. With the speed and small step size this works visually. The original code was *sure* to make an opposite jump back inside at the next step.

After some thought, I noticed that the initial version of the `bounce3.py` code for `bounceInBox` broke that assumption. When the ball was where a bounce-back is required, a mouse click could change (dx, dy) and mess up the bounce. The idea for a fix is not to let the user change the direction in the moment when the ball needs to bounce back.

Neither of the original boundary-checking `if` statements, by *itself*, always determines if the ball is in the region where it needs to reverse direction. I dealt with this situation by introducing a *Boolean variable* `isInside`. It is initially set as `True`, and then either of the `if` statements can correct it to `False`. Then, at the end of the loop, `isInside` is used to make sure the ball is safely inside the proper region when there is a check for a new mouse click and a possible user adjustment to (dx, dy).


Exercise Moving Undraw

** As discussed above at *Where to split the loop* (page 150), the basic loop logic works whether the `poly.undraw()` call is at the beginning or end of the loop. Write a variation `makePoly2.py` that makes the code work the other way, with the `poly.undraw()` at the beginning of the loop. Do not change or move any other statement in the loop. The new place to cut the loop *does* affect the code before and after the loop. In particular, the extra statement drawing `poly` is not needed after the loop is completed. Make other changes to the *surrounding* code to make this work. Hints: ¹⁰

Make Path Exercise

** Write a program that is outwardly very similar to `makePoly.py`, and call it `makePath.py`, with a function `pathHere`. The only outward difference between `polyHere` and `pathHere` is that while the first creates a closed polygon, and returns it, and the new one creates a polygonal path, without the final point being automatically connected to the first point, and a *list* of the lines in the path is returned. Internally the functions are quite different. The change simplifies some things: no need to undraw anything in the main loop - just draw the latest segment each time going from the previous point to the just clicked point. There are complications however: You do need deal specially with the first point. It has no previous point to connect to. I suggest you handle this *before* the main loop: If the point is inside the rectangle, draw the point so it is a visible guide for the next point. Before returning, undraw this initial point. (The place on the screen will still be visible if an initial segment is drawn. If no more points were added, the screen is left blank, which is the way it should be, and an empty list of lines should be returned.) You also need to remember the previous point each time through the main loop. I suggest you think individually about what should happen if you stop the drawing when the first, second or third point is outside the rectangle. Also test each of those cases after the program is written.

In your main program, call the `makePath` function two times. Use the list of lines returned to loop through and change the color of all the lines in one path and the width of the lines in the other path. A portion of a sample image from this program is shown below.



¹⁰ The basic issue is similar to the old version: the undraw is not always needed – at the beginning in this case. In this place it is not needed the *first* time through the loop. The two basic approaches considered for the previous version still work here: make an extra compensating action outside the loop or break into cases inside the loop. Further hint: It is legal to draw a polygon with an empty vertex list - nothing appears on the screen.

Random Start Exercise

* (Optional) I chose to have the ball start motionless, by making the initial value of `pt` (which determines the initial (dx, dy)) be the center of the ball. Write a variation `startRandom.py` so `pt` is randomly chosen. Also make the initial location of the ball be random. You can copy the function `getRandomPoint` from `bounce1.py`.

Mad Lib While Exercise

** Write a program `madlib4.py` that modifies the `getKeys` method of `madlib2.py` to use a `while` loop. (This is not an animation program, but this section is where you have had the most experience with `while` loops!)

Hints: This is actually the most natural approach. I avoided `while` loops initially, when only `for` loops had been discussed. In the original approach, however, it is redundant to find every instance of `'{'` to *count* the number of repetitions and then *find* them all again when extracting the cue keys. A more natural way to control the loop is a `while` loop stopping when there are no further occurrences of `'{'` to find. This involves some further adjustments. You must cut the loop in a different place (to end after searching for `'{'`). As discussed before, cutting a loop in a different place may require changes before and after the loop, too.

Find Hole Game Exercise

** Write a graphical game program, `findHole.py`, “Find the Hole”. The program should use a random number generator to determine a circular “hole”, selecting a point and a perhaps the radius around that point. These determine the target and are not revealed to the player initially. The user is then prompted to click around on the screen to “find the hidden hole”. You should show the points the user has tried. Once the user selects a point that is within the chosen radius of the mystery point, the mystery circle should appear. There should be a message announcing how many steps it took, and the game should end.

Hint: you have already seen the code to determine the displacement (dx, dy) between two points: use the `getShift` function in `bounce2.py`. Once you have the displacement (dx, dy) between the hidden center and the latest mouse click, the distance between the points is $(dx*dx + dy*dy)**0.5$, using the Pythagorean Theorem of geometry. If this distance is no more than the radius that you have chosen for the mystery circle, then the user has found the circle! You can use `getShift` as written, or modify it into a function `getDistance` that directly returns the distance between two points.

Many elaborations on this game are possible! Have fun with it!

3.3.5 Fancier Animation Loop Logic (Optional)

The final variation is the example program `bounce4.py`, which has the same outward behavior as `bounce3.py`, but it illustrates a different internal design decision. The `bounce3.py` version has two levels of `while` loop in two methods, `moveInBox` for mouse clicks and `bounceInBox` for bouncing. The `bounce4.py` version puts all the code for changing direction inside the main animation loop in the old outer function, `moveInBox`. There are now three reasons to adjust (dx, dy) : bouncing off the sides, bouncing off the top or bottom, or a mouse click. That is a simplification and unification of the logic in one sense. The complication now is that the logic for determining when to quit is buried deep inside the `if-else` logic, not at the heading of the loop. The test for mouse clicks is inside the `while` loop and further inside another `if` statement. The test of the mouse click may merely lead to a change in (dx, dy) , or is a signal to quit. Here is the revised code, with a discussion afterward of the return statement:

```
def moveInBox(shape, stopHeight, xLow, xHigh, yLow, yHigh, win):
    ''' Animate a shape moving toward any mouse click below stopHeight and
        bouncing when its center reaches the low or high x or y coordinates.
        The animation stops when the mouse is clicked at stopHeight or above.'''

    scale = 0.01
```

```
delay = .001
dx = 0                                     #NEW dx and dy are no longer parameters
dy = 0                                     #NEW
while True:                                #NEW exit loop at return statement
    center = shape.getCenter()
    x = center.getX()
    y = center.getY()
    isInside = True
    if x < xLow or x > xHigh:
        dx = -dx
        isInside = False
    if y < yLow or y > yHigh:
        dy = -dy
        isInside = False
    if isInside:
        pt = win.checkMouse()
        if pt != None:                    #NEW dealing with mouse click now here
            if pt.getY() < stopHeight: # switch direction
                (dx, dy) = getShift(center, pt)
                (dx, dy) = (dx*scale, dy*scale)
            else:                          #NEW exit from depths of the loop
                return                    #NEW
    shape.move(dx, dy)
    time.sleep(delay)
```

Recall that a `return` statement immediately terminates function execution. In this case the function returns no value, but a bare `return` is legal to force the exit. Since the testing is not done in the normal `while` condition, the `while` condition is set as permanently `True`. This is not the most common `while` loop pattern! It obscures the loop exit. The choice between the approach of `bounce3.py` and `bounce4.py` is a matter of taste in the given situation.

3.4 Arbitrary Types Treated As Boolean

The following section would merely be an advanced topic, except for the fact that many common mistakes have their meaning changed and obscured by the Boolean syntax discussed.

You have seen how many kinds of objects can be converted to other types. Any object can be converted to Boolean (type `bool`). Read the examples shown in this Shell sequence:

```
>>> bool(2)
True
>>> bool(-3.1)
True
>>> bool(0)
False
>>> bool(0.0)
False
>>> bool(None)
False
>>> bool('')
False
>>> bool('0')
True
>>> bool('False')
True
>>> bool([])
False
```

```
>>> bool([0])
True
```

The result looks pretty strange, but there is a fairly short general explanation: Almost everything is converted to `True`. The only values among built-in types that are interpreted as `False` are

- The Boolean value `False` itself
- Any numerical value equal to 0 (0, 0.0 but not 2 or -3.1)
- The special value `None`
- Any empty sequence or collection, including the empty string ('', but not '0' or 'hi' or 'False') and the including empty list([], but not [1, 2, 3] or [0])

A possibly useful consequence occurs in the fairly common situation where something needs to be done with a list only if it is nonempty. In this case the explicit syntax:

```
if len(aList) > 0:
    doSomethingWith(aList)
```

can be written with the more succinct Pythonic idiom

```
if aList:
    doSomethingWith(aList)
```

This automatic conversion can also lead to extra trouble! Suppose you prompt the user for the answer to a yes/no question, and want to accept 'y' or 'yes' as indicating `True`. You might write the following *incorrect* code. Read it:

```
ans = input('Is this OK? ')
if ans == 'y' or 'yes':
    print('Yes, it is OK')
```

The problem is that there are two binary operations here: `==`, `or`. Comparison operations all have higher precedence than the logical operations `or`, `and`, and `not`. The `if` condition above can be rewritten equivalently with parentheses. Read and consider:

```
(ans == 'y') or 'yes'
```

Other programming languages have the advantage of stopping with an error at such an expression, since a string like 'yes' is not of type `bool`. Python, however, accepts the expression, and treats 'yes' as `True`. To test, run the example program `boolConfusion.py`, shown below:

```
ans = 'y'
if ans == 'y' or 'yes':
    print('y is OK')

ans = 'no'
if ans == 'y' or 'yes':
    print('no is OK!???)
```

Python detects no error. The `or` expression is treated as `True`, since 'yes' is a non-empty sequence, interpreted as `True`.

The intention of someone writing

```
if ans == 'y' or 'yes':
```

presumably was that the condition meant something like

```
(ans == 'y') or (ans == 'yes')
```

This version also translates directly to other languages. Another correct Pythonic alternative that groups the alternate values together is

```
ans in ['y', 'yes']
```

which reads pretty much like English.

Be careful to use a correct expression when you want to specify a condition like this.

Things get even stranger! Enter these conditions themselves, one at a time, directly into the *Shell*:

```
'y' == 'y' or 'yes'
'no' == 'y' or 'yes'
'y' == 'y' and 'yes'
'no' == 'y' and 'yes'
'no' or 'yes'
'no' and 'yes'
```

The meaning of (a or b) and of (a and b) are exactly as discussed so far *if* each of the operands a and b are *actually* Boolean, but more elaborate definitions are needed if an operand is not Boolean:

```
val = a or b
```

means

```
if bool(a):
    val = a
else:
    val = b
```

and in a similar vein:

```
val = a and b
```

means

```
if bool(a):
    val = b
else:
    val = a
```

This strange syntax was included in Python to allow code like in the following example program orNotBoolean.py. *Read* and test if you like:

```
defaultColor = 'red'
userColor = input('Enter a color, or just press Enter for the default: ')
color = userColor or defaultColor
print('The color is', color)
```

which sets color to the value of defaultColor if the user enters an empty string.

Again, this may be useful to experienced programmers, bhe syntax can certainly cause difficult bugs, particularly for beginners!

The not operator always produces a result of type bool.

3.5 Further Topics to Consider

Chapter 4 gives an application of Python to the web. It does not introduce new language features. We have come to end of the new language features in this tutorial, but there are certainly more basic topics to learn about programming and Python in particular, if you continue in other places:

1. Creating your own kinds of objects (writing classes)
2. Inheritance: Building new classes derived from existing classes
3. Python list indexing and slicing, both to read and change parts of lists
4. Other syntax used with loops: `break`, `continue`, and `else`
5. Exception handling
6. Python's variable length parameter lists, and other options in parameter lists
7. List comprehensions: a concise, readable, fast Pythonic way to make new lists from old ones
8. Event handling in graphical programming
9. Listing, moving and deleting stored files; creating folders
10. Recursion (not special to Python): a powerful programming technique where functions call themselves

Beyond these language features, Python has a vast collection of useful modules. For example, I wrote a real-world program, `sakaihw.py`, that I have in regular use for processing large numbers of files submitted to Sakai in homework submissions. It uses string methods and slicing and both kinds of loops, as well as illustrating some useful components in modules `sys`, `os`, and `os.path`, for accessing command line parameters, listing file directories, creating folders, and moving and renaming files.

3.6 Summary

1. Comparison operators produce a Boolean result (type `bool`, either `True` or `False`): [*More Conditional Expressions* (page 123)]

Meaning	Math Symbol	Python Symbols
Less than	$<$	<code><</code>
Greater than	$>$	<code>></code>
Less than or equal	\leq	<code><=</code>
Greater than or equal	\geq	<code>>=</code>
Equals	$=$	<code>==</code>
Not equal	\neq	<code>!=</code>

Comparisons may be chained as in `a < b <= c < d != e`. [*Multiple Tests and if-elif Statements* (page 125)]

2. The `in` operator: [*Arbitrary Types Treated As Boolean* (page 158)]

value `in` *sequence*

is `True` if *value* is one of the elements in the *sequence*.

3. Operators on Boolean expressions [*Compound Boolean Expressions* (page 133)]

(a) *condition1* and *condition2*

`True` only if both conditions are `True`

(b) *condition1* or *condition2*

`True` only if at least one condition is `True`

(c) not *condition*

`True` only when *condition* is `False`

This description is sufficient if the result is used as a Boolean value (in an `if` or `while` condition). See [*Arbitrary Types Treated As Boolean* (page 158)] for the advanced use when operands are not explicitly Boolean, and the result is not going to be interpreted as Boolean.

4. `if` Statements

- (a) Simple `if` statement [*Simple if Statements* (page 121)]

```
if condition :  
    indentedStatementBlockForTrueCondition
```

If the condition is `True`, then do the indented statement block. If the condition is not `True`, then skip it.

- (b) `if-else` statement [*if-else Statements* (page 122)]

```
if condition :  
    indentedStatementBlockForTrueCondition  
else:  
    indentedStatementBlockForFalseCondition
```

If the condition is `True`, then do the first indented block only. If the condition is not `True`, then skip the first indented block and do the one after the `else` :

- (c) The most general syntax for an `if` statement, `if-elif-else` [*Multiple Tests and if-elif Statements* (page 125)]

```
if condition1 :  
    indentedStatementBlockForTrueCondition1  
elif condition2 :  
    indentedStatementBlockForFirstTrueCondition2  
elif condition3 :  
    indentedStatementBlockForFirstTrueCondition3  
elif condition4 :  
    indentedStatementBlockForFirstTrueCondition4  
else:  
    indentedStatementBlockForEachConditionFalse
```

The `if`, each `elif`, and the final `else` line are all aligned. There can be any number of `elif` lines, each followed by an indented block. (Three happen to be illustrated above.) With this construction exactly *one* of the indented blocks is executed. It is the one corresponding to the *first* `True` condition, or, if all conditions are `False`, it is the block after the final `else` line.

- (d) `if-elif` [*Multiple Tests and if-elif Statements* (page 125)] The `else` : clause above may also be omitted. In that case, if none of the conditions is true, no indented block is executed.

5. `while` statements [*Simple while Loops* (page 143)]

```
while condition :  
    indentedStatementBlock
```

Do the indented block if *condition* is `True`, and at the end of the indented block loop back and test the *condition* again, and continue repeating the indented block as long as the condition is `True` *after* completing the indented block. Execution does not stop in the middle of the block, even if the *condition* becomes `False` at that point.

A `while` loop can be used to set up an (intentionally) apparently infinite loop by making *condition* be just `True`. To end the loop in that case, there can be a test inside the loop that sometime becomes `True`, allowing the execution of a `return` statement to break out of the loop. [*Fancier Animation Loop Logic (Optional)* (page 157)]

6. range function with three parameters [*Simple while Loops* (page 143)]

```
range ( start , pastEnd , step )
```

Return a list of elements

```
[ start , start + step , ... ]
```

with each element *step* from the previous one, ending just *before* reaching *pastEnd*. If *step* is positive, *pastEnd* is larger than the last element. If *step* is negative, *pastEnd* is smaller than the last element.

7. Type tuple

```
( expression , expression , and so on )
```

```
( expression , )
```

```
( )
```

(a) A literal tuple, with two or more elements, consists of a comma separated collection of values all enclosed in parentheses. A literal tuple with only a single element *must* have a comma after the element to distinguish from a regular parenthesized expression. [*Loops and Tuples* (page 138)]

(b) A tuple is a kind of sequence.

(c) Tuples, unlike lists, are immutable (may not be altered).

8. Interpretation as Boolean (`True`, `False`): All Python data may be converted to Boolean (type `bool`). The only built-in data that have a Boolean meaning of `False`, in addition to `False` itself, are `None`, numeric values equal to 0, and empty collections or sequences, like the empty list `[]` and the empty string `''`. [*Arbitrary Types Treated As Boolean* (page 158)]

9. Additional programming techniques

(a) These techniques extend the techniques listed in the summary of the previous chapter. [*Summary* (page 117)]

(b) The basic pattern for programming with a while loop is [*Simple while Loops* (page 143)]

```
initialization
```

```
while continuationCondition :
```

```
    main action to repeat
```

```
    prepare variables for next time through loop
```

(c) Interactive while loops generally follow the pattern [*Interactive while Loops* (page 146)]

```
input first data from user
```

```
while continuationConditionBasedOnTestOfUserData :
```

```
process user data
input next user data
```

Often the code to input the first data and the later data is the same, but it must appear in both places!

(d) Sentinel Loops [[Interactive while Loops](#) (page 146)]

Often the end of the repetition of a data-reading loop is indicated by a *sentinel* in the data: a data value known to both the user and the program to not be regular data, that is specifically used to signal the end of the data.

(e) Nesting Control Flow Statements [[Nesting Control-Flow Statements](#) (page 127)]

- i. `If` statements may be nested inside loops, so the loop does not have to execute all the same code each time; it just needs to start with the same *test*.
- ii. Loops may be nested. The inner loop completes its repetitions each time before going back to the outer loop heading.

(f) Breaking a repeating pattern into a loop [[Graphical Applications](#) (page 149)]

Since a loop is basically circular, there may be several choices of where to split it to list it in the loop body. The split point needs to be where the continuation test is ready to be run, but that may still allow flexibility. When you choose to change the starting point of the loop, and rotate statements between the beginning and the end of the loop, you change what statements need to be included before and after the loop, sometimes repeating or undoing actions taken in the loop.

- (g) Tuples in lists [[Loops and Tuples](#) (page 138)] A list may contain tuples. A `for`-each loop may process tuples in a list, and the `for` loop heading can do multiple assignments to variables for each element of the next tuple.
- (h) Tuples as return values [[Loops and Tuples](#) (page 138)] A function may return more than one value by wrapping them in a tuple. The function may then be used in a multiple assignment statement to extract each of the returned variables.

10. Graphics

- (a) Zelle's Graphics GraphWin method `checkMouse()` allows mouse tests without stopping animation, by testing the last mouse click, not waiting for a new one. [[Graphical Applications](#) (page 149)]
- (b) The most finished examples of using Zelle's graphics are in [[Loops and Tuples](#) (page 138)] and [[Graphical Applications](#) (page 149)].

DYNAMIC WEB PAGES

4.1 Overview

This chapter leads up to the creation of dynamic web pages. These pages and supporting programs have you using a simple Python web server available on your local machine. If you have access, the pages and programs may be uploaded to a public server accessible to anyone on the Internet.

A few disclaimers:

- This tutorial does not cover uploading to an account on a public server.
- No core Python syntax is introduced in this Chapter. Only a few methods in a couple of Python library modules are introduced.
- The chapter is by no means a major source of information about specific HTML codes. The appendix [HTML Source Markup](#) (page 197) introduces the limited source code for the html markup needed for the dynamic web exercises, and a bit more. Beyond that you can avoid dealing with specific codes with the use of a modern word-processor-like HTML editor. As a specific example, the open source HTML editor Kompozer is discussed, plus a little bit about the Mac application textedit, since Kompozer is not available for OSX versions from Catalina on.
- You need to work in a folder *where all the folders above it, up to the root folder for your hard drive, have no blanks in the name*. As long as your home folder has no blank in the name, the folder can be under that, like on your Desktop or in your Documents.

If you *do* have a blank in the name of your home folder, you will need to keep the files for this Chapter elsewhere. That may mean a separate folder on your hard drive or on a removable drive like a flash drive.

If the examples subfolder `www` is not in a place with all further up folders having no blank in the names, then move it now.

The chapter does allow you to understand the overall interaction between a browser (like Firefox on your local machine) and a web server and to create dynamic web content with Python. We treat interaction with the web basically as a mechanism to get input into a Python program and data back out and displayed. Web pages displayed in your browser are used for both the input and the output. The advantage of a public server is that it can also be used to store data accessible to people all over the world.

There are a number of steps in the development in this chapter, so I start with an overview:

1. A few bits about the basic format of *hypertext markup language* are useful to start.
2. The simplest *static* pages can be written with a word-processor. or by modifying simple html source examples.
3. Next we look at pages generated *dynamically*. An easy way to accomplish this is to create specialized static pages to act as templates into which the dynamic data is easily embedded. Web page creation can be tested totally locally, by creating HTML files and pointing your web browser to them. Initially we supply input data by

our traditional means (keyboard input or function parameters), and concentrate on having our Python program *convert* the input to the desired html output, and *display* this output in a web page.

4. We generate data from within a web page, using web forms. Initially we will test web forms by automatically dumping their raw data.
5. To fully integrate a browser and server, we
 - (a) use web forms to provide data,
 - (b) use a Python program specified on the server, called a *CGI script*, to access the web form data and transform the input data into the desired output,
 - (c) embed the output in a new dynamic web page that gets sent back to your browser. This Python server program transforms the input data, and generates output web pages much like we did in step 3, above.

4.2 Web page Basics

4.2.1 Format of Web Page Markup

Documents can be presented in many forms. A simple editor like Idle or Windows' Notepad produce plain text: essentially a long string of meaningful characters that appear in the final text you view.

Documents can be displayed with formatting of parts of the document. Web pages allow different fonts, italic, and boldfaced emphases, and different sized text and paragraph layouts. Microsoft Word, Libre Office, and OSX Pages, all display documents with various amounts of formatting. The syntax for the ways different systems *encode* the formatting information varies enormously.

If you look at an old Microsoft Word .doc document in a plain text editor like Notepad, you should be able to find the original text buried inside, but most of the symbols associated with the formatting are unprintable gibberish as far as a human is concerned.

Hypertext markup language (HTML) is very different in that regard. It produces a file of entirely human-readable characters, that could be produced with a plain text editor, but the *markup* parts of the file do not appear directly in your browser, but *instruct* the browser how to format the page.

For instance in HTML, the largest size of a heading with the text “Web Introduction”, would look like

```
<h1>Web Introduction</h1>
```

The heading format is indicated by bracketing the heading text ‘Web Introduction’ with markup sequences, `<h1>` beforehand, and `</h1>` afterward. All HTML markup is delimited by *tags* enclosed in angle brackets, and most tags come in pairs, surrounding the information to be formatted. The end tag has an extra `/`. Here ‘h’ stands for heading, and the number indicates the relative importance of the heading. (There is also h2, h3, for smaller headings.) In the early days of HTML, editing was done in a plain text editor, with the tags being directly typed in by people who memorized all the codes!

We will use little enough of the markup that the very limited introduction in [HTML Source Markup](#) (page 197), along with samples that show easily modified examples, will cover all the markup you need for the course.

With the enormous explosion of the World Wide Web, specialized software has been developed to make web editing be much like word processing, with a graphical interface, allowing formatting to be done by selecting text with a mouse and clicking menus and icons labeled in more natural language. The software then automatically generates the necessary markup. In this tutorial, a possible example for Windows users and Macs that are NOT upgraded to the Catalina OSX version, is the free, open source Kompozer from <https://sourceforge.net/projects/kompozer/>. It downloads the appropriate version for either a Windows machine or Mac with operating system version *before* Catalina. Users of Catalina, or later OSX versions, can look at the introduction to the Mac app TextEdit in [HTML Source Markup](#) (page 197).

If your operating system fits, you might download Kompozer, if you are not already using another environment that lets you see both the unformatted plain text and the formatted view.

An alternative for the simple markup needed for exercises is to modify example html source code using the ideas in [HTML Source Markup](#) (page 197).

4.2.2 Introduction to Static Pages in Kompozer

If you cannot run Kompozer, you can see the parallel html source discussion in [HTML Source Markup](#) (page 197), and skip this section that is specifically on Kompozer.

This section introduces the Kompozer web page editor to create *static* pages. A *static* page is one that is created ahead of time and just opened and used as needed. This is as opposed to a *dynamic* page, which is a custom page generated by software on demand, given some input parameters.

You can open Kompozer and easily generate a document with a heading, and italic and boldfaced portions....

Kompozer is used because it is free software, and is pretty easy to use, like a common word processor. Unlike a common word processor you will be able to easily look at the HTML markup code underneath. It is not necessary to know a lot about the details of the markup codes for HTML files to use Kompozer, but you can *see* the results of the markup.

We will use static pages later as a part of making dynamic pages, using the static pages as templates in which we insert data dynamically.

To creating static web pages

1. However you start Kompozer, go to the menu in Kompozer and select *File* → *New*. You will get what looks like an empty document.
2. Look at the bottom of your window. You should see a **Normal** tab selected, with other choices beside it, including a **Source** tab. Click on the **Source** tab. You should see that, though you have added no content, you already have the basic markup to start an html page!
3. Click again on the Normal tab to go back to the Normal view (of no content at the moment).
4. Assume you are making a home page for yourself. Make a title and some introductory text. Use regular word processor features like marking your title as Heading 1 in the drop down box on a menu bar. (The drop down menu may start off displaying 'Paragraph' or 'Body Text'.) You can select text and make it bold or italics; enlarge it ... using the editing menu or icons.
5. Before getting too carried away, save your document as `home.html` in the existing *www directory under your earlier Python examples*. It will save a lot of trouble if you keep your web work together in this `www` directory, where I have already placed a number of files that you will want to keep together in one directory.
6. Just for comparison, switch back and forth between the Normal and Source views to see all that has gone on underneath your view, particularly if you edited the format of your text. Somewhere embedded in the Source view you should see all the text you entered. Some individual characters have special symbols in HTML that start with an ampersand and end with a semicolon. Again, it is more important to understand that there are two different views than to be able to reproduce the Source view from memory.
7. You can use your web browser to see how your file looks outside the editor. The easiest way to do this is to go to the web browser's menu and select something like *File* → *Open File*, and find the `home.html` file that you just wrote. It should look pretty similar to the way it looked in Kompozer, but if you had put in hyperlinks, they should now be active.

The discussion of web page editing continues in [Editing HTML Forms](#) (page 180), but first we get Python into the act.

4.2.3 Editing and Testing Different Document Formats

Note: In this chapter you will be working with several different types of documents that you will edit and test in very different ways. The ending of their names indicate their use.

Each time a new type of file is discussed in later sections, the proper ways to work with it will be repeated, but with all the variations, it is useful to group them all in one place now:

...Web.py *My* convention for regular Python programs taking all their input from the keyboard, and producing output displayed on a web page. These programs can be run like other Python programs, directly from an operating system folder or from inside Idle. They are *not* a final product, but are a way of breaking the development process into steps in a testable way.

...cgi Python program to be started from a web browser and run by a web server. You will develop code using a local web server on your own machine.

...html Web documents most often composed in an editor like Kompozer. By *my* convention, these have a sub-categories

...Template.html not intended to be displayed directly in a browser, but instead are read by a Python program (...cgi or ...Web.py) to create a template or format string for a final web page that is dynamically generated inside the Python program.

Other files ending in .html are intended to be directly viewed in a web browser. Except for the simple static earlier examples in *Introduction to Static Pages in Kompozer* (page 167), the pages for this course are designed to reside on a web server, and include forms that can pass information to a Python CGI program (...cgi).

To make this work on your computer:

1. Have all the web pages in the same directory as the example program localCGIServer.py. It is easiest to leave it in the www subdirectory of your examples directory.
2. Looking ahead to when we get to using a server dynamically (CGI - Dynamic Web Pages (page 172)):
 - (a) Include the Python CGI server programs in the same directory.
 - (b) Have localCGIServer.py running, started from a directory window, *not from inside Idle*
 - (c) In the browser URL field, *the web page file name must be preceded by* `http://localhost:8080/`. For example, `http://localhost:8080/adder.html` would refer to the file `adder.html`, in the same directory as the *running* localCGIServer.py. The URL may either be an html file or possibly a CGI file. For example, `http://localhost:8080/now.cgi` would call the file `now.cgi` (assuming it is in the same directory as the running localCGIServer.py).
 - (d) Most often CGI programs are referenced in a web form, and the program is called *indirectly* by the web server. CGI programs can be edited and saved inside Idle, but they do *not* run properly from inside Idle. They must be run via the server/browser combination. More on this later.

4.3 Composing Web Pages in Python

4.3.1 Dynamically Created Static Local Pages from Python

For the rest of this chapter, the example files will come from the www directory under the main examples directory you unzipped. I will refer to example file there as “example www files”.

As the overview indicated, dynamic web applications typically involve getting input from a web page form, processing the input in a program on the server, and displaying output to a web page. Introducing all these new ideas at once

could be a lot to absorb, so this section uses familiar keyboard input into a regular Python program and then, like in the final version, processes the input and produces the final web page output.

Follow this sequence of steps:

1. Open the example `www` file `hello.html` in your browser, to see what it looks like.
2. Change your browser view - for instance go back to the previous page you displayed.
3. Open the same `hello.html` file in Kompozer, if that works for you, or another editor that will show the html source, as discussed in [HTML Source Markup](#) (page 197).
4. If using Kompozer, switch to the Source view (clicking the Source tab). Sometimes you will want to copy HTML text into a Python program. For instance, I selected and copied the entire contents of the `hello.html` source view and pasted it into a multi-line string in the Python program shown and discussed below.
5. Careful, note the change from past practice here: Start Python *from inside the www directory*. In Windows you may start Idle with the IdleOnWindows shortcut that I placed *in the www directory*, not the original example directory.
6. Open the `www` example program `helloWeb1.py` in an Idle edit window.
7. *Run it.*

You should see a familiar web page appear in your *default* browser (possibly not the one you have been using). This is obviously not a very necessary program, since you can select this page directly in your browser! Still, one step at a time: it illustrates several useful points. The program is copied below. *Read it:*

```
'''A simple program to create an html file from a given string,
and call the default web browser to display the file.'''

contents = '''<!DOCTYPE html PUBLIC "-//W3C//DTD HTML 4.01 Transitional//EN">
<html>
<head>
  <meta content="text/html; charset=ISO-8859-1"
  http-equiv="content-type">
  <title>Hello</title>
</head>
<body>
Hello, World!
</body>
</html>
'''

def main():
    browseLocal(contents)

def strToFile(text, filename):
    """Write a file with the given name and the given text."""
    output = open(filename, "w")
    output.write(text)
    output.close()

def browseLocal(webpageText, filename='tempBrowseLocal.html'):
    '''Start your webbrowser on a local file containing the text
    with given filename.'''
    import webbrowser, os.path
    strToFile(webpageText, filename)
    webbrowser.open("file://" + os.path.abspath(filename)) #elaborated for Mac

main()
```

This program encapsulates two basic operations into the last two functions that will be used *over and over*. The first, `strToFile`, has nothing new, it just puts specified text in a file with a specified name. The second, `browseLocal`, does more. It takes specified text (presumably a web page), puts it in a file, and directly displays the file in your default web browser. It uses the `open` function from the `webbrowser` module to start the new page in your web browser.

The `open` function here requires the name of a file or URL. Since the page is automatically generated by the program for one-time immediate viewing, it automatically uses the same throwaway filename, `tempBrowseLocal.html` specified as the default in the keyword parameter. If you really want another specific, name you could pass it as a parameter.

In this particular program the text that goes in the file is just copied from the literal string named `contents` in the program.

This is no advance over just opening the file in the browser directly! Still, it is a start towards the aim of creating web content dynamically.

An early example in this tutorial displayed the fixed `Hello World!` to the screen. This was later modified in `hello_you4.py` to incorporate user input using the string format method of [Dictionaries and String Formatting](#) (page 44),

```
person = input('Enter your name: ')
greeting = 'Hello {person}!'.format(**locals())
print(greeting)
```

Similarly, I can turn the web page contents into a format string, and insert user data. Load and *run* the `www` example program `helloWeb2.py`.

The simple changes from `helloWeb1.py` are marked at the beginning of the file and shown below. I modified the web page text to contain `'Hello, {person}!'` in place of `'Hello, World!'`, making the string into a *format* string, which I renamed to the more appropriate `pageTemplate`. The changed initial portion with the literal string and the main program then becomes

```
pageTemplate = '''
<!DOCTYPE html PUBLIC "-//W3C//DTD HTML 4.01 Transitional//EN">
<html>
<head>
  <meta content="text/html; charset=ISO-8859-1"
  http-equiv="content-type">
  <title>Hello</title>
</head>
<body>
Hello, {person}!
</body>
</html>''' # NEW note '{person}' two lines up

def main():    # NEW
    person = input("Enter a name: ")
    contents = pageTemplate.format(**locals())
    browseLocal(contents)
```

Now the line

```
contents = pageTemplate.format(**locals())
```

incorporates the person's name into the contents for the web page before saving it to a file and displaying it.

In this case, I stored the literal format string inside the Python program, but consider a different approach:

Load and *run* the `www` example program `helloWeb3.py`. It behaves exactly like `helloWeb2.py`, but is slightly different internally - it does not directly contain the web page template string. Instead the web page template string is read from the file `helloTemplate.html`.

Below is the beginning of `helloWeb3.py`, showing the only new functions. The first, `fileToStr`, will be a standard function used in the future. It is the inverse of `strToFile`.

The main program obtains the input. In this simple example, the input is used directly, with little further processing. It is inserted into the web page, using the file `helloTemplate.html` as a format string.

```
def fileToStr(fileName): # NEW
    """Return a string containing the contents of the named file."""
    fin = open(fileName);
    contents = fin.read();
    fin.close()
    return contents

def main():
    person = input('Enter a name: ')
    contents = fileToStr('helloTemplate.html').format(**locals()) # NEW
    browseLocal(contents)
```

Although `helloTemplate.html` is not intended to be viewed by the user (being a template), you should open it in a browser or web editor (Kompozer or ...) to look at it. It is legal to create a web page in a web page editor with expressions in braces embedded in it! If you look in the source view in Kompozer or in a web source editor, you will see something similar to the literal string in `helloWeb2.py`, except the lines are broken up differently. (This makes no difference in the formatted result, since in html, all white space is considered the same.)

Back in the Normal mode in Kompozer, or in source mode for any html editor, add an extra line of text right after the line “Hello, {person}!”. Then save the file again (under the *same* name). Run the program `helloWeb3.py` again, and see that you have been able to change the *appearance* of the output without changing the Python program itself. That is the aim of using the template html page, allowing the web output formatting to be managed mostly *independently* from the Python program.

A more complicated but much more common situation is where the input data is processed and transformed into results somehow, and these *results*, often along with some of the original input, are embedded in the output web page that is produced.

As a simple example, load and *run* the www example program `additionWeb.py`, which uses the template file `additionTemplate.html`.

The aim in the end of this chapter is to have user input come from a form on the web rather than the keyboard on a local machine, but in either case the input is still transformed into results and all embedded in a web page. To make parts easily reusable, I *obtain* the input in a *distinct* place from where the input is *processed*. In keeping with the later situation with web forms, all input is of string type (using keyboard input for *now*).

Look at the program. You will see only a few new lines! Because of the modular design, most of the program is composed of recent standard functions reused.

The only new code is at the beginning and is shown here:

```
def processInput(numStr1, numStr2): # NEW
    """Process input parameters and return the final page as a string."""
    num1 = int(numStr1) # transform input to output data
    num2 = int(numStr2)
    total = num1+num2
    return fileToStr('additionTemplate.html').format(**locals())

def main(): # NEW
    numStr1 = input('Enter an integer: ') # obtain input
    numStr2 = input('Enter another integer: ')
    contents = processInput(numStr1, numStr2) # process input into a page
    browseLocal(contents) # display page
```



The input is obtained (via `input` for now), and it is processed into a web page string, and as a separate step it is displayed in a local web page.

There are a few things to note:

- All input is strings. Before the numerical calculations, the digit strings must be converted to integers.
- I do calculate (a very simple!) result and use it in the output web page.
- Although it is not in the Python code, an important part of the result comes from the web page format string in `additionTemplate.html`, which includes the needed variable names in braces, `{num1}`, `{num2}`, and `{total}`. View it in your browser or in a web editor.

When you write your own code, you might modify `additionWeb.py`, or you can start from a stripped down skeleton in the example `www` folder, `skeletonForWeb.py`, with comments about where to insert your special code.

We will examine the bottom part of the following diagram later. The top part outlines the flow of data from string input to web page in your browser for a regular Python program like what we have been describing, with the processing outlined in the middle line. The parts in the middle will be common to the later client/server program, that manages input and output with the bottom line, that we will discuss later.



Again, this last section was somewhat artificial. You are not in the end likely to find such programs practical as end products. However such programs are reasonable to write and test and they include *almost* all the code you will need for a more practical (but harder to debug) CGI program, coming next....

Quotient Web Exercise

* Save `additionWeb.py` or `skeletonForWeb.py` as `quotientWeb.py`. Modify it to display the results of a division problem in a web page. As in the exercises in Chapter 1, display a full sentence labeling the initial data and both the integer quotient and the remainder. You can take your calculations from [Quotient String Return Exercise](#) (page 40). You should only need to make Python changes to the `processInput` and `main` functions. You will also need the HTML for the output page displayed. Make a web page template file called `quotientTemplate.html` and read it into your program. Turn in both `quotientWeb.py` and `quotientTemplate.html`.

4.4 CGI - Dynamic Web Pages

CGI stands for *Common Gateway Interface*. This interface is used by web servers to process information requests supplied by a browser. Python has modules to allow programs to do this work. The convention used by many servers is to have the server programs that satisfy this interface end in `.cgi`. That is the convention used below. All files below ending in `.cgi` are CGI programs on a web server, and in this chapter, they will all be Python programs (though there are many other languages in use for this purpose). These programs are often called scripts, so we will be dealing with *Python CGI scripts*.

You cannot run a .cgi file from inside Idle.

4.4.1 An Example in Operation

The web examples folder provides a simple web server, built into Python, that you can run on your own computer. (It is also possible to set your computer up with the right software to be a server for the Internet - that is *totally unnecessary* for this class.)

Windows In an operating system file window, go to the folder with the www examples. Depending on the setup of your operating system, there are several ways to start the local server that might work.

1. Double click on `startServer.cmd`, which I have placed in the example www folder. If this does not work, try:
2. Right click on `localCGIServer.py` in the File Explorer window, and select Open With -> Python Launcher
3. If neither work, check if you need to modify your Python installation, covered in [Some Special Windows Instructions](#) (page 193), and then try the `startServer.cmd` approach again.

Mac This is more involved the first time. See [Some Special Mac Instructions](#) (page 194).

You should see a console window pop up, saying “Localhost CGI server started”. This approach starts the `localCGIServer.py` server without monopolizing Idle. Once the server is started, *leave the server console window there* as long as you want the local server running for *that folder*.

Warning: Do *not* start the local server running from inside Idle. It will monopolize Idle.

Note: If the server aborts and gives an error message about *spaces in the path*, look at the path through the parent directories over this www directory. If any of the directory names have spaces in them, the local file server will not work.

In case of this error, either go up the directory chain and alter the directory names to eliminate spaces or move the examples directory to a directory that does not have this issue.

For a very simple but complete example:

1. Make sure you have the local server going.
2. Open the web link <http://localhost:8080/adder.html> (preferably in a new window, separate from this tutorial).
3. You see a web *form*. Follow the instructions, enter integers, and click on the *Find Sum* button. You get back a web page that obviously used *your* data.
4. Look at the local server console window. You should see a log of the activity with the server.

We will end up completely explaining the web pages and .cgi file needed to accomplish this, allowing you to generalize the idea, but for now just see how it works.

First consider the rather involved basic execution steps behind the scene:

1. The data you type is handled directly by the browser. It recognizes forms.
2. An action instruction is stored in the form saying what to do when you press a button indicating you are ready to process the data (the *Find Sum* button in this case).
3. In the cases we consider in this tutorial, the action is given as a web resource, giving the location of a CGI script on some server (in our cases, the same directory on the server as the current web page). It is a resource handled by the local server, when the URL starts with “<http://localhost:8080/>” followed by the name of the starting web file. *All the URL’s you use for this section and its exercises should start that way.*
4. When you press the button, the browser sends the data that you entered to that web location (in this case `adder.cgi`, in the same folder as the original web page).

5. The server recognizes the web resource as an executable script, sees that it is a Python program, and executes it with the Python interpreter, using the data sent along from the browser form as input.
6. The script runs, manipulates its input data into some results, and puts those results into the text of a web page that is the output of the program via `print` statements.
7. The server captures this output from the program and sends it back to your browser as a new page to display.
8. You see the results in your browser.

Close the server window.

Test what happens if you try to reload the web link <http://localhost:8080/adder.html>. You should get an error, since you refer to localhost, but you *just stopped the local server*.

For the rest of this chapter, we will be wanting to use the local server, so *restart* it in the example www folder, in a manner appropriate for your operating system:

- Windows: whatever worked when you started it the first time.
- Mac: Start the local server whatever way worked last time, either double clicking on `cgiServerScript` that you should have created, or right/control click on `localCGIServer.py` in the Finder window, and select Open With -> Python Launcher

Now you can *keep the local server going* as long as you want to run CGI scripts from the same folder.

If you ever want to have cgi scripts and supporting files in a different folder, *stop the server for any other folder* first, and start it up in the folder where you have your materials.

4.4.2 A Simple Buildup

Before we get too complicated, consider the source code of a couple of even simpler examples.

hellotxt.cgi

The simplest case is a CGI script with no input that just generates plain text, rather than HTML. *Assuming you have your local server going*, you can go to the link <http://localhost:8080/hellotxt.cgi>. The code is in the www example directory, `hellotxt.cgi`, and below for you to read:

```
#!/usr/bin/env python3

# Required header that tells the browser how to render the text.
print("Content-Type: text/plain\n\n") # here text -- not html

# Print a simple message to the display window.
print("Hello, World!\n")
```

The top line is what tells the operating system that this is a Python 3 program. It says where to find the right Python interpreter to process the rest of the script. This exact location is significant on a Unix derived server (like any Mac with OS X). In Windows the only thing important in the line is the distinction between Python 2 and 3. If you leave the line there as a part of your standard text, you have one less thing to think about when uploading to a Unix server or running on a Mac.

The first print function is telling the server receiving this output that the format of the rest of the output will be plain text. This information gets passed back to the browser later. This line should be included exactly as stated IF you only want the output to be plain text (the simplest case, but *not our usual* case).

The rest of the output (in this case just from one print function) becomes the body of the plain text document you see on your browser screen, verbatim since it is plain text. The server captures this output and redirects it to your browser.

hellohtml.cgi

We can make some variation and display an already determined *html* page rather than plain text. Try the link <http://localhost:8080/hellohtml.cgi>. The code is in the `www` example directory, `hellohtml.cgi`, and below for you to read:

```
#!/usr/bin/env python3

print("Content-Type: text/html\n\n") # html markup follows

print("""
<html>
  <Title>Hello in HTML</Title>
<body>
  <p>Hello There!</p>
  <p><b>Hi There!</b></p>
</body>
</html> """)
```

There are two noteworthy changes. The *first* print function call now declares the rest of the output will be *html*. This is a standard boilerplate line you will be using for your CGI programs. The remaining print function call has the markup for an html page. Note that the enclosing triple quotes work for a multi line string. Other than as a simple illustration, this CGI script has no utility: Just putting the contents of the last print function in a file for a static web page `hello.html` would be much simpler.

now.cgi

One more simple step: we can have a CGI script that generates dynamic output by reading the clock from inside of Python: Try the link <http://localhost:8080/now.cgi>. Then click the refresh button and look again. This cannot come from a static page. The code is in the `www` example directory, `now.cgi`, and below for you to read:

```
#!/usr/bin/env python3

import time
print("Content-Type: text/html\n\n") # html markup follows

timeStr = time.strftime("%c") # obtains current time

htmlFormat = """
<html>
  <Title>The Time Now</Title>
<body>
  <p>The current Central date and time is: {timeStr}</p>
</body>
</html> """

print(htmlFormat.format(**locals())) # see {timeStr} embedded above
```

This illustrates a couple more ideas: First a library module, `time`, is imported and used to generate the string for the current date and time.

The web page is generated like in `helloWeb2.py`, embedding the dynamic data (in this case the time) into a literal web page format string. (Note the embedded `{timeStr}`.) Unlike `helloWeb2.py`, this is a CGI script so the web page contents are delivered to the server just with a `print` function.

adder.cgi

It is a small further step to get to processing dynamic input. Try filling out and submitting the adder form one more time, <http://localhost:8080/adder.html>. This time notice the URL at the top of the browser page *when the result is displayed*. You should see something like the following (only the numbers should be the ones *you* entered):

<http://localhost:8080/adder.cgi?x=24&y=56>

This shows one mechanism to deliver data from a web form to the CGI script that processes it. The names `x` and `y` are used in the form (as we will see later) and the data you entered is associated with those names. In fact a form is not needed at all to create such an association: If you directly go to the URLs

<http://localhost:8080/adder.cgi?x=24&y=56>

or

<http://localhost:8080/adder.cgi?x=-12345678924&y=3333333333>

you get arithmetic displayed without the form. This is just a new input mechanism into the CGI script.

You have already seen a program to produce this adder page from inside a regular Python program taking input from the keyboard. The new CGI version, `adder.cgi`, only needs to make a few modifications to accept input this way from the browser. New features are commented in the source and discussed below. The new parts are the `import` statement through the `main` function, and the code after the end of the `fileToStr` function. *Read* at least these new parts in the source code shown below:

```
#!/usr/bin/env python3

import cgi      # NEW

def main(): # NEW except for the call to processInput
    form = cgi.FieldStorage()      # standard cgi script lines to here!

    # use format of next two lines with YOUR names and default data
    numStr1 = form.getfirst("x", "0") # get the form value associated with form
                                         # name 'x'. Use default "0" if there is none.
    numStr2 = form.getfirst("y", "0") # similarly for name 'y'
    contents = processInput(numStr1, numStr2) # process input into a page
    print(contents)

def processInput(numStr1, numStr2):
    '''Process input parameters and return the final page as a string.'''
    num1 = int(numStr1) # transform input to output data
    num2 = int(numStr2)
    total = num1+num2
    return fileToStr('additionTemplate.html').format(**locals())

# standard code for future cgi scripts from here on
def fileToStr(fileName):
    """Return a string containing the contents of the named file."""
    fin = open(fileName);
    contents = fin.read();
    fin.close()
    return contents

try:      # NEW
    print("Content-type: text/html\n\n")      # say generating html
    main()
except:
    cgi.print_exception()                    # catch and print errors
```

First the overall structure of the code:

- To handle the CGI input we import the `cgi` module.
- The main body of the code is in a `main` method, following good programming practice.
- After the definition of `main` come supporting functions, each one copied from the earlier local web page version, `additionWeb.py`.
- At the end is the new, boilerplate cgi wrapper code for `main()`. This is code that you can always just copy. I chose to put the initial `print` function here, that tells the server html is being produced. That mean the `main` method only needs to construct and print the *actual* html code. Also keep the final `try-except` block that catches any execution errors in the program and generates possibly helpful trace information that you can see from your browser. (How to write such error catching code in general is not covered in this introductory tutorial, but you can copy it in this situation!)

The `main` function has three sections, as in the local web page version: read input (this time from the form, not the keyboard), process it, and generate the html output.

- Reading input: The first line of `main` is a standard one (for you to copy) that sets up an object called `form` that holds the CGI form data accompanying the web request sent by the browser. You access the form data with statements like the next two that have the pattern:

```
variable = form.getfirst( nameAttrib , default )
```

If there is a form input field with **name** `nameAttrib`, its **value** from the browser data is assigned to `variable`. If no value is given in the browser's data for `nameAttrib`, `variable` is set equal to `default` instead.

In this way data associated with names given by the browser can be transferred to your Python CGI program, and if there is no such name in a form feeding this cgi program, the program does not immediately bomb out.

In this program the values associated with the browser-supplied names, 'x' and 'y', are extracted. I use slightly verbose Python variable names that remind you that all values from the browser forms are strings.

- The `processInput` function that is passed the input parameters from whatever source, is *exactly the same* as in `additionWeb.py`, so we already know it works!
- Output the page. In a CGI script, this is easier than with the local web pages: just *print* it - no need to save and separately display a file! The server captures the "printed" output.

This program can now serve as a template for your own CGI scripts: The only things you need to change are

1. The lines in `main()` that get the input from a web form, using the names from the input tags in the form, and assigning the string values to Python variables.
2. In `main` call `processInput(...)` with all the data from the form that you need to pass as parameters to `processInput`.
3. The heading of the definition of `processInput` need to fit with the actual parameters passed by the call in `main()`. Furthermore the `processInput` part can be written and tested earlier with a Python program in the format of the `...Web.py` programs that we have discussed.
4. While this is the only Python code, you still need to create an output web page template, and refer to it as the parameter of `fileToStr`. Again, if you tested your logic using an earlier `...Web.py` program, just use the same output web template!

A stripped down skeleton, to start a cgi program from, with comments about needed changes is in `skeletonFor.cgi`. If you do not want to start your code by modifying an existing example cgi program, then you might start by copying `skeletonFor.cgi`.

Idle and .cgi Files You can always start Idle a way that you have before, like on an existing `.py` file. Then deal with editing `.cgi` files from inside Idle.

For a Mac, See the Chapter 4 part of [Some Special Mac Instructions](#) (page 194) for a way to start Idle on a .cgi file easily, after some initial work the first time.


On Windows, the easiest thing may be to use IdleOnWindows.cmd.

You will want to open and save .cgi files in Idle. Then dialog windows in both Windows and on a Mac have the same ideas, but different labels. There is a file type filter field for both. It is labeled “Format” on a Mac. On Windows, for saving, it is labeled “Save as Type”, and for opening a file, there is a field it at the lower right, unlabeled.

If you want a file ending in .cgi, change the filter field to All files (*). For saving, be sure to enter the full file name you want, with the extension, .cgi.

If you forget and do not change the file filter when saving, a “.py” will be added to your file name. Then you can rename it in an operating system file folder.

In the following diagram, now we have discussed both the top regular Python sequence using the top, the bottom cgi specific sequence, and the common part in the middle, as shown. In both cases input data gets processed into the content of a web page that goes to a browser. For any major application the main work is in the processing in the middle. Since that part is shared in both approaches, it can be tested with a simple Python program, before the starting and ending steps of the input and output flow are changed for the cgi client/server model.



The only part that still needs details explained is for web forms. Before going on to that, it is time to talk about handling errors in the CGI scripts we have been discussing.

The programs discussed here follow the simple pattern:

get all input data; process input data; output results all together.

This pattern can be used both in a testing . . . Web . py version *and* in a dynamic cgi version, using a `processInput` function common to both.

Clearly more complicated patterns are often needed when input, processing, and output are mixed in a different way, but for these examples and for the chapter exercises, this is all we need.

4.4.3 Errors in CGI Scripts

Before you start running your own CGI scripts on the local server, it is important to understand how the different kinds of errors that you might make will be handled.

If you write a regular Python program, even one that produces a web page, you can write the code and run it in Idle, and Idle will display all the kinds of errors.

With a CGI script, you can still use Idle to write your code, but *you cannot run the cgi code in Idle*, and errors show up in *three* different places, depending on their type:

Syntax errors You are encouraged to check for syntax errors *inside* Idle, by using the menu sequence *Run -> Check Module*. If you fail to do this and try running a script with a syntax error, the error trace appears in the *console* window that appears when you start the local server – better to have it fixed before then, while you are still

editing. If you want an illustration, you might try changing `adder.cgi`, making an error like `import cgi`, and try using `adder.html` with the flawed script. (Then fix it and try again.)

If you find it in Idle, you can jump to the line where the error was detected.

Execution Errors The error trace for *execution* errors is displayed in your *web browser*, thanks to the final boilerplate code with the `try-catch` block at the end of the CGI script. *If you omit that final boilerplate code, you completely lose descriptive feedback: Be sure to include that boilerplate code!* You can also see an illustration now. Get an error by introducing the statement:

```
bad = 'a'.append('b')
```

in the main function and run it. (Then take it out.)

Server Errors Your work can cause an issue inside the local server, not directly in the Python execution. Some errors are communicated to the browser, but not necessarily all. Other errors appear in the log generated in the local server's window. You could have a file named wrong, for instance, in any operating system.

Also, on a Mac or in Linux, where the CGI script needs to be set as *executable*, an error with a non-executable CGI script only shows up in this log in the local server window. You should be able to fix this error by running the `CGIfix.py` program, *in the same folder*.

Logical Errors Since your output appears in the web browser, when you produced something legal but other than what you intended, you see it in the browser. If it is a formatting error, fix your output page template. If you get wrong answers, check your `processInput` function.

Here is an outline for client/server program testing, emphasizing errors to be conscious of and avoid. If you have problems, please actively check out this whole list:

- You are encouraged to add your files into the examples `www` folder. If you really want to work in a different folder, you will want to copy a number of support files into that folder: `CGIfix.py` and `localCGIServer.py`, plus `dumpcgi.cgi` if you want to test web forms separately. For Windows: `startServer.cmd`. On a Mac be sure to run `CGIfix.py`, to generate the folder-specific version of `cgiServerScript`.
- If you want an easy environment to test a fancy `processInput` function, embed it in a regular Python program, as we have discussed for `...Web.py` programs. Then you can test it normally in Idle. This will also allow you to make sure the web template, that you refer to in your `processInput` function, is in a legitimate form, with substitutions only for local variables.
- You can *code* a CGI script in idle, but *not run* it. Be sure to save it with the suffix `.cgi`, *not* `.py`. *Do not run* it in Idle. The only testing you can do in Idle is for syntax, using the menu sequence *Run -> Check Module* or its keyboard shortcut. *Do* run that test.
- At the end of your CGI script, make sure you include the boilerplate code that catches execution errors.
- Remember to run `CGIfix.py` in the same folder as a precaution to clean things up, particularly with a new file on a Mac.
- Make sure your local server is going, and that all the files you reference are in the same folder as the local server.
- Make sure you test your page by starting it in your web browser with a URL starting `http://localhost:8080/`. If you load a web page directly from your file system by mistake, it *will not cause an obvious error* - the dynamic actions will just *not* take place. If you are not paying attention, this can happen and be very confusing!
- If things do not work, remember the three places to check for errors. After initially checking for syntax errors in Idle, the remaining errors might be displayed on the output page in the browser (if you confirmed that you have the `try-catch` boilerplate code at the end). If that does not totally explain things, remember to check the server console window, too.

We have not covered web forms yet, but rather than bite off too much at once, this is a good time to write your own first CGI script in the following exercise.

Quotient.cgi Exercise

* Modify *Quotient Web Exercise* (page 172) and save it as a CGI script `quotient.cgi` in the *same* directory where you have `localCGIServer.py` and your output html page template from `quotientWeb.py`. Make `quotient.cgi` take its input from a browser, rather than the keyboard. This means merging all the standard CGI code from `adder.cgi` with the `processInput` function code from your `quotientWeb.py`. Please keep the same web form data names, 'x' and 'y', as in `adder.cgi`, so the main method should not need changes from `adder.cgi`. Remember to test for syntax errors inside Idle, and to have the local web server running when you run the CGI script in your browser. Since we have not yet covered web forms, test your CGI script by entering test data into the URL in the browser. In particular use links <http://localhost:8080/quotient.cgi?x=24&y=56> and <http://localhost:8080/quotient.cgi?x=36&y=15>. These URLs depend on you keeping the same data names, x and y, in the form. After trying these links, you can edit the numbers in the URL in the browser to see different results.

4.4.4 Editing HTML Forms

This section is a continuation of *Introduction to Static Pages in Kompozer* (page 167), intended for users running Kompozer. A *parallel development, without Kompozer, that may be simpler* is in *HTML Source Markup* (page 197).

This section is about HTML editing using Kompozer – not about Python. HTML forms will allow user-friendly data entry for Python CGI scripts. This is the last elaboration to allow basic web interaction: Enter data in a form, submit it, and get a processed result back from the server.

The initial example, `adder.html`, had a form with only text input fields and a submit button inside. *You will not need anything with further kinds of markup for the exercises.*

Now open `adder.html` in Kompozer. Switch to the Source view. This is a short enough page that you should not get lost in the source code. The raw text illustrates another feature of html: attributes. The tag to start the form contains not only the tag code *form*, but also several expressions that look like Python assignment statements with string values. The names on the left-hand side of the equal signs identify a type of *attribute*, and the string value after the equal sign gives the corresponding string *value* for the attribute. The tag for many kinds of input fields is `input`. Notice that each field includes `name` and `value` attributes. (So there is some confusion possible here from the fact the **value** is the name of a particular attribute, and all attributes have string as their value. I will try to use the phrase “string value” consistently for the second usage.) See that the 'x' and 'y' that are passed in the URL by the browser come from the **name** attribute given in the HTML code for the corresponding fields!

Kompozer and other web editors translate your menu selections into the raw html code with proper attribute types. This high level editor behavior is convenient to avoid having to learn and debug the exact right html syntax! On the other hand, using pop-up field editing windows has the disadvantage that you can only see the attributes of one field at a time, and likely need multiple mouse clicks, plus typing. Particularly if you want to modify a number of name or value attributes, it is annoying that you need a number of mouse clicks to go from one field to the next.

If you *only* want to modify the *string values* assigned to existing attributes like `name` and `value`, it may be easier to do in the source window, where you can see everything at once. (Or use a separate html source editor, as described in *HTML Source Markup* (page 197).) Making syntax errors in the html source is not very likely if the only changes that you make to tags are data *inside* quoted value strings.

The action URL is a property of the entire form. To edit it in Kompozer via the GUI, right click inside the form, but *not* on any field element, and select the bottom pop-up choice, Form Properties. Then you see a window listing the Action URL and you can change the value to the name of the CGI script that you want to receive the form data. When you create your own web form, I suggest you make the initial action URL be `dumpcgi.cgi`. This will allow you to debug your form separate from your CGI script. When you have tested that your web form has all the right names and initial values, you can change the action URL to your CGI script name (like `quotient.cgi`), and go on to test the combination of the form and the CGI script!

If you are modifying a previous working form, it is likely easier to use the source view, and just replace the value of the form's action attribute to the new `.cgi` file name.


Optionally, you can test various input methods by opening and playing with <http://localhost:8080/commonFormFields.html>. (Make sure your local server is still running!)

To allow easy concentration on the data sent by the browser, this form connects to a simple CGI script `dumpcgi.cgi`, that just dumps and labels all the form data to a web page. Press the submit button in the form, and see the result. Back up from the output to the previous page, the form, and change some of the data in all kinds of fields. Submit again and see the results. Play with this until you get the idea clearly that the form is passing on your data.

If you want to create a form and input fields *using the Kompozer GUI*, open this same file, the `www` example `commonFormFields.html`, in *Kompozer*. The static text in this page is set up as a tutorial on forms in *Kompozer*. Read the content of the page describing how to edit at least forms with text input fields and submit buttons. *The other fancier fields are optional – not needed for the chapter exercises.*

Read the static text about how to edit individual fields, and change some field parameters, save the file and reload it in your browser, and submit again. If you change the name or value attributes, they are immediately indicated in the dumped output. If you change things like the text field size, it makes a change in the way the form looks and behaves. You can return to the original version: An extra copy is saved in `commonFormFieldsOrig.html`.

Now we have discussed the last piece, web forms, in the diagram for the comparison of generating web pages dynamically by a regular Python program or a server CGI script:



Note the last three Python videos do not directly corresponding to a single place in the Tutorial text. Instead they go through the entire process for web based programs from the beginning. Video 4.4.4b creates a `birthday.html` web form looking forward to `birthday.cgi` of video 4.4.4d. In the middle video 4.4.4c creates `birthdayWeb.py`, testing the process function and output template to be used in `birthday.cgi`.

QuotientWeb Form Exercise

* Complete the web presentation for `quotient.cgi` of *Quotient.cgi Exercise* (page 180) by creating a web form `quotient.html` that is intelligible to a user and which supplies the necessary data to `quotient.cgi`.

Be sure to test the new form on your local server, using the URL <http://localhost:8080/quotient.html>. Remember that you must have the local server running first. You must have all the associated files in the same directory as the server program you are running, and you cannot just click on `quotient.html` in a *file* browser. You must start it from the the URL <http://localhost:8080/quotient.html>, that specifically refers to the server localhost.

Dynamic Web Programming Exercise

* Make a simple complete dynamic web presentation with a CGI script that uses at least *three* user inputs from a form. The simplest would be to just add three numbers instead of two. Call your form `dynamic.html`. Call your CGI script `dynamic.cgi`. Call an output template `dynamicTemplate.html`. Remember the details listed in the previous exercise to make the results work on localhost. After the server is started and you have all the files, go to <http://localhost:8080/dynamic.html> to test it a few times.

Summary (page 183) starts with the overall process for creating dynamic web pages.

4.4.5 More Advanced Examples

This is an optional section.

One of the advantages of having a program running on a public server is that data may be stored centrally and augmented and shared by all. In high performance sites data is typically stored in a sophisticated database, beyond the scope of this tutorial. For a less robust but simpler way to store data persistently, we can use simple text files on the server.

The `www` example page `namelist.html` uses `namelist.cgi` to maintain a file `namelist.txt` of data submitted by users of the page. You can test the program with your local Python server. It is less impressive when you are the only one who can make changes! The source code is documented for those who would like to have a look.

You also may want to look at the source code of the utility script you have been using, `dumpcgi.cgi`. It uses a method of getting values from the CGI data that has not been discussed:

```
val = form.getlist(name)
```

This method returns a list of values associated with a name from the web form. The list may have, 0, 1, or many elements. It is needed if you have a number of check boxes with the same name. (Maybe you want a list of all the toppings someone selects for a pizza.)

Both `dumpcgi.cgi` and `namelist.html` add an extra layer of robustness in reflecting back arbitrary text from a user. The user's text may include symbols used specially in html like '<'. The function `safePlainText` replaces reserved symbols with appropriate alternatives.

The examples in earlier sections were designed to illustrate the flow of data from input form to output page, but neither the html or the data transformations have been very complicated. A more elaborate situation is ordering pizza online, and recording the orders for the restaurant owner. You can try <http://localhost:8080/pizza1.cgi> several times and look at the supporting example `www` files `pizza1.cgi`, `pizzaOrderTemplate1.html`, and the simple `pizzaReportTemplate.html`. To see the report, the owner needs to know the special name `owner777`. After ordering several pizzas, enter that name and press the Submit button again.

This CGI script gets used in two ways by a regular user: initially, when there is no order, and later to confirm an order that has been submitted. The two situations use different logic, and the script must distinguish what is the current use. A *hidden variable* is used to distinguish the two cases: when `pizza1.cgi` is called directly (not from a form), there is no `pastState` field. On the other hand the `pizzaOrderTemplate1.html` includes a hidden field named `pastState`, which is set to the value 'order'. (You can confirm this by examining the end of the page in Kompozer's source mode.) The CGI script checks the value of the field `pastState`, and varies its behavior based on whether the value is 'order' or not.

The form in `pizzaOrderTemplate1.html` has radio buttons and check boxes hard coded into it for the options, and copies of the data are in `pizza1.cgi`. Keeping multiple active copies of data is not a good idea: They can get out of sync. If you look at the source code for `pizzaOrderTemplate1.html`, you see that all the entries for the radio button and check box lines are in a similar form. In the better version with altered files `pizza.cgi` and `pizzaOrderTemplate.html` (that appears the same to the user), the basic data for the pizza options is only in one place in `pizza.cgi`, and the proper number of lines of radio buttons and check boxes with the right data are generated *dynamically*. To do the dynamic generation, templates for an individual html line with a size radio button is in the source code, and it is used repeatedly to generate multiple lines, each with a different size and price embedded into the format string from the program data. These lines are joined together and placed as one entity into the html form template. A similar procedure is done with the toppings and check-boxes.

The logic of using the hidden input field is further outlined in [HTML Source Markup](#) (page 197).

A further possible elaboration would be to also allow the restaurant manager to edit the size, cost and available topping data online, and store the data in a file rather than having the data hard coded in `pizza.cgi`, so if the manager runs out of a topping, she can remove it from the order form. This change would be a fairly elaborate project compared to the earlier exercises!

4.5 Summary

1. The Overall Process for Creating Dynamic Web Pages

Making dynamic web pages has a number of steps. I have suggested several ways of decoupling the parts, so you can alter the order, but if you are starting from nothing, you might follow the following sequence:

- (a) Determine the inputs you want to work with and make a web form that makes it easy and obvious for the user to provide the data. You may initially want to have the form's action URL be `dumpcgi.cgi`, so you can debug the form separately. Test with the local server. When everything seems OK, *make sure to change the action URL to be the name of the CGI script you are writing*. [*Editing HTML Forms* (page 180)]
- (b) It is easier to debug a regular Python program totally inside Idle than to mix the Idle editor and server execution. Particularly if the generation of output data is going to be complicated or there are lots of places you are planning to insert data into an output template, I suggest you write the `processInput` function with its output template first and test it *without* a server, as we did with `additionWeb.py`, providing either canned input in the main program, or taking input data from the keyboard, and saving the output page to a local file that you examine in your webbrowser. [*Dynamically Created Static Local Pages from Python* (page 168)]
- (c) When you are confident about your `processInput` function, put it in a program with the proper cgi skeleton, and add the necessary lines at the beginning of the `main` function to take all the CGI script input from the browser data. Include all the variable names you need in the actual parameter list for calling `processInput`. They should match up with the formal parameters you wrote earlier for the definition of `processInput`. [*adder.cgi* (page 175)]
- (d) Be sure to check for syntax errors in Idle, by using the menu sequence *Run -> Check Module*. Fix as necessary.
- (e) Remember to run `CGIfix.py` in the same folder as a precaution to clean things up, particularly with a new `.cgi` file on a Mac.
- (f) Finally test the whole thing with the local server. Make sure the local server is running, and all the resources that you refer to are in the same folder as the local web server: Initial web page, web page templates, CGI script. Do not open the starting web page or CGI script in Idle or by finding it in your file system. You must run it in your browser with a URL that starts with `http://localhost:8080/`. In error, if you load a web page directly from your file system, it will not cause an obvious error - the dynamic actions will just not take place.
- (g) If it does not work right:
 - If you get a page that uses your template, but it looks wrong, either fix your template or look for a logical error in your program. (If you had tested your `processInput` function in a regular Python program before, this should not happen.)
 - If the web page output shows an error description, see if you can pick any help out and go back and fix your code.
 - If you get nothing back in your web browser, make sure you had tested the final version of the code in Idle for syntax errors (*Run -> Check Module*), and that you have the final error catching code in the CGI script, and that you used a URL that starts with `http://localhost:8080/`.
 - If all of the parts mentioned above are there, the problem may show in the server, not Python. Look in the local server window's log output, and see if it points to a filename that it cannot find or

2. Markup: Plain text may be *marked up* to include formatting. The formatting may be easily interpreted only by a computer, or it may be more human readable. One form of human-readable markup is hypertext markup language (HTML). [*Format of Web Page Markup* (page 166)]

- (a) HTML markup involves tags enclosed in angle braces. Ending tags start with '/'. For instance `<title>Computer Science</title>`.

Tags may be modified with attributes specified similar to Python string assignments, for example the text input field tag,

```
<input value="red" name="color" type="radio">
```

- (b) Modern editors allow HTML to be edited much like in a word processor. Two views of the data are useful: the formatted view and the source view, showing the raw HTML markup.
3. Python and HTML: Since HTML is just a text string, it can easily be manipulated in Python, and read and written to text files. [[Dynamically Created Static Local Pages from Python](#) (page 168)]
 4. The `webbrowser` module has a function `open`, that will open a file or web URL in your default browser: [[Dynamically Created Static Local Pages from Python](#) (page 168)]

```
webbrowser.open(filename)
```

5. Common Gateway Interface (CGI). The sequence of events for generating a dynamic web page via CGI: [[An Example in Operation](#) (page 173)]
 - (a) The data a user types is handled directly by the browser. It recognizes forms.
 - (b) The user presses a Submit button. An action is stored in the form saying what to do when the button is pressed.
 - (c) In the cases we consider in this tutorial, the action is given as a web resource, giving the location of a CGI script on some server. The browser sends the data that you entered to that web location.
 - (d) The server recognizes the page as an executable script, sees that it is a Python program, and executes it, using the data sent along from the browser form as input.
 - (e) The script runs, manipulates the input data into some results, and puts those results into the text of a web page that is the output of the program.
 - (f) The server captures this output from the program and send it back to the user's browser as a new page to display.
 - (g) The results appear in the user's browser.

6. The `cgi` Module

- (a) Create the object to process CGI input with [[adder.cgi](#) (page 175)]

```
form = cgi.FieldStorage()
```

- (b) Extract the first value specified by the browser with name `nameAttrib`, or use `default` if no such value exists [[adder.cgi](#) (page 175)]

```
variable = form.getfirst(nameAttrib, default)
```

- (c) Extract the list of all values specified by the browser associated with name `nameAttrib` [[More Advanced Examples](#) (page 182)]

```
listVariable = form.getlist(nameAttrib)
```

This case occurs if you have a number of checkboxes, all with the same name, but different values. The list may be empty.

7. Local Python Servers.

- (a) Python has a module for creating a local testing server that can handle static web pages and Python CGI scripts. [[An Example in Operation](#) (page 173)]

- (b) Different kinds of errors with CGI scripts are handled different ways by a local Python server. [*Errors in CGI Scripts* (page 178)]
- 8. A comparison of the various types of files used in web programming, listing the different ways to edit and use the files, is given in *Editing and Testing Different Document Formats* (page 168).

APPENDICES

5.1 Using Error Messages


You can expect to make some errors while coding. Idle provides information about the location and type of errors in several ways, depending on the kind of error. To be most useful, you want to be able to decode the error feedback.

Idle developers keep updating error messages to make them more useful. The versions shown below are for Python 3.8.

To illustrate, I start from a file that is purposefully incorrect, example program BADexamplecode.py, to show off debugging ideas:

```
x = input("Enter a number")
y = x + 10
print('10 more is {}'.format(y)
print('Now we are done!)
```

I also have an initial documentation line, followed by lots of blank lines, so the popup window shown below does not obscure any code. If I try to run this code, I get



A pop-up Invalid Syntax window indicates the **syntax error** was found by the interpreter in just trying to read the program - never getting to execution. *After* you click on OK, the popup window goes away, and Idle highlights where it detected that there was an error: You should see the “p” at the beginning of the last line with a pink background highlight.

You should know that print statements are perfectly legal. There does not seem to be an issue with the word print. Note carefully what I said earlier: This is where the interpreter *first noticed* there was an error: The actual error could be earlier - it just was not clear that there was one yet. The most common earlier place is the previous line, and I illustrated the most common such error. The interpreter did not find an error on the previous line because it did not

realize it was at the end of a statement. When can a statement go on to the next line? - When there are unmatched grouping characters, most commonly ().

It is very easy to have unmatched parentheses, particularly when there are many levels of pairs of parentheses. Recall that when you type in Idle it shows you what closing parentheses match with. Here is the image just after I added the correct final) at the end of the previous line:

```
x = input("Enter a number")
y = x + 10
print('10 more is {}'.format(y))
print('Now we are done!')
```


I did not show the progress in entering this program with its error, but Idle would have given a clue. If we back up to when the first incorrect print line was entered, right after the enter key is pressed, you would see

```
x = input("Enter a number")
y = x + 10
print('10 more is {}'.format(y)
|
```

Note where the vertical bar cursor (|) jumped to: not the beginning of the next line, where you would put the next statement. If you look where it is positioned relative to the previous line, it is just after the unmatched opening parenthesis! This is Idle's convention, so if you are paying attention to the automatic cursor indent, you should realize there was an error with unmatched delimiters.

Note that Idle also should give you warning of the opposite error: If you add an excess close-parenthesis, you should hear a beep, indicating it was not expecting that character.

So now assume we have done this correction to the program, adding the closing parenthesis. If we try to run again:



Another syntax error, this time at the end of the last line, and with more information about the error. EOL stands for “End Of Line”, so it got all the way to the end of the line reading a string literal. The coloring also indicates this: green all the way to the end of the line. What does a string literal need at the end? - A final matching quote character! And we need a closing parenthesis, remembering our previous error. Suppose I complete the line as

```
print('Now we are done!')
```



I can now try to run again. This time we do not get a pop-up syntax error window. This means the interpreter did not find any errors *reading* the program. Many errors are only found when running the program, so execution starts in the shell, leading to a **run-time error**. The program first prompts for a number, and I enter 100:

```
Enter a number100
Traceback (most recent call last):
  File "/Users/anh/handsonpython/examples/BADexamplecodeFIXED.py", line 7, in <module>
    y = x + 10
TypeError: can only concatenate str (not "int") to str
```

We see a red **error traceback**. We will discuss its various parts. It shows the program line

```
y = x + 10
```

In this little short program, it is easy to go back to the Python source and locate the line. Idle also gives you help with this in general: The next screen shows me right-clicking the mouse (or control-click on a Mac) on top of the red “line 14”, where it is saying the error is. This generates a pop-up window.



The screenshot shows the same traceback as before. A right-click context menu is open over the line number '14' in the traceback. The menu options are 'Cut', 'Copy', 'Paste', and 'Go to file/line'. The 'Go to file/line' option is highlighted.

```
Enter a number100
Traceback (most recent call last):
  File "/Users/anh/www/150/online/examples/readingErrorMessages.py", line 14, in <module>
    y = x + 10
TypeError: Can't convert 'int' object to str implicitly
>>>
```

The only allowed option is to select **Go to file/line**



A close-up of the context menu from the previous screenshot. The 'Go to file/line' option is now highlighted in blue, indicating it has been selected.

and then the focus jumps to the window with the source code, and highlights the desired line:

So we have the line with the execution error. We still need to figure out what is going on. The bottom line of the red traceback gave a description of the error:

TypeError: can only concatenate str (not “int”) to str

Think. You could start by considering the implications of “concatenate”, or, since it is a type error, you could look for the types it refers to. Let us start by looking at the types. It refers to an int. Clearly we have 10. There is something about a string. The other data is `x`. What is its type? Of course the prompt in the previous line asks for a number, but what type is returned by the input function? – always a string! Look at the expression again `x + 10` – a string, plus-sign, and a number – a plus-sign after a string means concatenation, not numeric addition. As the error says, you can only concatenate onto the first string with another string, not an `int`.

We want numeric addition, so we need two numbers, and the string must be explicitly converted. You might need to look that up, but you have an idea what you are looking for: we can use `int` as a function to convert the string. We do not need to add an extra line – we can make `x` start off as an `int`, changing the first line to

```
x = input("Enter a number")
y = x + 10
print('10 more is {}'.format(y))
print('Now we are done!')
```

```
x = int(input("Enter a number"))
```

Note that the error was suggesting a fix that you do not want: ending up with string concatenation. When something does not make sense, the interpreter does not know what you mean. It tries to make a suggestion that is *likely* to be helpful, though in this case it is wrong. At least in this case it was suggesting something you should understand already.

We can go a bit further in this case: Though running the original first line by itself did not cause an error, looking at the output above, you can see it is ugly, with the prompt running into the user response. This is a **logical error**. It is easy to correct, changing the ending of the first line prompt so we have

```
x = int(input("Enter a number: "))
y = x + 10
print('10 more is {}'.format(y))
print('Now we are done!')
```

Now run again:

```
Enter a number: 100
10 more is 110
Now we are done!
>>>
```

One final logical error is the close-parenthesis in this output. When debugging, I added a required final quote character on the last line, but I left an extra close-parenthesis. In “fixing” the last line earlier, I added another error. I am illustrating that this is unfortunately easy to do! Final code:

```
x = int(input("Enter a number: "))
y = x + 10
print('10 more is {}'.format(y))
print('Now we are done!')
```

Final run:

```
Enter a number: 100
10 more is 110
Now we are done!
>>>
```

So we have illustrated all three kinds of errors:

- Syntax errors detected with a pop-up window in Idle before the program executes;
- Run time errors causing a red traceback sequence in the Shell output;
- Logical errors that Python does not find, but we need to note and troubleshoot in the source code when the results are not what we want.

I chose common simple errors, so hopefully you would have been able to figure out the meaning of the error message. That is a *lot* to expect in general. We are only gradually adding explanations of bits of Python syntax. You can easily make an error that the Python interpreter guesses as being based on a more advanced feature, so the error message makes no sense to you.

Even if you do not understand the error message, you should get the information about where the error occurred. Hopefully a concentrated look there will lead to you seeing the error and being able to correct it.

If you did not understand the original error message, then there is a further useful step after you *do* figure it out (with or without outside help): **Go back and consider the error message again.** After seeing what was actually wrong, the error message may make sense now, AND that knowledge may be useful to speed up your understanding and your fix the next time you see that error message.

Particularly as a beginner, you can still hit a brick wall some of the time, even with a partner. You are also in a course with an instructor: that is a major reason I am here. Ask for help if considering the information provided by Idle, plus a little thought, are not enough!

5.1.1 Nested Calls in Traceback

In the previous example program, the execution error occurred outside of any function call. There are further useful features in an error traceback, when there are errors inside function calls.

We illustrate, showing the output, with error traceback, for a silly example program, `showtraceback.py`:

```
'''Program with intended error to demonstrate traceback from nested call'''

def invminus4(x):
    return 1.0/(x-4)

def main():
    print('This program is INTENDED to cause an execution error.')
    print('Ok call to invminus4(6) next:')
    print(invminus4(6))
    print('Bad call invminus4(4) next:')
    print(invminus4(4))
    print("Won't get to here!")


main()
```

Note that the first call to `invminus4`, with parameter 6, is fine: $1.0/(6-4) = 0.5$. In the execution of the call `invminus4(4)`, we get an error traceback message. The image below comes after the traceback is displayed, and then just as the user uses the mouse to select the line where the error was:

Note that after the title line in the traceback there are three indented lines starting with “File”, not just one line as in the earlier program. The bottom File line shows the line where the error occurred, and we could jump to the source, continuing from the step in the previous image:

The error takes place in a function, and a function can be called in many places with different parameters. The further up lines in the traceback show the **chain of function calls** to reach that occurrence of the error. The program calls `main` in the bottom line of the program (line 13, first File line reference), and then `main` calls `invminus4` twice. We can tell *which* call caused the error, since the traceback shows the call to `invminus4` at line 10. If you had any question of the context for any of the nested calls leading to the error, you could also select a previous File line with the mouse, and jump to the calling line in the source.

```
This program is INTENDED to cause an execution error.
Ok call to invminus4(6) next:
0.5
Bad call invminus4(4) next:
Traceback (most recent call last):
  File "/Users/anh/150dev/debugNotes/showtraceback.py", line 14, in <module>
    main()
  File "/Users/anh/150dev/debugNotes/showtraceback.py", line 11, in main
    print(invminus4(4))
  File "/Users/anh/150dev/debugNotes/showtraceback.py", line 10, in invminus4
    return 1.0/(x-4)
ZeroDivisionError: float division by zero
>>> |
```



```
'''Program with intended error to demonstrate traceback from nested call'''

def invminus4(x):
    return 1.0/(x-4)

def main():
    print('ok call to invminus4 next:')
    print(invminus4(6))
    print('bad call to invminus4 next:')
    print(invminus4(4))
    print("Won't get to here!")

main()
```

5.2 Some Special Windows Instructions

While the Python language changes slowly, operating systems and setup methods change more rapidly with succeeding versions. The attempt here is to keep all such information in one place for the Windows operating system. It may become out of date at any time.

– Last checked this on Windows 10 and Windows 7 with Python 3.7.

5.2.1 Versions

I will use Python 3.8+ to mean the current version of Python, with version number at least 3.8.1. Make sure you have the latest recommended version installed from <https://www.python.org/downloads/>. Download the Windows version. *Read this section before doing any installation.* In particular note paragraph below with italics in it.

If the only option is to save it, agree, and find it in your download folder and double click to execute it. If you have an option to immediately run on download, you can choose that.

You are likely to get a security message before running. Click Run.

Pay attention: *before clicking on Install Now*, note if there are check-boxes at the bottom of a window you see. Make sure *both* are checked, about the Python Launcher AND to add Python to environment variables.

The final screen that you reach in the installation links to more advanced references than we will want in this course, so probably skip them for now.

Python now behaves differently if you installed a previous version before (like me). I could have missed something for someone installing Python for the first time. Feel free for me to watch you while you share your screen in Zoom.

If you install Python *without* putting a check mark on Add Python to environment variables, then you can go back and fix it. This is important for Ch 4:

1. Run the Python installation script again. Since python is already there it looks different when it starts - the first option is modify; click on that.
2. Just click Next on the second screen
3. On the following screen is where you make a change: Click to put a checkmark in front of the line saying:

Add Python to environment variables.

Then click next/continue/finish - whatever to just advance to the end.

You are encouraged to test if Python did get added to the environment by starting Idle as discussed on the next section.

5.2.2 Starting Idle Shortcut

If you want to start Idle without a starting file, but later deal with files in the examples folder, then a one-step shortcut is to double click on the file `IdleOnWindows.cmd` in the examples folder. If this does not work (in Windows), then go back and modify your Python installation, as discussed in the previous section.

If you want to do extensive Idle work in another folder, you can copy `IdleOnWindows.cmd` to there and use it.

5.2.3 File Names in the File Explorer

By default Windows does not display file extensions in File Explorer Windows. You may have multiple files with the same base name but different extensions. Particularly if you want to attach one to an email or homework submission, this can lead to problems.

You are strongly suggested to change the viewing default in File Explorer to show extensions.

5.2.4 Chapter 4 CGI Instructions

You can skip this until you are starting Chapter 4.4 on CGI files.

Opening .cgi Files in Idle

By convention the server programs that you will be writing end in ".cgi". That is not an extension that is automatically associated with Idle for editing. If you want to open a .cgi file (or any other type but .py) to edit (and never run) from inside of Idle, it is possible to do this directly in many steps, but it is easier to go indirectly:

- Start a .py file you have in Idle (like localCGIServer.py), or if IdleOnWindows.cmd is there, as in my www folder, use it to start Idle.
- To open a .cgi file from *inside* Idle, you select Open from the File menu like normally, but then notice the drop-down choice in the lower right of the file open window that probably shows Python files (.py): *Change this file filter to All files (*.*)*.
- Then all files in the current folder should be listed, not grayed out, and you can navigate to and choose the one you want.

Saving a new .cgi file

As with opening a .cgi file, set the format filter at the bottom of the dialog window to All files (.). Then enter the full file name with the .cgi. If you forget and do not change the file filter, a ".py" will be added to your file name. Then you can rename it in File Explorer.

Running CGI Scripts

If you insist on doing cgi work in a different folder, copy both startServer.cmd and localCGIServer.py as well as all related .html and .cgi files to that folder, and then when you want to test your work, start the local server from *there* with startServer.cmd.

At this point you can do all the web server based activities in Chapter 4. There are a number of steps: be sure you carefully go through the list in the tutorial. Remember, html files calling a cgi file, and cgi files used directly are *only* run in your web browser with a URL starting with localhost:8080/, and only *after* you have a local server running from the *same* folder. Otherwise nothing dynamic happens.

5.3 Some Special Mac Instructions

While the Python language changes slowly, operating systems and setup methods change more rapidly with succeeding versions. The attempt here is to keep all such information in one place for the Mac OS-X operating system. It may become out of date at any time.

I will assume a version of Max OSX of at least High Sierra (10.13 or later). Upgrades are free.

5.3.1 Versions

I will use Python 3.8+ to mean the current version of Python, with version number at least 3.8.1. Make sure you have the latest recommended version installed from <https://www.python.org/downloads/>. Download the pkg file and double click to execute.

5.3.2 Editing by Default in Idle

You will be working mostly with files ending in .py – Python source files. Most of the time you will be editing them and running them in IDLE, so the best default behavior when opening a file with extension .py is to have it open in Idle 3.8+. If you can double click on a .py file in my examples, and Idle opens as soon as you have installed Python 3.8+, great - you should skip the rest of this section.

If Idle did not open, here is how to change the default behavior:

1. In the Finder go to a file in my examples folder with the .py extension. and right click or control click on it. Select **Get Info**.
2. In the Info window that pops up, In the drop-down menu for **Open with:**, you want to see **IDLE.app** on the top line (meaning it is already the default). You may possibly also see the version listed if you have several. Presumably you are going through this because you do *not* see IDLE.app there.
3. You may see **IDLE.app** lower down in the list of options. Then select it there.
4. If you did not see IDLE.app in the drop-down list at all:
 - Select **Other...**
 - A window of apps pops up. Toward the bottom is a check box for “Always Open With”. Check it.
 - If you do not see a Python folder in the list, just below the bottom of the page change Recommended Applications to All Applications
 - Now you should see a Python 3.8 folder. Open it and select Idle.app.
5. The Info window should become active again. Be sure that now under **Open with:** you see IDLE.app.
6. Under the IDLE.app you should see a button, **Change All...** So that you never have to go through all these steps again, be sure to click that button. A confirmation window will pop up. Select Continue.
7. Now you can close the Info window, and you should be able to open all .py files directly in Idle for editing by double clicking in the Finder!
8. Then if you should happen to want to directly run a Python file from the Finder window, you will need to select the file with control-click or right-click and select the latest Python Launcher for Python 3.

5.3.3 Running Graphics (Chapter 2)

The graphics window likely comes up behind an unneeded Console Window. You can close the console window, and click on the graphics window title bar to bring it to the front.

5.3.4 Chapter 4 CGI Instructions

Opening .cgi Files in Idle

By convention the server programs that you will be writing end in “.cgi”. That is not an extension that is automatically associated with Idle for editing. You will want to change the association. Do it the same way as the instructions above

for getting .py files to open in Idle by default, except choose a .cgi file in my www folder, and go through the same procedure.

Setup: Making CGI Scripts Executable

A complication on a Mac, like any Unix derived system, is that programs that you run must be explicitly marked *executable*. (On Windows it follows from the file extension, like .exe.) The examples/www folder may not have the cgi files marked executable (nor have several other technical things right).

The example program examples/www/CGIfix.py is used to give direct Unix/Mac/Linux executability to CGI files for Chapter 4.

In the finder open your www directory. You can open CGIfix.py in Idle and run it. Note the comment that the file cgiServerScript was created. This is used to launch the local server.

Important! Particularly if you later copy in a CGI script from a Windows machine, or if you *create any new cgi script* in the www directory, make sure it becomes executable (and possibly fix some other technical things) by launching CGIfix.py again.

If you forget this, and the file is not executable, nothing happens in the browser when you try to run it, and the error message in the server window is very unhelpful - it says "... File not found ...". Make sure you make new CGI files executable (with CGIfix.py)! Running it extra times does not hurt.

5.3.5 Terminal Use (Optional)

To use the Hands-on Python Tutorial, the information above should be sufficient to get your Mac usage going. Terminals are quite useful in other contexts: There are many things that can be done from such a window that cannot be done from the Finder or with an App.

If you would like a bit more background, read on.

Navigation

OS X and Unix (from which OS X is derived) have a concept of the *current directory*. Directory is the older term for folder from when there were not pictures of folders in a graphical interface.

You start in your home directory. My login id is anh, so my home directory is /Users/anh. Substitute your login id for your machine. The slashes separate nested directories. The top hard drive directory is /, which contains the directory Users which contains users' home directories, like my anh. A shorthand in a terminal for your home directory is ~.

The terminal shows a system prompt when it is ready for user input. The prompt can be set to show many things. The end of the prompt is often \$. Before that is often some indication of your current directory, like ~ for the home directory.

If you want to see the full name of the current directory enter the command

```
pwd
```

Single commands are executed after you press the Enter key.

You can list the contents of a directory with the ls command. Unix tends to abbreviate words in commands.

If you use the ls command in your home directory, you should see Desktop, Documents, Downloads, ... listed.

To **change** directory, use the cd command followed by the directory you would like to change to. You can use the full name of the directory starting with /, but more commonly you just indicate where to go relative to where you are now. Desktop is a subdirectory of your home directory, so from the home directory you can just enter


```
cd Desktop
```

Here is a sequence on my computer after starting a terminal (skipping most of the output from `ls`)

```
Last login: Sat May 19 18:03:19 on ttys001
```

```
anh@lucky13 (anh@lucky13):~$ pwd
```

```
/Users/anh
```

```
anh@lucky13 (anh@lucky13):~$ ls
```

```
...
```

```
Desktop ...
```

```
Documents ...
```

```
Downloads ...
```

```
...
```

```
anh@lucky13 (anh@lucky13):~$ cd Desktop
```

```
anh@lucky13 (anh@lucky13):~/Desktop$ pwd
```

```
/Users/anh/Desktop
```

```
anh@lucky13 (anh@lucky13):~/Desktop$ cd ..
```

```
anh@lucky13 (anh@lucky13):~$ pwd
```

```
/Users/anh
```

```
anh@lucky13 (anh@lucky13):~$
```

Notice that the last use of the `cd` command used directory `..`. That stands for the parent directory, the directory containing the current directory.

If you unzipped `examples.zip` from your Desktop, you can go to the examples with

```
cd ~/Desktop/examples
```

Alter this if you put your examples somewhere else!

It is useful to be in the examples folder. If you start Idle from there, it is easy to open any of the example programs.

When scripts are directly called by the operating system, they look for the proper interpreter to read them. Our scripts are set up to look for `python3`.

To start a regular python program from the current directory, like `hello_you.py`, you would enter a command with `python3` and the file name, like

```
python3 hello_you.py
```

Instead of shifting to a separate Shell as in Idle, the output appears right in the terminal window.

5.4 HTML Source Markup

The section [Web page Basics](#) (page 166) compares HTML format with other document formats. Here we concentrate on HTML: Hypertext Markup Language.

I use a convenient plain text editor, Sublime Text (free download at <https://www.sublimetext.com/3>) that colors the syntax of html source, much as Idle colors Python syntax. This is an *advantage* over Kompozer.

Unlike hybrid editors such as Kompozer, the editor only shows the raw HTML text, not the way it looks in a browser. With a plain text editor like this, you have a couple extra steps to look at the formatted view: You need to save the file, and separately load it into a browser. If you make a change to the html source, and want to see what that changes in the browser view, then you need to save the source file again, and then get the browser to *reload* the page.

Mac users – TextEdit: You can also edit raw html with the included Mac app TextEdit, but with several steps to *change* the defaults. (The initial defaults are to show *no* html source.) Since TextEdit does not do syntax coloring, an editor like Sublime Text is likely better, as long as you do not mind doing one extra download.

If you *do* want to use TextEdit to see and edit html source:

1. Open TextEdit,
2. Click on Help in the menu bar
3. Select *TextEdit help page*
4. In the list that pops up, select “Work with HTML documents”.
5. Follow the instructions in the section “Always open HTML files in code-editing mode”.
6. As a beginner, I suggest these settings in the last help section, “Change how HTML files are saved”:
 - In 2. select the CCS style “No CSS”. Leave the defaults for document type and encoding.
 - In 3. do *not* select preserve white space.

Now, for everyone, we get into the first simple example, the raw html for `hello.html`. This file is in the examples sub-folder `www`.

```
1 <!DOCTYPE html PUBLIC "-//W3C//DTD HTML 4.01 Transitional//EN">
2 <html>
3   <head>
4     <title>Hello</title>
5   </head>
6
7   <body>
8     <h1>A Simple Page</h1>
9     Hello,
10    world! <br>
11    It is a fine day.
12   </body>
13 </html>
```

You are encouraged to open it both in a plain text editor like Sublime Text or Mac TextEdit and in a browser. The other HTML files discussed here, are in the same folder, and you are encouraged to open them in the same two ways.

With the html source text coloring in this tutorial. the only text that you will see in a browser’s usual formatted view is what appears as black in the image. Everything else is markup. Markup tag names are boldface, and colored dark blue. Most of the markup appears inside angle brackets, and most markup has both an opening and a closing tag, with affected contents in between, like `<title>` and `</title>` in line 4. The closing tag has a `/` right after the `<`.

Much of the markup is boilerplate - I am not going to explain it much.

In particular all the part through the opening tag for the body, `<body>`, in lines 1-7 is standard for our very simple pages, except for the bit in black, inside the title markup, on line 4. The title text appears in the *tab label* in your browser, *not* inside the formatted page that appears in the browser.

The only parts you actually see on the page are inside the body: here the body contents are in lines 8-11.

You are likely to want to start with a heading. Line 8 uses the `<h1>` markup to create a main heading.

I spaced the text in the body in a strange way, to illustrate a major feature of html: It reformats if you change the window width. That means the browser generally *chooses the places to wrap* to the next line. In particular *any amount of white space*, including newlines in your raw text, are merely treated as a place where *there could be a break to the next line*, or it could just display as a *single* space before the next word.

Unless you have an extremely narrow window where you display `hello.html` in your browser, you should see “Hello, world!” all on one line. That means the newline after “Hello,” in the source text and the blanks before “world”, just turn into a single space when displayed.

Sometimes you want an explicit line break, that shows in the browser. The `
` markup forces a line break. (There are much more flexible ways to break to a new line, like using the paragraph tag, `<p>`, but we are keeping things simple here.)

In `hello.html`, that means that no matter how wide your browser window is, you will always see “It is a fine day.” starting on a line *after* “Hello, world!”, because of the `
` on line 10.

This compression of white space also means that I can indent to help me keep track of multi-line contents between opening and closing markup, and this does not change the html formatting.

The final two lines 12-13 are also standard boilerplate, closing the tags that were started earlier for the body and the entire html section.

There is plenty more formatting markup for fonts, text size, paragraphs, ... that is not discussed here. Common document editors like Microsoft Word and Open Office *do* allow you to generate static html files. However the source html text is NOT visible through these editors, and they all add lots of extra detailed formatting information in the html source that greatly lengthens the file and obscures the text that you do add. Also, such editors cannot handle html *forms*.

For the exercises, I am expecting a pattern with output page templates. The templates are just static html files (that later get modified by the string format operation inside your Python program).

An example is the output template for the adder programs: the initial testing program `additionWeb.py` and the later cgi server program `adder.cgi`. The template file is `additionTemplate.html` in the `www examples` folder:

```

1  <!DOCTYPE html PUBLIC "-//W3C//DTD HTML 4.01 Transitional//EN">
2  <html>
3      <head>
4          <title>Addition Answer</title>
5      </head>
6
7      <body>
8
9          <h1>Addition Answer</h1>
10
11          The result is: <br>
12          {num1} + {num2} = {total}
13
14      </body>
15 </html>

```

The text that is *not* inside tags is what you will see *if* this page is displayed directly in a browser, including the formatting instructions in curly braces.

The Python adder programs do not display this page directly. Instead they use it as a format string, so the substitutions into the curly braces are made before the page is displayed.

5.4.1 Special characters

We had markup in Python string literal notation for special characters. For the strings the markup all started with the backslash character, so ‘`\n`’ is a newline, ‘`\\`’ is a displayed backslash

In html `<` and `>` have special meaning, so if we want to *see* those symbols in the browser, we need a special substitute for the individual characters in the raw html. Those substitutes start with an ampersand (&) and end with a semicolon (;), with an abbreviation in between:

- < is replaced by <
- > is replaced by >
- & is replaced by &

Since & now is used specially for character markup, we need the & to *display* an ampersand in the browser.

The collapsing of whitespace sequences is a feature of html. If you really want more spaces in sequence, you can use a character that looks like a space, but is not considered as whitespace by the html formatter. The character markup is abbreviating Non-Breaking SPace.

You can put arbitrary text, possibly with some special character codes, *outside* of tags, and it will be displayed for the user to see in a browser.

5.4.2 HTML Form Markup

For a page that is totally static, or just displaying output from a server cgi program, you do not need form syntax. However if you want the user to input data into a cgi program from a web page, then you need a form. Static document generation apps are no use here!

First we introduce the basic syntax needed for the exercises. *More Advanced Form Input Tags (optional)* (page 201) introduces further features that might be useful in a more elaborate project.

Here is `adder.html`, from the examples sub-folder `www`:

```
1  <!DOCTYPE HTML PUBLIC "-//W3C//DTD HTML 4.01 Transitional//EN">
2  <html>
3
4      <head>
5          <title>Adder</title>
6      </head>
7
8      <body>
9          <h1>Fantastic Adder - Sum Two Numbers</h1>
10
11         <form action="adder.cgi" method="get" enctype="multipart/form-data">
12
13             Number 1: <input name="x" value="0" maxlength="60" size="60">
14             <br> <br>
15             Number 2: <input name="y" value="0" maxlength="60" size="60">
16             <br> <br>
17             <input value="Find Sum" type="submit">
18
19         </form>
20     </body>
21 </html>
```

This page includes a simple form, lines 11-19.

A form can only appear nested inside the body. Input tags can only appear inside the form.

Unlike the opening markup for tags introduced so far, input tags include not only the tag name, but also *attributes* are inside the angle brackets after the tag.

This is illustrated in line 11 for the form, with syntax coloring, with attribute assignments in light blue.

Attributes have a standard format, with an attribute identifier and an equal sign and a double-quoted string. Attribute assignments are separated by whitespace.

In line 11 the form attributes are **action**, **method** and **enctype**. We will not edit the attribute identifiers. The only things inside the opening tags that we will edit for new examples are the *contents of some of the quoted strings*. This

way it is not important in this course for you to learn a bunch of html syntax. You can copy models, and modify just data in quoted strings.

The syntax for an attribute looks like a Python assignment statement, with the string on the right being the value assigned to the attribute.

A form requires a further markup tag inside of it: `input`.

Some confusion is possible here from the fact **value** is also the name of a required attribute for a `input` tag, and all attributes have a string assigned as their value. I will try to use the phrase “string value” consistently for the second usage, and I will try to show the attribute names in boldface, so **value** refers to the attribute name used inside an `input` tag. Or I will show a full attribute assignment like `value="0"`.

The one form attribute that is important to modify correctly is the **action** attribute. Its string value should be the server program that will act on the data coming from the inputs in the form. In this case that is `adder.cgi`. Be sure you update this field when you copy to modify for a new page!

The generic `input` tags used to get data in a form are like in lines 13 and 15. `input` tags do not have a closing tag. They typically have a separate label as part of the web page’s displayed text, like “Number 1:” and “Number 2:”. The browser shows a box for the user input.

The important `input` attributes for us here are **name** and **value**.

The initial **value** attribute string is what the user sees inside the input box when the page is first displayed. When the user changes the text in the box, it is remembered as a replacement **value** attribute’s string, to be later passed on to the `cgi` program.

In order for the `cgi` program to know which **value** is which, the **name** attribute is used. In `cgi` programs the form accessing methods like `getfirst` must have the first parameter match *the quoted string in the associated name attribute in the form*. For example, in a `cgi` file, the method call `form.getfirst('x')` makes sense *only* if there is an `input` tag in the html form page with attribute `name="x"` (as we have in `adder.html`).

Forms can have any number of input fields like these, distinguished in the `cgi` script by their **name** attribute.

A form must always have exactly one special input tag like in line 17: The attributes here are somewhat different: **value** and **type**. The **type** attribute must be assigned the string `"submit"`. With this **type**, the **value** attribute’s string does not appear in a user-editable input box. Instead it is the label text on the *submit button*. When the user clicks on that button, the browser immediately sends all the form’s input to the `cgi` program given in the form’s **action** attribute. Then the next page viewed in the browser is the one produced by the `cgi` program....

This is all you really need if you just are going to get user data from text input fields, as in the Chapter 4 exercises. Between your form’s starting and ending tag, you can have any number of input tags with different **name** attributes values to record user text. You must have exactly one input tag in the form with `type="submit"`.

5.4.3 More Advanced Form Input Tags (optional)

You have probably seen other input and display mechanisms on web pages, like radio buttons and check boxes.

You can see an example by running the `pizza1.cgi` URL in the optional Tutorial section ref: *More-Advanced-Examples*.

The form here is created in the `cgi` program from a template page, `pizzaOrderTemplate1.html` in the examples sub-folder `www`, which shows the syntax that you can copy for input tags where the **type** attribute has string value “checkbox”, “radio”, or “hidden”:

```

1 <!DOCTYPE html PUBLIC "-//W3C//DTD HTML 4.01 Transitional//EN">
2 <html>
3
4     <head>
5         <title>Andy's Pizza</title>
6     </head>

```

```

7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
<body>

    <h1>Andy's Pizza</h1>
    
    <h2>Online Ordering</h2>
    {msg} <br>
    {invitation} <br>

    <form action="pizzal.cgi">
        Your name <input name="client" value="{client}" maxlength="40" size="40"> <br><br>
        Select the size:<br>
        <input name="size" value="small" type="radio">
            Small: $5.50 plus $0.50 per topping<br>
        <input name="size" value="medium" type="radio">
            Medium: $7.85 plus $0.75 per topping<br>
        <input name="size" value="large" type="radio">
            Large: $10.50 plus $1.00 per topping<br>
        <br>
        Check desired toppings:<br>
        <input name="topping" value="pepperoni" type="checkbox">
            Pepperoni<br>
        <input name="topping" value="sausage" type="checkbox">
            Sausage<br>
        <input name="topping" value="onions" type="checkbox">
            Onions<br>
        <input name="topping" value="mushrooms" type="checkbox">
            Mushrooms<br>
        <input name="topping" value="extra cheese" type="checkbox">
            Extra cheese<br>
        <br>
        <input value="Submit Pizza Order" type="submit">
        <input name="pastState" value="{state}" type="hidden"><br>
    </form>
</body>
</html>

```

Radio buttons allow you to make a unique choice among multiple options in a group. If you click on one, and then another, the selection of the previous one is removed and the later one is noted instead. Lines 19, 21, and 23 show a group of radio buttons, with text after each one describing its meaning. They are radio buttons because of the attribute settings `type="radio"`. They form a group, because the **name** attribute's string value is the *same* for each. (In this case, `name="size"`). The **value** of the chosen one is passed to the cgi program. When the cgi program calls `form.getfirst('size')`, just the string assigned to the selected input's **value** attribute is returned. Here it would be 'small', 'medium' or 'large'.

If you want to allow multiple *simultaneous* selections from a group, use input tag attribute `type="checkbox"`, as in lines 27, 29, 31, 33, and 35. Other than this new string value for the **type** attribute, the syntax in this tag is like for radio buttons, with distinct assignments to the **value** attribute. In the cgi program, however, you access the data differently: Read the results of a group of check boxes with the `getlist` method, that returns a *list* of the values of checked checkboxes. For instance if the user of this form checks for sausage, onions, and extra cheese, `form.getlist('topping')` returns `['sausage', 'onions', 'extra cheese']`.

Finally, there is a major complication when wanting to go back and forth, running a sequence of cgi programs, displaying a sequence of forms in between to get further user input. Even if you are running the same cgi program each time, each call the the cgi program is *independent*: Nothing is automatically remembered from the previous call the the cgi program. If you want to remember things defined in a previous call to a cgi program, then the output of the earlier cgi program can have a form with one or more input fields with `type="hidden"`.

Here “input” is not referring to *user* input in the form: *Nothing about this tag is visible to the user of the form*. The input is input *into the following cgi program* from the the form. It can be read in the cgi program via its **value** attribute, like a regular text box input.

This syntax is pretty straightforward. Explaining its use in the cgi program `pizza1.cgi` is more involved:

1. The first time the cgi program is called directly with `http://localhost:8080/pizza1.cgi`. Then there was *not* a previous form feeding into it, so when this initial execution of the cgi program calls `form.getfirst('pastState', '')`, the default `''` is returned, indicating there was no earlier form,
2. After testing this value in an if-statement, the cgi program chooses to *create* the form for an order. Note the braces various places in `pizzaOrderTemplate1.html`: This is not a final html page. It is used as a format string to create a page. The cgi program creates its output, which is a form, substituting `'order'` for `{state}` in line 40. This form is created and sent back to the user's browser, so the hidden input field with `name="pastState"` has `value="order"`.
3. In the browser, the user fills in the fields in the order form. The user does *not* see the hidden input field, but it is there. The user submits the form back to `pizza1.cgi`, so `pizza1.cgi` executes a *second* time.
4. In the second execution of the cgi program, the call is made again: `form.getfirst('pastState', '')` and this time `'order'` is returned, since it was specified in the hidden field in the form. Hence the cgi program sees that there *was* a previous form. Then the cgi program goes through the code to read the order fields and process the data to return a response page.

There is a huge amount to learn about more elaborate HTML that we are omitting: All sort of formatting, form actions acted on within the browser via the programming language *javascript* (without server interaction), custom formatting rules via cascading style sheets (CSS),

What we have in this tutorial appendix is sufficient to have simple pages interact with a server.

genindex